
	'		
DESIGN INT. DATE REASON			
			STANDARDS
		201 05	CTANDARD CYUROL C. ARRESTATIONS AND DATTERNS
		001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
		001-04	TEMPORARY EROSION CONTROL SYSTEMS
	(001-04	PCC BASE COURSE WITH HMA BINDER AND SURFACE COURSES
		201-01	MAILBOX TURNOUT
		001-07	PAVEMENT JOINTS
[4240	001-05	CURB RAMPS FOR SIDEWALKS
	4820	001-02	HMA SHOULDER ADJACENT TO FLEXIBLE PAVEMENT
		006-03	HMA SHOULDER ADJACENT TO RIGID PAVEMENT
	4820	011-03	HMA SHLD STRIPS/SHLDS WITH RESURFACING OR
			WIDENING AND RESURFACING PROJECTS
	5423	101-01	PRECAST REINFORCED CONCRETE FLARED END SECTION
	5423	106-01	PRECAST REINFORCED CONCRETE ELLIPTICAL FLARED END SECTION
	5423	311	GRATING FOR CONCRETE FLARED END SECTION (FOR 600 MM (24") THRU 1300 MM (54") PIPE)
	5426	606	REINFORCED CONCRETE PIPE TEE
	6023	301-01	INLET - TYPE A
PLOTS & CHECKS	6023	306-01	INLET - TYPE B
INT. DATE NO. REASON	6024	101-01	MANHOLE TYPE A
	6024	106-02	MANHOLE TYPE A 6'-DIAMETER
	6026	501-01	PRECAST REINFORCED CONCRETE FLAT SLAB TOP
	6027	701-01	MANHOLES STEPS
	6040	001-02	FRAME AND LIDS TYPE 1
	6040	36-01	GRATE TYPE 8
	6040	091-01	FRAME AND GRATE TYPE 24
	6060	001-03	CONCRETE CURB TYPE B AND COMBINATION CONCRETE
			CURB AND GUTTER
	6061	01-03	TYPE A GUTTER (INLET, OUTLET AND ENTRANCE)
	6061	06-03	OUTLET TYPE 1 FOR TYPE A GUTTER
	6300	001-07	STEEL PLATE BEAM GUARDRAIL
	6302	201-05	PCC/HMA STABILIZATION AT STEEL PLATE
			BEAM GUARDRAIL
	6303	301-04	SHOULDER WIDENING FOR TYPE 1 SPECIAL
	6350	001	DELINEATORS
	6350	006-02	REFLECTOR AND TERMINAL MARKER PLACEMENT
	6350	011-01	REFLECTOR MARKER AND MOUNTING DETAIL
	6660	001	RIGHT-OF-WAY MARKERS
	6671	.01	PERMANENT SURVEY MARKERS
	7010	06-02	OFF ROAD OPERATIONS, 2L. 2W, 4.5 M (15') TO 600 MM (24") FROM PAVEMENT EDGE
	7012	01-02	LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS >= 45 MPH
	7013	06-01	LANE CLOSURE 2L, 2W, SLOW MOVING OPERATIONS - DAY ONLY FOR SPEEDS >= 45 MPH
	7013	11-02	LANE CLOSURE 2L, 2W, MOVING OPERATIONS - DAY ONLY
	7013	26-02	LANE CLOSURE 2L, 2W, PAVEMENT WIDENING FOR SPEEDS >= 45 MPH
	7013	31-02	LANE CLOSURE, 2L, 2W, WITH RUN-AROUND, FOR SPEEDS >= 45 MPH
		01-03	SIDEWALK CLOSURE
	7019		TRAFFIC CONTROL DEVICES
CHECKS INT. DATE REASON		001-04	TEMPORARY CONCRETE BARRIER
STE NEASON	7200		METAL POSTS FOR SIGNS, MARKERS AND DELINEATORS
		001-01	TYPICAL PAVEMENT MARKINGS
		01-02	TYPICAL APPLICATION RAISED REFLECTIVE PAVEMENT MARKERS

LEGEND APPLIES FOR THE FOLLOWING:
PLAN AND PROFILE, DRAINAGE, EROSION CONTROL.
AND REMOVAL AND ADJUSTMENTS

EROS	SION CONTROL LEGEND
	SEEDING, CLASS 1 (URBAN)
	SEEDING, CLASS 2 (RURAL)
	AGGREGATE SURFACE COURSE, TYPE I
\oplus	INLET AND PIPE PROTECTION
	EROSION CONTROL BLANKET
	STONE RIPRAP, CLASS A3 OR A4
Chandlandhandhan	PERIMETER EROSION BARRIER



COMMITMENTS

Parcel 8906025 - First National Bank of Millstadt Station 10+25, Rt. to Station 12+60, Rt. - The Department will contact the First National Bank of Millstadt pior to beginning any construction activities that will require the closure of the bank's drive-up window and ATM exit lanes on Illinois Route 163.

Parcel 8906026 - Leesman Station 13+18, Rt. to Station 14+37, Rt. - The property owner will be given 48 hours advance notice by the Contractor and/or Engineer when the work to remove and replace the parking area within the Temporary Easement is to begin. If at all possible, the Contractor will adjust the schedule if funeral services have already been scheduled. Mr. Bruce Leesman can be contacted at 618-476-1000 or 618-781-5365.

The Department will complete the removal and reconstruction of the parking area within the Temporary Easement within 3 days. The work shall not extend through the weekend. Permanent striping of the parking stalls is a specialty item and is not to be considered as an item that will be completed within the constraints of this commitment.

CONTRACT NO. 76A34

The business sign for "Struss Funeral Home" located with the Temporary Easement will not be disturbed, however the landscaping items surrounding the sign will be disturbed and compensation for these items has been included in the negotiated settlement.

Parcel 8906018 - Englebretson The following trees wil not be removed as part of this project: Juniper tree at Station 14+52, 38' Lt., Black Cherry tree at Station 14+86, Lt., and Green Ash tree at Station 15+03, 39' Lt.

Parcel 8906042 and 8906043 - Seib Station 51+50, Lt. to Station 56+25, lt. Property owner's fence will not be disturbed at any time during construction of the project.

Parcel 8906044 - Station 59+05, Lt. - The property owners mailbox post shall be removed as necessary and set aside for the property owner to salvage.


Parcel 8906065 - Station 126+58, Rt. - The property owners brick pillars along the driveway and the electrical wiring between the two and the house shall remian in place and not damaged.

Tree felling will be restricted to the dates between September 30 and April 1 of any given year.

Parcel 8906097 - Previously owned by Dorothy P. and John A. LaFlamme now owned by Jason and Elizabeth McWhorter.

The contractor shall remove all fencing along the front of the property. In addition, the shrubs and bushes along the fence near illinois Route 163 shall also be removed. The two large trees in front of the house will not be removed. The resident engineer shall contact the property owner prior to any removal to confirm the limits of the fence and shrub removal and identify the two trees that WILL NOT be removed.

Δ



A Rev. 10-20-08