

# Stage II Traffic 14'-0" Stage II Construction 19'-7" P.G. STAGE II CONSTRUCTION


### Notes:

- 1. Hatched areas indicate removal.
- 2. All staging sections are looking South.
- 3. For quantity of Temporary Concrete Barrier, see roadway plans.
- 4. For details of Temporary Concrete Barrier see Sheet 5 of 22.

# STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION



Contract # 94770



# SHEET PILING ELEVATION

(North Abut. shown: South Abut. similar)

### Notes:

- Minimum section modulus of temporary sheet piling shall be as shown in the Elevation View of this sheet.
- If the contractor chooses to alter the temporary cantilevered sheet pile design requirements shown on the plans for lesser design requirements, the full design calculations with the required seals shall be submitted to the Department for review and approval.
- 3. The contractor shall connect the first sheet to the existing abutment wall to ensure stability of the sheets driven to the top of the footing. This connection shall be reviewed and accepted by the Engineer and included in the cost for Temporary Sheet Piling.

STAGED CONSTRUCTION
US 51 / RICHLAND CREEK
F.A.P. RT. 322
FAYETTE COUNTY
SN. 026-0104

## BENTON & ASSOCIATES, INC.

	TIBBO CHITES, II
DESIGNED	MBH
CHECKED	NRF
DRAWN	MBH .
CHECKED	NRF