



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 30, 2013

SUBJECT: FAU 201 (Hart Road)
Project M-9003(482)
Section 00-00025-00-FP (Round Lake)
Lake County
Contract No. 63868
Item 078
November 8, 2013 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

- 1. Replaced the Schedule of Prices.**
- 2. Revised pages 2, 3, 4 & 5 of the Index of Special Provisions.**
- 3. Revised pages 45 – 138 to the Special Provisions.**
- 4. Added pages 138A – 138C and pages 354 – 380 to the Special Provisions.**
- 5. Revised sheets 4, 10, 24, 33, 34, 42, 43, 54, 68, 73 & 98 of the Plans.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.", with a small "P.E." to the right.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

COUNTY NAME	CODE	DIST	SECTION NUMBER	PROJECT NUMBER	ROUTE
LAKE	097	01	00-00025-00-FP ROUND LAKE	M-9003/482/000	FAU 201

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
B2000778	T-AMELAN LAEV TF 3"	EACH	10.000	X	=		
B2001624	T-CRAT CRU-I TF 3	EACH	11.000	X	=		
XX003643	BASE REPAIR SPECIAL	SQ YD	581.000	X	=		
XX005928	TRAF SIGL P 10FT SPL	EACH	2.000	X	=		
XX005931	TRAF SIGL P 16FT SPL	EACH	1.000	X	=		
XX005937	LED INT IL S-NAME SGN	EACH	3.000	X	=		
XX005940	REMOTE CONTR VIDEO SY	EACH	1.000	X	=		
XX008131	ELCBL C VIDEO 18 3C	FOOT	580.000	X	=		
XX008253	VIDEO ENCODER	EACH	1.000	X	=		
XX008392	OUTDR RTD NTRK CABLE	FOOT	53.000	X	=		
XX008536	PREPARATION OF BSE SP	SQ YD	5,810.000	X	=		
XX008904	STORM SEW PILE SUP	FOOT	71.000	X	=		
XX008905	PRC FL-END SEC P \$	EACH	1.000	X	=		
XX008906	S C MAA&P DMA 22&34SP	EACH	1.000	X	=		
XX008907	EC C EPR TYPE 2-1C 10	FOOT	345.000	X	=		

* Revised 10/30/13

FAU 201
 00-00025-00-FP ROUND LAKE
 LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63868

ECMS002 DTGECM03 ECMR003 PAGE 2
 RUN DATE - 10/29/13
 RUN TIME - 183129

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
XZ127900	RETAINING WALL REMOV	FOOT	270.000	X	=	=	=
X0324085	EM VEH P S LSC 20 3C	FOOT	302.000	X	=	=	=
X0325366	STORM SEWER REPAIR	FOOT	65.000	X	=	=	=
X0326950	INST EXSTG ELEC CABLE	FOOT	624.000	X	=	=	=
X0327566	ROADSIDE DETECTOR	EACH	1.000	X	=	=	=
X2130010	EXPLOR TRENCH SPL	FOOT	500.000	X	=	=	=
X4021000	TEMP ACCESS- PRIV ENT	EACH	3.000	X	=	=	=
X4022000	TEMP ACCESS- COM ENT	EACH	33.000	X	=	=	=
X4023000	TEMP ACCESS- ROAD	EACH	10.000	X	=	=	=
X5120005	DRIVING PILES SPL	FOOT	800.000	X	=	=	=
X5610680	WATER MAIN PROTECTION	FOOT	80.000	X	=	=	=
X6022120	MAN DT 7 DIA T1F CL	EACH	1.000	X	=	=	=
X6023102	MAN TA 5D T1F CL SPL	EACH	1.000	X	=	=	=
X6026050	SANITARY MANHOLE ADJ	EACH	8.000	X	=	=	=
X6640306	CH LK FENCE RELOC	FOOT	180.000	X	=	=	=

* Revised 10/30/13

FAU 201
 00-00025-00-FP ROUND LAKE
 LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63868

ECMS002 DTGECM03 ECMR003 PAGE 3
 RUN DATE - 10/29/13
 RUN TIME - 183129

*

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
X7010216	TRAF CONT & PROT SPL	L SUM	1.000 X	=		=	
X8570226	FAC T4 CAB SPL	EACH	1.000 X	=		=	
X8620200	UNINTER POWER SUP SPL	EACH	1.000 X	=		=	
X8730571	EC C COAXIAL	FOOT	105.000 X	=		=	
X8730800	ELCBL C VIDEO 20 4C	FOOT	105.000 X	=		=	
X8770139	S C MAA&P 44 SPL	EACH	1.000 X	=		=	
Z0004562	COMB C C&G REM & REPL	FOOT	300.000 X	=		=	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000 X	=		=	
Z0018500	DRAINAGE STR CLEANED	EACH	4.000 X	=		=	
Z0030850	TEMP INFO SIGNING	SQ FT	230.000 X	=		=	
Z0033046	RE-OPTIMIZE SIG SYS 2	EACH	1.000 X	=		=	
Z0033072	VIDEO VEH DET SYS	EACH	1.000 X	=		=	
Z0048665	RR PROT LIABILITY INS	L SUM	1.000 X	=		=	
Z0056608	STORM SEW WM REQ 12	FOOT	82.000 X	=		=	
Z0062456	TEMP PAVEMENT	SQ YD	500.000 X	=		=	

* Revised 10/30/13

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
Z0073510	TEMP TR SIGNAL TIMING	EACH	1.000 X				
Z0076600	TRAINEES	hour	1,000.000 X	0.80		800.00	
Z0076604	TRAINEES TPG	hour	1,000.000 X	10.00		10,000.00	
20100110	TREE REMOV 6-15	UNIT	135.000 X				
20100210	TREE REMOV OVER 15	UNIT	20.000 X				
20101100	TREE TRUNK PROTECTION	EACH	28.000 X				
20101200	TREE ROOT PRUNING	EACH	28.000 X				
20101300	TREE PRUN 1-10	EACH	14.000 X				
20101350	TREE PRUN OVER 10	EACH	14.000 X				
20200100	EARTH EXCAVATION	CU YD	5,474.000 X				
20201200	REM & DISP UNS MATL *	CU YD	3,663.000 X				
20800150	TRENCH BACKFILL	CU YD	15,826.000 X				
21001000	GEOTECH FAB F/GR STAB	SQ YD	12,260.000 X				
21101615	TOPSOIL F & P 4	SQ YD	6,249.000 X				
25000200	SEEDING CL 2	ACRE	0.260 X				

* Revised 10/30/13

FAU 201
 00-00025-00-FP ROUND LAKE
 LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63868

ECMS002 DTGECM03 ECMR003 PAGE 5
 RUN DATE - 10/29/13
 RUN TIME - 183129

*

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
25000310	SEEDING CL 4	ACRE	0.130 X	=			
25000314	SEEDING CL 4B	ACRE	0.370 X	=			
25000322	SEEDING CL 5A	ACRE	0.130 X	=			
25000400	NITROGEN FERT NUTR	POUND	89.000 X	=			
25000600	POTASSIUM FERT NUTR	POUND	89.000 X	=			
25100630	EROSION CONTR BLANKET	SQ YD	3,524.000 X	=			
25100900	TURF REINF MAT	SQ YD	415.000 X	=			
25200110	SODDING SALT TOLERANT	SQ YD	5,046.000 X	=			
25200200	SUPPLE WATERING	UNIT	100.000 X	=			
28000250	TEMP EROS CONTR SEED	POUND	338.000 X	=			
28000400	PERIMETER EROS BAR	FOOT	2,522.000 X	=			
28000510	INLET FILTERS	EACH	54.000 X	=			
28001100	TEMP EROS CONTR BLANK	SQ YD	18,780.000 X	=			
30300001	AGG SUBGRADE IMPROVE	CU YD	1,482.000 X	=			
30300112	AGG SUBGRADE IMPR 12	SQ YD	12,311.000 X	=			

* Revised 10/30/13

FAU 201
 00-00025-00-FP ROUND LAKE
 LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63868

ECMS002 DTGECM03 ECMR003 PAGE 6
 RUN DATE - 10/29/13
 RUN TIME - 183129 *

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
35101400	AGG BASE CSE B	TON	320.000 X	=			
35101600	AGG BASE CSE B 4	SQ YD	4,048.000 X	=			
35501288	HMA BASE CSE 2 1/2	SQ YD	4,030.000 X	=			
35501308	HMA BASE CSE 6	SQ YD	112.000 X	=			
35501316	HMA BASE CSE 8	SQ YD	452.000 X	=			
40600200	BIT MATLS PR CT	TON	23.000 X	=			
40600300	AGG PR CT	TON	74.000 X	=			
40600990	TEMPORARY RAMP	SQ YD	660.000 X	=			
40603080	HMA BC IL-19.0 N50	TON	1,698.000 X	=			
40603335	HMA SC "D" N50	TON	1,206.000 X	=			
40701871	HMA PAVT FD 9 1/2	SQ YD	6,630.000 X	=			
40800050	INCIDENTAL HMA SURF	TON	50.000 X	=			
42001300	PROTECTIVE COAT	SQ YD	5,132.000 X	=			
42300400	PCC DRIVEWAY PAVT 8	SQ YD	182.000 X	=			
42400200	PC CONC SIDEWALK 5	SQ FT	24,822.000 X	=			

* Revised 10/30/13

FAU 201
 00-00025-00-FP ROUND LAKE
 LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63868

ECMS002 DTGECM03 ECMR003 PAGE 7
 RUN DATE - 10/29/13
 RUN TIME - 183129

*

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
42400300	PC CONC SIDEWALK 6	SQ FT	644.000 X	=	=	=	=
42400410	PC CONC SIDEWALK 8	SQ FT	3,445.000 X	=	=	=	=
42400800	DETECTABLE WARNINGS	SQ FT	140.000 X	=	=	=	=
44000100	PAVEMENT REM	SQ YD	8,740.000 X	=	=	=	=
44000165	HMA SURF REM 4	SQ YD	5,810.000 X	=	=	=	=
44000200	DRIVE PAVEMENT REM	SQ YD	1,038.000 X	=	=	=	=
44000300	CURB REM	FOOT	233.000 X	=	=	=	=
44000500	COMB CURB GUTTER REM	FOOT	5,203.000 X	=	=	=	=
44000600	SIDEWALK REM	SQ FT	10,055.000 X	=	=	=	=
48102100	AGG WEDGE SHLD TYPE B	TON	13.000 X	=	=	=	=
50105220	PIPE CULVERT REMOV	FOOT	37.000 X	=	=	=	=
550A0050	STORM SEW CL A 1 12	FOOT	509.000 X	=	=	=	=
550A0070	STORM SEW CL A 1 15	FOOT	542.000 X	=	=	=	=
550A0160	STORM SEW CL A 1 36	FOOT	26.000 X	=	=	=	=
550A0340	STORM SEW CL A 2 12	FOOT	280.000 X	=	=	=	=

* Revised 10/30/13

FAU 201
 00-00025-00-FP ROUND LAKE
 LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63868

ECMS002 DTGECM03 ECMR003 PAGE 8
 RUN DATE - 10/29/13
 RUN TIME - 183129

*

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
550A0450	STORM SEW CL A 2 36	FOOT	242.000 X	=			
550A0750	STORM SEW CL A 3 36	FOOT	2,000.000 X	=			
550A1050	STORM SEW CL A 4 36	FOOT	467.000 X	=			
550A1320	STORM SEW CL A 5 36	FOOT	809.000 X	=			
550A2320	SS RG CL A 1 12	FOOT	31.000 X	=			
55100200	STORM SEWER REM 6	FOOT	4.000 X	=			
55100400	STORM SEWER REM 10	FOOT	55.000 X	=			
55100500	STORM SEWER REM 12	FOOT	613.000 X	=			
55100700	STORM SEWER REM 15	FOOT	560.000 X	=			
55101600	STORM SEWER REM 36	FOOT	48.000 X	=			
55201300	STORM SEWERS JKD 36	FOOT	187.000 X	=			
56300100	ADJ SAN SEWER 8 LESS	FOOT	22.000 X	=			
56300200	ADJ SAN SEWER OVER 8	FOOT	40.000 X	=			
56300300	ADJ WATER SERV LINES	FOOT	422.000 X	=			
56400100	FIRE HYDNTS TO BE MVD	EACH	3.000 X	=			

* Revised 10/30/13

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
56400300	FIRE HYDNTS TO BE ADJ	EACH	1.000 X	=			
56500600	DOM WAT SER BOX ADJ	EACH	1.000 X	=			
60107600	PIPE UNDERDRAINS 4	FOOT	450.000 X	=			
60200105	CB TA 4 DIA T1F OL	EACH	1.000 X	=			
60200205	CB TA 4 DIA T1F CL	EACH	3.000 X	=			
60201105	CB TA 4 DIA T11F&G	EACH	3.000 X	=			
60201110	CB TA 4 DIA T11V F&G	EACH	5.000 X	=			
60205515	CB TA 5D M INL 604106	EACH	1.000 X	=			
60207905	CB TC T11F&G	EACH	5.000 X	=			
60207915	CB TC T11V F&G	EACH	4.000 X	=			
60218300	MAN TA 4 DIA T1F OL	EACH	1.000 X	=			
60221100	MAN TA 5 DIA T1F CL	EACH	10.000 X	=			
60223800	MAN TA 6 DIA T1F CL	EACH	1.000 X	=			
60224446	MAN TA 7 DIA T1F CL	EACH	2.000 X	=			
60224469	MAN TA 9 DIA T1F CL	EACH	1.000 X	=			

* Revised 10/30/13

FAU 201
 00-00025-00-FP ROUND LAKE
 LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63868

ECMS002 DTGECM03 ECMR003 PAGE 10
 RUN DATE - 10/29/13
 RUN TIME - 183129

*

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
60234200	INLETS TA T1F OL	EACH	2.000 X	=	=	=	=
60236825	INLETS TA T11V F&G	EACH	4.000 X	=	=	=	=
60255500	MAN ADJUST	EACH	2.000 X	=	=	=	=
60260100	INLETS ADJUST	EACH	1.000 X	=	=	=	=
60261300	INLETS ADJ NEW T11F&G	EACH	2.000 X	=	=	=	=
60262700	INLETS RECONST	EACH	2.000 X	=	=	=	=
60263900	INL RECON NEW T11F&G	EACH	3.000 X	=	=	=	=
60265700	VV ADJUST	EACH	1.000 X	=	=	=	=
60266600	VALVE BOX ADJ	EACH	9.000 X	=	=	=	=
60500040	REMOV MANHOLES	EACH	2.000 X	=	=	=	=
60500060	REMOV INLETS	EACH	18.000 X	=	=	=	=
60500070	REMOV MAN - MAIN FLOW	EACH	1.000 X	=	=	=	=
60600605	CONC CURB TB	FOOT	192.000 X	=	=	=	=
60603800	COMB CC&G TB6.12	FOOT	6,994.000 X	=	=	=	=
60605000	COMB CC&G TB6.24	FOOT	97.000 X	=	=	=	=

* Revised 10/30/13

*

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
63300575	R&R RAIL ELEM EX GDRL	FOOT	50.000 X	=	=	=	=
66300105	CALCIUM CHLORIDE APLD	TON	21.000 X	=	=	=	=
66900200	NON SPL WASTE DISPOSL	CU YD	6,100.000 X	=	=	=	=
66900450	SPL WASTE PLNS/REPORT	L SUM	1.000 X	=	=	=	=
66900530	SOIL DISPOSAL ANALY	EACH	2.000 X	=	=	=	=
67100100	MOBILIZATION	L SUM	1.000 X	=	=	=	=
70106800	CHANGEABLE MESSAGE SN	CAL MO	30.000 X	=	=	=	=
70300100	SHORT TERM PAVT MKING	FOOT	2,077.000 X	=	=	=	=
70300210	TEMP PVT MK LTR & SYM	SQ FT	770.000 X	=	=	=	=
70300220	TEMP PVT MK LINE 4	FOOT	18,458.000 X	=	=	=	=
70300240	TEMP PVT MK LINE 6	FOOT	2,044.000 X	=	=	=	=
70300260	TEMP PVT MK LINE 12	FOOT	1,648.000 X	=	=	=	=
70300280	TEMP PVT MK LINE 24	FOOT	338.000 X	=	=	=	=
70300520	PAVT MARK TAPE T3 4	FOOT	1,800.000 X	=	=	=	=
70301000	WORK ZONE PAVT MK REM	SQ FT	938.000 X	=	=	=	=

* Revised 10/30/13

FAU 201
 00-00025-00-FP ROUND LAKE
 LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63868

ECMS002 DTGECM03 ECMR003 PAGE 12
 RUN DATE - 10/29/13
 RUN TIME - 183129

*

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
72000100	SIGN PANEL T1	SQ FT	205.000 X				
72400100	REMOV SIN PAN ASSY TA	EACH	21.000 X				
72800100	TELES STL SIN SUPPORT	FOOT	512.000 X				
78000100	THPL PVT MK LTR & SYM	SQ FT	385.000 X				
78000200	THPL PVT MK LINE 4	FOOT	9,184.000 X				
78000300	THPL PVT MK LINE 5	FOOT	90.000 X				
78000400	THPL PVT MK LINE 6	FOOT	1,022.000 X				
78000600	THPL PVT MK LINE 12	FOOT	824.000 X				
78000650	THPL PVT MK LINE 24	FOOT	169.000 X				
78100100	RAISED REFL PAVT MKR	EACH	16.000 X				
78300100	PAVT MARKING REMOVAL	SQ FT	710.000 X				
78300200	RAISED REF PVT MK REM	EACH	10.000 X				
80500020	SERV INSTALL POLE MT	EACH	1.000 X				
81028200	UNDRGRD C GALVS 2	FOOT	218.000 X				
81028210	UNDRGRD C GALVS 2 1/2	FOOT	66.000 X				

* Revised 10/30/13

FAU 201
 00-00025-00-FP ROUND LAKE
 LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63868

ECMS002 DTGECM03 ECMR003 PAGE 13
 RUN DATE - 10/29/13
 RUN TIME - 183129

*

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
81028230	UNDRGRD C GALVS 3 1/2	FOOT	50.000 X	=			
81028240	UNDRGRD C GALVS 4	FOOT	196.000 X	=			
81400100	HANDHOLE	EACH	2.000 X	=			
81400300	DBL HANDHOLE	EACH	1.000 X	=			
82103250	LUM SV HOR MT PC 250W	EACH	2.000 X	=			
87301215	ELCBL C SIGNAL 14 2C	FOOT	660.000 X	=			
87301225	ELCBL C SIGNAL 14 3C	FOOT	583.000 X	=			
87301245	ELCBL C SIGNAL 14 5C	FOOT	1,330.000 X	=			
87301255	ELCBL C SIGNAL 14 7C	FOOT	375.000 X	=			
87301805	ELCBL C SERV 6 2C	FOOT	48.000 X	=			
87301900	ELCBL C EGRDC 6 1C	FOOT	394.000 X	=			
87800100	CONC FDN TY A	FOOT	12.000 X	=			
87800150	CONC FDN TY C	FOOT	4.000 X	=			
87800415	CONC FDN TY E 36D	FOOT	31.000 X	=			
87900200	DRILL EX HANDHOLE	EACH	1.000 X	=			

* Revised 10/30/13

FAU 201
00-00025-00-FP ROUND LAKE
LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - 63868

ECMS002 DTGECM03 ECMR003 PAGE 14
RUN DATE - 10/29/13
RUN TIME - 183129

*

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
88030020	SH LED 1F 3S MAM	EACH	5.000 X				
88030050	SH LED 1F 3S BM	EACH	3.000 X				
88030100	SH LED 1F 5S BM	EACH	1.000 X				
88030110	SH LED 1F 5S MAM	EACH	1.000 X				
88102717	PED SH LED 1F BM CDT	EACH	2.000 X				
88200210	TS BACKPLATE LOU ALUM	EACH	6.000 X				
88700200	LIGHT DETECTOR	EACH	2.000 X				
88700300	LIGHT DETECTOR AMP	EACH	1.000 X				
88800100	PED PUSH-BUTTON	EACH	2.000 X				
89000100	TEMP TR SIG INSTALL	EACH	1.000 X				
89500120	REM EX SERV INSTALL	EACH	1.000 X				
89502300	REM ELCBL FR CON	FOOT	6,403.000 X				
89502375	REMOV EX TS EQUIP	EACH	1.000 X				
89502380	REMOV EX HANDHOLE	EACH	4.000 X				
89502382	REMOV EX DBL HANDHOLE	EACH	1.000 X				

* Revised 10/30/13

FAU 201
00-00025-00-FP ROUND LAKE
LAKE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - 63868

ECMS002 DTGECM03 ECMR003 PAGE 15
RUN DATE - 10/29/13
RUN TIME - 183129 *

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
89502385	REMOV EX CONC FDN	EACH	6.000 X			=	

TOTAL \$

NOTE:

1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.

* Revised 10/30/13

INDEX OF SPECIAL PROVISIONS (CONT.)

	<u>PAGE NO.</u>
STORM SEWER ADJACENT TO OR CROSSING WATER MAIN.....	40
TEMPORARY PAVEMENT.....	40
RETAINING WALL REMOVAL	41
STORM SEWER REPAIR.....	42
INSTALL EXISTING ELECTRICAL CABLE	42
ROADSIDE DETECTOR.....	43
EXPLORATION TRENCH, SPECIAL.....	43
AGGREGATE SURFACE COURSE FOR TEMPORARY ACCESS.....	44
DRIVING PILES (SPECIAL).....	45
WATER MAIN PROTECTION.....	46
MANHOLES, DROP TYPE	47
MANHOLES, SPECIAL.....	47
SANITARY MANHOLES TO BE ADJUSTED	48
CHAIN LINK FENCE TO BE RELOCATED.....	49
TRAFFIC CONTROL AND PROTECTION (ARTERIALS).....	50
BASE REPAIR, SPECIAL	50
PREPARATION OF BASE (SPECIAL).....	51
STORM SEWERS, PILE SUPPORTED	52
PRECAST REINFORCED CONCRETE FLARED END SECTION, PILE SUPPORTED	53
ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW), 2-1/C NO. 10.....	54
TRAFFIC SIGNAL SPECIAL PROVISIONS (LAKE COUNTY DOT)	54
.....SUBMITTALS.....	56
.....MARKING PROPOSED LOCATIONS	57
.....INSPECTION OF ELECTRICAL SYSTEMS	57
.....MAINTENANCE AND RESPONSIBILITY	57
.....LIQUIDATED DAMAGES FOR UNTIMELY WORK.....	60
.....DAMAGE TO TRAFFIC SIGNAL SYSTEM.....	60
.....TRAFFIC SIGNAL INSPECTION (TURN-ON).....	61
.....LOCATING UNDERGROUND FACILITIES.....	63
.....MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	63

INDEX OF SPECIAL PROVISIONS (CONT.)

	<u>PAGE NO.</u>
....TEMPORARY TRAFFIC SIGNAL INSTALLATION.....	65
....REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT.....	68
....RESTORATION OF WORK AREA	69
....CABINET NEATNESS	69
....VENDOR REPRESENTATION.....	69
....INTERRUPTION OF COMMUNICATION	70
....ELECTRIC SERVICE INSTALLATION	70
....GROUNDING OF TRAFFIC SIGNAL SYSTEMS.....	73
....GROUNDING EXISTING HANDHOLE FRAME AND COVER	74
....UNDERGROUND CONDUIT	75
....CONCRETE FOUNDATIONS.....	75
....HANDHOLES	76
....COILABLE NON-METALLIC CONDUIT	77
....DETECTOR LOOP	77
....ELECTRIC CABLE	80
....GROUNDING CABLE	80
....RAILROAD INTERCONNECT CABLE	81
....ELECTRIC CABLE IN CONDUIT, COAXIAL	81
....EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	81
....ELECTRICAL CABLE IN CONDUIT, VIDEO NO 20 4 C.....	82
....OUTDOOR RATED NETWORK CABLE	82
....TRAFFIC-ACTUATED CONTROLLER.....	82
....CONTROLLER CABINET AND PERIPHERAL EQUIPMENT	83
....FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	84
....TRAFFIC ACTUATED CONTROLLER & CABINET INTERCONNECTED WITH RAILROADS.....	85
....MASTER CONTROLLER	85
....INTERSECTION MONITOR	86
....INDUCTIVE LOOP DETECTOR.....	86
....UNINTERRUPTABLE POWER SUPPLY, SPECIAL.....	86

INDEX OF SPECIAL PROVISIONS (CONT.)

	<u>PAGE NO.</u>
.....EMERGENCY VEHICLE PRIORITY SYSTEM	89
.....STEEL MAST ARM ASSEMBLY AND POLE	90
.....STEEL MAST ARM ASSEMBLY AND POLE (SPECIAL)	90
.....LUMINAIRE.....	92
.....TRAFFIC SIGNAL POST.....	92
.....TRAFFIC SIGNAL POST (SPECIAL)	92
.....PEDESTRIAN PUSH-BUTTON.....	93
.....ILLUMINATED SIGN, LIGHT EMITTING DIODE.....	94
.....LED INTERNALLY ILLUMINATED STREET NAME SIGN	95
.....MAST ARM SIGN PANELS.....	98
.....SIGNAL HEADS	99
.....PEDESTRIAN SIGNAL HEAD, LED	100
.....SIGNAL HEAD, LED, RETROFIT	100
.....TRAFFIC SIGNAL BACKPLATE	101
.....VIDEO VEHICLE DETECTION SYSTEM	101
.....REMOTE-CONTROLLED VIDEO SYSTEM	102
.....CAMERA MOUNTING ASSEMBLY.....	104
.....VIDEO TRANSMISSION SYSTEM.....	104
.....COMMUNICATIONS CABINET.....	105
.....LAYER II (DATA LINK) SWITCH.....	107
.....LAYER III (NETWORK) SWITCH	107
.....FIBER OPTIC TRANSCEIVER MODULE, SFP TYPE, LONG DISTANCE	108
.....FIBER OPTIC TRANSCEIVER MODULE, SFP TYPE, EXTRA LONG DISTANCE	108
.....FIBER OPTIC TRANSCEIVER MODULE, GBIC TYPE, LONG DISTANCE	109
.....FIBER OPTIC TRANSCEIVER MODULE, GBIC TYPE, EXTRA LONG DISTANCE	109
.....VIDEO ENCODER	109
.....MEDIA CONVERTER.....	110
.....TERMINAL SERVER.....	111
.....FIBER OPTIC CABLE	111
.....TERMINATE FIBER IN CABINET	112

INDEX OF SPECIAL PROVISIONS (CONT.)

	<u>PAGE NO.</u>
.....SPLICE FIBER IN CABINET	113
.....FIBER OPTIC TRACER CABLE.....	113
.....WIRELESS TRANSMISSION SYSTEM SHORT RANGE.....	114
.....WIRELESS TRANSMISSION SYSTEM LONG RANGE.....	115
.....WIRELESS TRANSMISSION SYSTEM EXTRA LONG RANGE	116
.....WIRELESS TRANSMISSION SYSTEM POINT TO POINT	117
.....WIRELESS TRANSMISSION SYSTEM BACKHAUL	117
.....WIRELESS TRANSMISSION SYSTEM BASE STATION.....	118
.....RELOCATE EXISTING VIDEO DETECTION SYSTEM (COMPLETE INTERSECTION)	119
.....RELOCATE EXISTING REMOTE-CONTROLLED VIDEO SYSTEM.....	120
.....RELOCATE EXISTING SWITCH.....	120
.....TEMPORARY TRAFFIC SIGNAL TIMING.....	120
.....RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM.....	121
.....OPTIMIZE TRAFFIC SIGNAL SYSTEM.....	124
LAKE COUNTY D.O.T. TRAFFIC CONTROL AND PROTECTION SPECIAL PROVISION	127
DETECTABLE WARNINGS (LCDOT STANDARD)	137
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROV. (TPG) <i>138A.</i>	
STORM WATER POLLUTION PREVENTION PLAN (SWPPP)	139
NOTICE OF INTENT FOR CONSTRUCTION (NOI)	146
METRA RIGHT-OF-ENTRY PERMIT APPLICATION FORM	148
CCDD SOIL TESTING RESULTS	150
US ARMY CORP OF ENGINEERS 404 PERMIT	354
LAKE COUNTY D.O.T. BOND AND INSURANCE REQUIREMENTS	363
<i>LAKE COUNTY SMC PERMIT</i>	<i>378</i>

When use of the temporary access is discontinued, the aggregate shall be removed and utilized in the permanent construction or disposed of according to Article 202.03.”

Add the following to Article 402.12 of the Standard Specifications:

“Aggregate surface course for temporary access will be measured for payment as each for every private entrance, commercial entrance or road constructed for the purpose of temporary access. If a residential drive, commercial entrance, or road is to be constructed under multiple stages, the aggregate needed to construct the second or subsequent stages will not be measured for payment but shall be included in the cost per each of the type specified.”

Revise the second paragraph of Article 402.13 of the Standard Specifications to read:

“Aggregate surface course for temporary access will be paid for at the contract unit price per each for TEMPORARY ACCESS (PRIVATE ENTRANCE), TEMPORARY ACCESS (COMMERCIAL ENTRANCE) or TEMPORARY ACCESS (ROAD).

Partial payment of the each amount bid for temporary access, of the type specified, will be paid according to the following schedule:

- (a) Upon construction of the temporary access, sixty percent of the contract unit price per each, of the type constructed, will be paid.
- (b) Subject to the approval of the Engineer for the adequate maintenance and removal of the temporary access, the remaining forty percent of the pay item will be paid upon the permanent removal of the temporary access.”

DRIVING PILES (SPECIAL):

This work shall be done in accordance with Section 512 of the Standard Specifications and the Concrete Cradle / Pile Support Detail provided in the Plans, except as modified herein.

512.01 Description. Revise this Article to read:

“**512.01 Description.** This work shall consist of furnishing and installing timber or helical piles for the pile/concrete cradle support of the storm sewer or flared end section complete in place, including support for pile handling and installation equipment; driving timber piles with a backhoe/excavator to resistance, or installing helical piles, to the load bearing capacity indicated in the Detail; cleanup; and all other work necessary for a complete pile installation.”

512.02 Materials. Add the following to the end of this Article:

“(l) Helical piles shall provide an extendable foundation system with helical bearing plates welded to a central steel shaft. Extension shafts shall include bolted couplings. The helices shall not auger into and through soil, but shall instead be installed to screw into the soil with minimal soil disturbance. Multiple helices shall be spaced far enough

apart to function independently. Capacity of the helical piles shall be determined by a torque meter or shear pin coupling.

Acceptable helical pile manufacturers:

1. AB Chance by Hubbell Incorporated
(855 477 2121; civilconstruction@hubbell.com)
2. Helical Piers by Empire Piers
(636 922 4747; info@empirepiers.com)
3. Helical Pile System by Magnum Piering, Inc.
(513 259 0725;)
4. Helical Piles / Helical Piers by Cantsink
(678 280 7453; info@cantsink.com)

Timber piles shall be treated wood.”

512.14 Determination of Nominal Bearing. Add the following to end of this Article:

“If pile hammers are not used to drive timber piles or if helical piles are used, timber piles shall be driven to refusal to a minimum of 15,000 pounds. Helical piles shall be driven to the torque or shear force required by the manufacturer to obtain 15,000 pound minimum bearing.”

512.17 Method of Measurement. Revise this article to read:

“This work will be measured for payment in place per vertical foot regardless of the material of the piles, subtracting cutoffs to grade.”

512.18 Basis of Payment. Revise this article to read:

“**512.18 Basis of Payment**. This work will be paid for at the contract unit price per foot for DRIVING PILES (SPECIAL) regardless of the material of the piles.”

WATER MAIN PROTECTION:

Description. This work shall consist of tunneling under, protecting and supporting existing water mains that intersect proposed storm sewer trenches. All existing water main exposed during storm sewer installation shall be protected and supported to prevent settlement, misalignment, or any other damage to the existing pipe.

Any damage to the existing water main caused by the Contractor's operations, as determined by the Engineer, shall be repaired at no additional cost to the Contract. Repairs shall be in

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

accordance with Village of Round Lake requirements and the latest edition of the "Standard Specifications for Water Main and Sewer Construction in Illinois."

Method of Measurement. This work will be measured for payment in feet to the limits of exposed water main requiring protection or as determined by the Engineer.

Basis of Payment. This work will be paid for at the contract unit price per foot for WATER MAIN PROTECTION.

MANHOLES, DROP TYPE:

This work shall be done in accordance with Section 602 of the Standard Specifications and the Drop Manhole Detail provided in the Plans, except as modified herein.

602.01 Description. Add the following sentence to the end of this Article:

"This work shall include all reinforcement bars, ductile iron pipe, fittings, and concrete encasement."

602.16 Basis of Payment. Add the following paragraph to this Article:

"Drop type manholes will be paid for at the contract unit price per each for MANHOLES, DROP TYPE, of the diameter specified and the type of frame and grate or lid specified."

MANHOLES, SPECIAL:

This work shall be done in accordance with Sections 602 of the Standard Specifications and the Manhole Pile Detail provided in the Plans, except as modified herein.

602.01 Description. Add the following sentence to the end of this Article:

"This work shall consist of the installation of pile supported storm manholes complete in place, including excavation in excess of that required for storm sewer construction; trenching; bracing, sheeting and shoring; dewatering, including erosion and sedimentation control methods and devices to provide protection to the environment from all pumping operation; placement of reinforced concrete pile cap/manhole bottom on driven piles; storm sewer manhole, including base, barrel sections, cone section, adjusting rings, steps, chimney seals, and frames and covers; watertight flexible connectors to match pipe; poured inverts and benches; backfilling with and compaction of excavated material or granular backfill materials; final adjustment of frame to final grade at time of surface restoration; finish grading; removal and disposal of waste

excavated material; and all other work necessary for a complete pile supported storm sewer manhole installation.”

602.02 Materials. Materials shall be in accordance with applicable material sections listed in this Article.

Method of Measurement. This work will be measured for payment in place as each pile-supported manhole, regardless of the amount of concrete and reinforcement for the pile cap.

Piles will be measured for payment separately according to DRIVING PILES (SPECIAL).

602.16 Basis of Payment. Revise this article to read:

“**602.16 Basis of Payment**. This work will be paid for at the contract unit price per each for MANHOLES, SPECIAL, of the type and diameter specified and the type of frame and grate or lid specified.”

SANITARY MANHOLES TO BE ADJUSTED:

This work shall be done in accordance with Section 602 of the Standard Specifications and shall consist of the adjustment of sanitary manholes. Non-hardening butyl rubber mastic sealant; minimum thickness ¼-inch, shall be used between adjusting rings in place of mortar, or as required by the Owner of the Sanitary Sewer. In locations where existing external frame seals exist, it shall be removed and reinstalled. In locations where internal frame seals exist, it shall be removed and disposed of and an external frame seal shall be installed. In locations where there are no existing frame seals, an external frame seal shall be installed. The installation of the external frame seal will not be paid for separately and will be considered included in this pay item.

The External Frame seal shall consist of the following:

- A. Provide frame seals consisting of a flexible external rubber sleeve and extension and stainless steel compression bands.
- B. Rubber sleeve and extension:
 - 1. Provide rubber sleeve and extension complying with ASTM C923.
 - 2. Comply with a minimum 1500 psi tensile strength, maximum 18 percent compression set and a hardness (durameter) of 48±5.
 - 3. Provide sleeve with a minimum thickness of 3/16-inch and unexpanded vertical heights of 6 or 9 inches.
- C. Provide extension having a minimum thickness of 3/16-inch.
- D. Compression band:
 - 1. Provide compression band to compress the sleeve against the manhole.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

2. Use 16 gauge stainless steel conforming to ASTM A240 Type 304 with no welded attachments and having a minimum width of 1-inch.
 3. Make a watertight seal having a minimum adjustment range of 2 diameter inches.
 4. Provide stainless steel screws, bolts, and nuts conforming to ASTM F593 and 594, Type 304.
- E. Or as required by the Owner of the sanitary sewer system.

The External Frame Seal shall be installed as follows:

- A. Install external rubber gasket on the manhole frame and chimney.
 1. Provide watertight gasket to eliminate leakage between the frame and each adjusting ring down to and including cone section.
- B. Clean surface and prepare the lower 2 inches of the manhole frame and exterior of all adjusting rings and cone section/corbel surfaces.
 1. Realign frame on adjusting rings or corbel as required.
- C. Repair and apply mortar grout to the adjusting rings as required to provide a smooth, circular surface for the rubber gasket.
- D. Install rubber gasket in accordance with manufacturer's recommendations.
 1. Field verify for suitable dimensions and layout before installation.
 2. Utilize sealing caulk where required.
- E. Or as required by the Owner of the sanitary sewer system.

Basis of Payment. This work will be paid for at the contract unit price per each for SANITARY MANHOLES TO BE ADJUSTED, which price shall include all of the above.

CHAIN LINK FENCE TO BE RELOCATED:

This work shall include removal, salvaging, and replacement according to Section 664 of the Standard Specifications of existing chain link fence to the limits shown on the Plans or as determined by the Engineer.

Removal shall consist of the complete removal and salvaging of the chain link fence; including chain link fabric, hardware, fence posts, terminal posts, horizontal braces, and any other parts that make up the construction of the existing chain link fence; and backfilling the post holes with granular material. All parts that are unable to be salvaged due to the condition or unavoidable damage caused by the removal operation shall be properly disposed of.

Replacement shall consist of installing the salvaged chain link fence at the proposed location as shown in the Plans or as determined by the Engineer in accordance with Section 664 of the Standard Specifications, with replacement parts being of new material meeting requirements of Article 664.02.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

Method of Measurement. This work will be measured for payment according to Article 664.12 of the Standard Specifications.

Basis of Payment. This work will be paid for at the contract unit price per foot for CHAIN LINK FENCE TO BE RELOCATED.

TRAFFIC CONTROL AND PROTECTION (ARTERIALS):

Effective: February 1, 1996

Revised: March 1, 2011

Specific traffic control plan details and Special Provisions have been prepared for this contract. This work shall include all labor, materials, transportation, handling and incidental work necessary to furnish, install, maintain and remove all traffic control devices required as indicated in the plans and as approved by the Engineer.

When traffic is to be directed over a detour route, the Contractor shall furnish, erect, maintain and remove all applicable traffic control devices along the detour route according to the details shown in the plans.

Method of Measurement: All traffic control (except Traffic Control and Protection (Expressways) and temporary pavement markings) indicated on the traffic control plan details and specified in the Special Provisions will be measured for payment on a lump sum basis.

Basis of Payment: All traffic control and protection will be paid for at the contract lump sum price for TRAFFIC CONTROL AND PROTECTION (SPECIAL).

Temporary pavement markings will be paid for separately unless shown on a Standard.

BASE REPAIR, SPECIAL:

This work is to be performed where the entire existing HMA surface is to be removed or pulverized and shall consist of the removal of the existing aggregate base course and subgrade materials to a minimum depth of 10 inches, disposal of surplus material, compacting the subgrade, and installation of porous granular embankment and aggregate base course Type B to a minimum compacted thickness of 10 inches.

After the subgrade has been brought to a smooth grade and proper shape, it shall be compacted by use of vibratory rollers and/or compactors in accordance with Article 351.04 of the Standard Specifications.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

Replacement shall consist of providing Porous Granular Embankment in accordance with Article 207.03 to a minimum compacted thickness of 7 inches on a previously prepared subgrade. This Porous Granular Embankment layer shall be capped by a CA-6 crushed gravel or crushed stone base course layer compacted to a minimum thickness of 3 inches in accordance with Article 351.05. The material for the Porous Granular Embankment layer shall conform to Article 1004.05 of the Standard Specifications except the gradation shall be as follows:

1. Crushed Stone and Crushed Concrete

<u>Sieve Size</u>	<u>Percent Passing</u>
6 inches	97±3
4 inches	90±10
2 inches	45±25
#4	20±20
#200	5±5

2. Crushed Gravel

<u>Sieve Size</u>	<u>Percent Passing</u>
6 inches	97±3
4 inches	90±10
2 inches	55±25
#4	30±20
#200	5±5

Method of Measurement. This work shall be measured for payment in place and the area computed in square yards.

Basis of Payment. This work will be paid for at the contract unit price per square yard for BASE REPAIR, SPECIAL”.

PREPARATION OF BASE (SPECIAL):

~~This work shall be done in accordance with Section 358 of the Standard Specifications except as modified herein.~~

358.04 Aggregate Bases. Add the following sentence to the beginning of the first paragraph of this Article:

“It may be necessary to remove up to 2-inches of existing aggregate base course in order to establish the proposed base course elevation.”

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

358.04 Aggregate Bases. Delete reference to Article 358.04 (a).

358.04 Aggregate Bases. Add the following sentence to Article 358.04 (b):

“Proof-rolling with a 45,000-pound, rubber-tired vehicle in the presence of the Engineer will be necessary to demonstrate that the base is in proper condition for resurfacing.”

358.06 Method of Measurement. Revise Article 358.06 (b) to read:

“(b) Measured Quantities. The work in connection with the preparation of bases, except base repairs and addition of materials, will be measured for payment in place and the area computed in square yards.”

358.07 Basis of Payment. Revise this Article to read:

“**358.07 Basis of Payment.** The work will be paid for at the contract unit price per square yard for PREPARATION OF BASE (SPECIAL).”

STORM SEWERS, PILE SUPPORTED:

This work shall be done in accordance with Sections 550 of the Standard Specifications and the Concrete Cradle / Pile Support Detail provided in the Plans, except as modified herein.

550.01 Description. Revise this Article to read:

“**550.01 Description.** This work shall consist of the installation of storm sewer pipe with concrete cradles complete in place on driven piles, including excavation and trenching; bracing, sheeting and shoring; dewatering, including erosion and sedimentation control methods and devices to provide protection to the environment from all pumping operations; forming and placement of reinforced concrete cradles; shimming of storm sewer pipe; backfilling with and compaction of excavated material; finish grading; removal and disposal of waste excavated material; cleanup; and all other work necessary for a complete pile/cradle supported storm sewer installation.”

550.02 Materials. Materials shall be in accordance with applicable material sections listed in this Article, except that storm sewer shall be 42-inch iron pipe size (IPS) DR41 H.D.P.E. meeting PE3408/PE3608/PE4710 Specifications and Portland cement concrete used for the pile caps/ pipe cradles shall be in accordance with Section 1020.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

Method of Measurement. This work will be measured for payment in place per foot for pile/ cradle supported storm sewers, regardless of the amount of concrete and reinforcement for the pipe cradles.

Piles will be measured for payment separately according to DRIVING PILES (SPECIAL).

550.10 Basis of Payment. Revise this article to read:

“550.10 Basis of Payment. This work will be paid for at the contract unit price per foot for STORM SEWERS, PILE SUPPORTED, which includes the construction of the pipe cradles on driven piles.

Piles will be paid for separately according to DRIVING PILES (SPECIAL).”

PRECAST REINFORCED CONCRETE FLARED END SECTION, PILE SUPPORTED:

This work shall be done in accordance with Sections 542 of the Standard Specifications and the Concrete Cradle / Pile Support Detail provided in the Plans, except as modified herein.

542.01 Description. Revise this Article to read:

“542.01 Description. This work shall consist of the installation of a 36” or 42” reinforced concrete pipe flared end section with concrete cradles on driven piles complete in place, including excavation and trenching; bracing, sheeting and shoring; dewatering, including erosion and sedimentation control methods and devices to provide protection to the environment from all pumping operations; forming and placement of reinforced concrete cradle(s); shimming of the flared end section and storm sewer pipe; providing a concrete collar transition to match the end section invert to storm sewer invert; backfilling with and compaction of excavated material; finish grading; removal and disposal of waste excavated material; cleanup; and all other work necessary for a complete pile/cradle supported flared end section installation.”

542.02 Materials. Materials shall be in accordance with applicable material sections listed in this Article, ~~except that end section shall be a 36” or 42” precast reinforced concrete meeting~~ rigid pipe requirements for Class A, Type 1 Storm Sewer Pipe and Portland cement concrete used for pile caps/ pipe cradles and concrete collars shall be in accordance with Section 1020.

542.08 Pipe Elbows, Tees, and Collars. Revise the second paragraph of part (a) to read:

“Concrete collars shall be constructed according to Section 503 and shall be 12 inches thick and 24 inches long and provide a smooth transition from the incoming storm sewer pipe and the end section, maintaining matching inverts.”

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

Method of Measurement. This work will be measured for payment in place per each pile/cradle supported end section, regardless of the size used or amount of concrete and reinforcement for the pipe cradle(s).

Piles will be measured for payment separately according to DRIVING PILES (SPECIAL).

542.11 Basis of Payment. Revise this article to read:

"542.11 Basis of Payment. This work will be paid for at the contract unit price per each for PRECAST REINFORCED CONCRETE FLARED END SECTION, PILE SUPPORTED, regardless of the diameter used, which includes the construction pipe cradles on driven piles.

Piles will be paid for separately according to DRIVING PILES (SPECIAL)."

ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW), 2-1/C NO. 10:

This work shall be done in accordance Section 817 of the Standard Specifications, except as modified herein.

Basis of Payment. This work will be paid for at the contract unit price per foot installed for ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW), 2-1/C NO. 10.

TRAFFIC SIGNAL SPECIAL PROVISIONS (LAKE COUNTY DOT):

LAKE COUNTY DIVISION OF TRANSPORTATION

TRAFFIC SIGNAL SPECIAL PROVISIONS

Effective: January 1, 2013

All work and equipment performed and installed under this Contract shall be governed by and shall comply with:

SPECIFICATION	ADOPTED/DATED
The State of Illinois "Standard Specifications for Road and Bridge Construction" referred to as "Standard Specifications"	Latest Edition

Village of Round Lake
 FAU 201 Hart Road
 Section No.: 00-00025-00-FP
 County: Lake
 Contract No.: 63868

The State of Illinois "Manual on Uniform Traffic Control Devices for Streets and Highways," referred to as "MUTCD"	Latest Edition
The National Electrical Code referred to as "NEC"	Latest Edition
The National Electrical Manufacturers Association (All publications for traffic control items) referred to as "NEMA"	Latest Edition
The International Municipal Signal Association ("Official Wire & Cable Specifications Manual,") referred to as "IMSA"	Latest Edition
The Institute of Transportation Engineers Technical Report No. 1, (A Standard for Adjustable Face Vehicular Traffic Control Heads) referred to as "ITE"	Latest Edition
AASHTO "Standard Specifications" Structural Supports for Highway Signs, Luminaires, and Traffic Signals	Latest Edition
Supplemental Specifications and Recurring Special Provisions	Latest Edition

The following Traffic Signal Special Provisions supplement the above specifications, manuals, and codes. In case of conflict with any part or parts of said documents, these Special Provisions shall take precedence and shall govern.

The following terms and acronyms are used:

IDOT	Illinois Department of Transportation
District 1	IDOT District 1
LCDOT	The Lake County Division of Transportation
Engineer	The Resident Engineer
Traffic Engineer	The County Traffic Engineer – LCDOT

The intent of these Special Provisions is to prescribe the materials and construction methods commonly used in traffic signal installations. All material furnished shall be new. The locations and the details of all installations shall be indicated on the plans or as directed by the Engineer.

The work performed under this contract shall consist of furnishing and installing all traffic signal work as specified on the plans and as specified herein in a manner acceptable and approved by the Engineer.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

SUBMITTALS.

Revise Article 801.05 of the Standard Specifications to read:

General requirements include:

- a. All material approval requests shall be submitted at the preconstruction meeting.
- b. Product data and shop drawings shall be assembled by pay item. Only the top sheet of each pay item submittal will be stamped by the LCDOT Traffic Department with the review status, except shop drawings for mast arm pole assemblies will be stamped with the review status on each sheet.
- c. Four complete copies of the manufacturer's descriptive literatures and technical data for the traffic signal materials. If the literature contains more than one item, the Contractor shall indicate which item or items will be furnished.
- d. Seven complete copies of the shop drawings for the mast arm assemblies and poles, and the combination mast arm assemblies and poles showing, in detail, the fabrication thereof and the certified mill analyses of the materials used in the fabrication, anchor rods, and reinforcing materials.
- e. Partial or incomplete submittals will be returned without review.
- f. Certain non-standard mast arm poles and structures will require additional review from IDOT's Bureau of Bridges and Structures. Examples include special mast arms and non-standard length mast arm pole assemblies. The contractor shall account for the additional review time in their schedule.
- g. The contract number or permit number, project location/limits and corresponding pay code number must be on each sheet of correspondence, catalog cuts and mast arm poles and assemblies drawings.
- h. Where certifications and/or warranties are specified, the information submitted for approval shall include certifications and warranties. Certifications involving inspections, and/or tests of material shall be complete with all test data, dates, and times.
- i. After the Engineer reviews the submittals for conformance with the design concept of the project, the Engineer will stamp the drawings indicating their status as 'APPROVED', 'APPROVED AS CORRECTED', 'NOT APPROVED', or 'RESUBMIT'. Since the Engineer's review is for conformance with the design concept only, it is the Contractor's responsibility to coordinate the various items into a working system as specified. The

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

Contractor shall not be relieved from responsibility for errors or omissions in the shop, working, layout drawings, or other documents by the Engineer's approval thereof. The Contractor must still be in full compliance with contract and specification requirements.

- j. All submitted items reviewed and marked 'APPROVED AS CORRECTED', 'NOT APPROVED', or 'RESUBMIT' are to be resubmitted in their entirety, unless otherwise indicated within the submittal comments., with a disposition of previous comments to verify contract compliance at no additional cost to the contract.
- k. Exceptions to and deviations from the requirements of the Contract Documents will not be allowed. It is the Contractor's responsibility to note any deviations from Contract requirements at the time of submittal and to make any requests for deviations in writing to the Engineer. In general, substitutions will not be acceptable. Requests for substitutions must demonstrate that the proposed substitution is superior to the material or equipment required by the Contract Documents. No exceptions, deviations or substitutions will be permitted without the approval of the Engineer.

MARKING PROPOSED LOCATIONS

Revise "Marking Proposed Locations for Highway Lighting System" of Article 801.09 to read "Marking Proposed Locations for Highway Lighting System and Traffic Signals."

INSPECTION OF ELECTRICAL SYSTEMS

Add the following to Article 801.10 of the "Standard Specifications":

All cabinets, including temporary traffic signal cabinets, shall be assembled by an approved equipment supplier in IDOT District 1. LCDOT reserves the right to request that any controller and cabinet be tested at an IDOT District 1 approved equipment supplier's facility prior to field installation. Such testing will be at no extra cost to the contract. All permanent or temporary "railroad interconnected" controllers and cabinets, shall be new, built, tested and approved by the controller equipment vendor, in the vendor's IDOT District 1 approved facility, prior to field installation. The vendor shall provide the technical equipment and assistance as required by the Engineer to fully test this equipment.

MAINTENANCE AND RESPONSIBILITY

Revise Article 801.11 of the "Standard Specifications" to read:

- a. Existing traffic signal installations and/or any electrical facilities at locations included in this contract may be altered or reconstructed totally or partially as part of the work on this contract. The Contractor is hereby advised that all traffic control equipment presently installed at these locations may be the property of the State of Illinois, Department of Transportation, Division of Highways, County, Private Developer, or the Municipality in which it is located. Once the Contractor has begun any work on any

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

portion of the project, all traffic signals within the limits of this contract or those which have the pay item MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION, TEMPORARY TRAFFIC SIGNAL INSTALLATION, and/or MAINTENANCE OF EXISTING FLASHING BEACON INSTALLATION, shall become the full responsibility of the Contractor. The Contractor shall supply the Engineer and the County's Traffic Signal Maintenance Contractor two 24-hour emergency contact names and telephone numbers. The Contractor shall provide sufficient qualified personnel to respond to all notifications of malfunctions on a round-the-clock basis (24 hours a day, 7 days a week). The Contractor is required to keep a time and date log of all maintenance items, including the time of the initial report, the response time, and the time of final permanent repair. The Contractor shall provide this information to the Engineer, upon request.

- b. When the project has a pay item for MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION, TEMPORARY TRAFFIC SIGNAL INSTALLATION, and/or MAINTENANCE OF EXISTING FLASHING BEACON INSTALLATION, the Contractor must notify the Traffic Engineer at **(847) 377-7000** of their intent to begin any physical construction work on the project or any portion thereof. This notification must be a minimum of seven (7) working days prior to the start of construction to allow sufficient time for an inspection of the existing traffic signal installation(s) and the transfer of maintenance to the Contractor. If work is started prior to the inspection, maintenance of the traffic signal installation(s) will be immediately transferred to the Contractor without an inspection. The Contractor shall then become responsible for repairing or replacing all equipment that is not operating properly or is damaged at no cost to the owner of the traffic signal. Final repairs to or the replacement of damaged equipment must meet the approval of the Engineer at the time of final inspection or the traffic signal installation will not be accepted.
- c. Contracts that don't include traffic signal installations or modifications, but do include pay items for milling or pavement patching which may result in the destruction of traffic signal loops, do not require maintenance transfer. These contracts do require a notification of intent to work and an inspection. A minimum of seven (7) working days prior to the loop removal, the Contractor shall notify the Traffic Engineer at **(847) 377-7000**, at which time arrangements will be made to adjust the traffic controller timing to compensate for the absence of detection.
- d. The Contractor is advised that the existing and/or temporary traffic signal installation must remain in operation during all construction stages, except for the most unavoidable down time. Any plan to shutdown the traffic signal installation for a period exceeding fifteen (15) minutes must receive prior approval from the Engineer. Approval to shutdown the traffic signal installation will only be granted during the hours of 9:00 A.M. to 3:00 P.M. on weekdays. Shutdowns will not be allowed during inclement weather, weekends or holiday periods.

Village of Round Lake
 FAU 201 Hart Road
 Section No.: 00-00025-00-FP
 County: Lake
 Contract No.: 63868

- e. The Contractor shall be fully responsible for the safe and efficient operation of the traffic signals. Any inquiry, complaint or request by the Division, the County's Traffic Signal Maintenance Contractor or the public, shall be investigated and repairs started. The Contractor shall restore service and complete permanent repairs in accordance with the following Repair Timetable. Failure to provide this service will result in liquidated damages of \$500 per day per occurrence. The Traffic Engineer reserves the right to assign any work not completed within this timeframe to the County's Traffic Signal Maintenance Contractor. All costs associated to repair this uncompleted work shall be the responsibility of the Contractor. Failure to pay these costs to the Traffic Signal Maintenance Contractor within one month after the incident will result in additional liquidated damages of \$500 per month per occurrence. Unpaid bills will be deducted from the cost of the Contract. The County's Traffic Signal Maintenance Contractor may inspect any signaling device on the Division's highway system at any time without notification.

Immediately after performing any work related to a signal maintenance item (troubleshooting, temporary repair, permanent repair, etc.) the Contractor shall contact the Lake County PASSAGE Transportation Management Center (TMC) at **(847) 377-7000**.

Unless specifically stated to the contrary, all items shall be repaired within the time frame described in the Repair Timetable. The times listed are noncumulative. Any repairs not specifically covered in the Repair Timetable, or described elsewhere, shall be completed within a time frame matching the most similar line item in the Repair Timetable.

REPAIR TIMETABLE
 (non cumulative)

<u>ITEM</u>	<u>RESPONSE TIME</u>	<u>SERVICE RESTORATION</u>	<u>PERMANENT REPAIRS</u>
KNOCKDOWNS/FAILURE/DAMAGE:			
Cabinet	1 hr	24hrs	2 wks
Controller (Local or Master)	1 hr	24hrs	2 wks
Detector Loop	1 hr	n.a.	3 wks
Loop-Detector/Amplifier	1 hr	4 hrs	2 wks
MVP Sensor	1 hr	4 hrs	2 wks
PTZ Camera	2 hrs	48 hrs	2 wks
Detector Interface Card/Mini Hub	1 hr	4 hrs	2 wks
Modem	2 hrs	NWD	2 wks
Load Switch	1 hr	2 hrs	2 hrs
Signal Head/Lenses	1 hr	2 hrs	NWD
Pole/Mast Arm	1 hr	2 hrs	ENG
Cabling/Conduit	1 hr	4 hrs	ENG

Village of Round Lake
 FAU 201 Hart Road
 Section No.: 00-00025-00-FP
 County: Lake
 Contract No.: 63868

Interconnect/Communication	1 hr	NWD	ENG
Graffiti/Advertising	NWD	NWD	NWD
Telemetry, Electrical	1 hr	2 hrs	NWD
Ethernet Switches/Video Encoders	1 hr	48 hrs	2 wks
Highway Advisory Radio (HAR)	1 hr	48 hrs	2 wks
Indicators/switches/LEDs/displays	NWD	n.a.	2 wks
Outages not covered elsewhere	1 hr	2 hrs	NWD
Filter/Cleanliness/fans/thermostat	NWD	NWD	n.a.
Misalignment (conflicting)	1 hr	2 hrs	NWD
Misalignment (non-conflicting)	2 hrs	4 hrs	NWD

COMPLAINTS/CALLS/ALARMS:

Timing/Phasing/Programming	1 hr	2 hrs	ENG
Coordination Alarm/Cycle Fail	NWD	ENG	ENG
Controller Alarm/Status Change	1 hr	NWD	1 wk
Detector Alarm/Status change	NWD	NWD	ENG
CMU Flash/Local Flash	1 hr	2 hrs	1 wk
Door Open/Maint. Req.	2 hrs	4 hrs	NWD

LEGEND: hr=hour, hrs=hours, NWD=next working day, wk=week, wks=weeks, ENG=acceptable to Engineer, days=calendar days, n.a.=not applicable

LIQUIDATED DAMAGES FOR UNTIMELY WORK

A primary concern of LCDOT is to maintain a safe and efficient roadway for the public. Therefore, the Contractor shall proceed with the traffic signal work as soon as conditions and project staging permit. If in the opinion of the Engineer construction conditions are suitable for traffic signal work, and the Contractor has not yet begun the traffic signal work, the Engineer shall notify the Contractor to proceed. The Contractor shall begin the traffic signal work within seven (7) calendar days after notification to proceed. The Contractor shall continue to prosecute the traffic signal work until completion, or until he can no longer proceed due to conditions beyond his control. The Contractor shall notify the Engineer of any conditions impeding and/or delaying his prosecution of the work. Failure by the Contractor to proceed with the traffic signal work as specified herein shall result in liquidated damages of **\$500.00** per calendar day per occurrence.

DAMAGE TO TRAFFIC SIGNAL SYSTEM

Revise Article 801.12(b) of the "Standard Specifications" to read:

Any damaged equipment or equipment not operating properly from any cause whatsoever shall be repaired and/or replaced with new equipment meeting current traffic signal specifications and

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

provided by the Contractor at no additional cost to the Contract and/or owner of the traffic signal system, to the satisfaction of the Engineer. Final repairs or replacement of damaged equipment must meet the approval of the Engineer prior to or at the time of final inspection; otherwise the traffic signal installation will not be accepted. Cable splices outside the controller cabinet shall not be allowed.

Automatic Traffic Enforcement equipment, such as Red Light Enforcement cameras, detectors, and peripheral equipment, damaged or not operating properly from any cause whatsoever, shall be the responsibility of the municipality or the Automatic Traffic Enforcement company per Permit agreement.

TRAFFIC SIGNAL INSPECTION (TURN-ON)

Revise Article 801.15(b) of the "Standard Specifications" to read:

It is LCDOT's intent to have all electric work completed and the equipment field-tested by the vendor, prior to LCDOT's "turn-on" field inspection. The Contractor must have all traffic signal work completed and the electrical service installation connected by the utility company prior to requesting an inspection and "turn-on" of the traffic signal installation. In the event the Traffic Engineer determines that the work is not complete and that the inspection will require more than two (2) hours to complete, the inspection shall be canceled and the Contractor will be required to reschedule at another date.

The Contractor may request a "turn-on" and inspection of the completed traffic signal installation at each separate location. This request must be made to the Traffic Engineer at **(847) 377-7000** a minimum of seven (7) working days prior to the time of the requested inspection. LCDOT will not grant a field inspection until the Contractor provides notification that the equipment has been field tested, and the intersection is operating according to contract requirements.

Signal indications being tested shall match the lane configurations and markings at the intersection. If any conflicting signal indications are visible to motorist or pedestrians while testing, Contractor shall be responsible to provide police officer(s) to direct traffic. In addition, the Contractor shall provide a representative from the control equipment vendor's office to attend the traffic signal inspection for both permanent and temporary traffic signal "turn-ons".

~~Upon demonstration that the signals are operating properly and that all work has been completed in accordance with the contract and to the satisfaction of the Traffic Engineer, the Traffic Engineer will then allow the signals to be placed in continuous operation. The Agency that is responsible for the maintenance of each traffic signal installation will reassume the traffic signal maintenance upon acceptance by the Traffic Engineer.~~

The Lake County Division of Transportation requires the following from the Contractor at Traffic Signal "turn-ons":

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

1. One (1) set of as-built signal plans.
2. One (1) letter from the electrical contractor certifying that all material and equipment provided and installed as part of the project is in accordance with the approved catalog cuts and shop drawings.
3. A knowledgeable representative of the controller equipment supplier shall be present at the traffic signal "turn-on". The representative shall be knowledgeable concerning the cabinet design and the controller functions.
4. One (1) CD or electronic version of the cabinet box prints.
5. One (1) copy of the operation and service manuals for the signal controller and the associated control equipment.
6. Five (5) copies (11" x 17") of the cabinet wiring diagrams.
7. Five (5) copies of the traffic signal installation cable log.
8. All manufacturer and contractor warranties and guarantees required by Article 801.14.

Acceptance of the traffic signal equipment by LCDOT shall be based on the inspection results at the traffic signal "turn-on". If approved, the traffic signal acceptance shall be given verbally at the "turn-on" inspection, followed by written correspondence from the Traffic Engineer. The Contractor shall be responsible for all traffic signal equipment and associated maintenance thereof until LCDOT acceptance is granted. Any "punch list" work remaining after the installation is accepted shall be completed within thirty (30) calendar days of the acceptance date. If this work is not completed within thirty days, LCDOT reserves the right to have the work completed by others at the Contractor's expense. This cost will be in addition to Liquidated Damages for Untimely Work.

The Contractor shall furnish all equipment and/or parts to keep the traffic signal installation operating.

All cost of work and materials required to comply with the above requirements shall be included in the pay item bid prices, under which the subject materials and signal equipment are paid, and no additional compensation will be allowed. Materials and signal equipment not complying with the above requirements will be subject to removal and disposal at the Contractor's expense.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

LOCATING UNDERGROUND FACILITIES

Revise Section 803 of the "Standard Specifications" to read:

Contractor requests for equipment locates will be granted only once prior to the start of the contract. Additional requests shall be at the expense of the Contractor. The location of underground traffic facilities does not relieve the Contractor of their responsibility to repair any item(s) damaged during the construction, at his/her own expense.

Locate requests should be directed to LCDOT's Traffic Signal Maintenance Contractor or to the LCDOT Traffic Engineering Department at (847) 377-7000.

The exact location of all utilities shall be field verified by the Contractor before the installation of any components of the traffic signal system. For locations of utilities call J.U.L.I.E. at **1-800-892-0123**. For the locations of some utilities, other Agencies or Municipalities may need to be contacted.

MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION

Revise Section 850 of the "Standard Specifications" to read:

The Contractor shall not be required to pay the energy charges for the operation of the existing traffic signal installation. Full maintenance responsibility shall start as soon as the Contractor begins any physical work on the Contract or any portion thereof.

The Contractor shall have electricians on staff with IMSA Level II certification to provide signal maintenance.

This item shall include maintenance of all traffic signal equipment at the intersection, including cameras, emergency vehicle pre-emption equipment, master controllers, telephone service installations, communication equipment, communication cables and conduits to adjacent intersections.

The maintenance shall be according to Article 850 of the "Standard Specifications", and the following contained herein.

The Contractor shall check all controllers every two (2) weeks, which will include visually inspecting all timing intervals, relays, detectors, and pre-emption equipment to ensure that they are functioning properly. This item includes, as routine maintenance, all portions of the emergency vehicle pre-emption system. The Contractor shall maintain in stock at all times a sufficient amount of materials and equipment to provide effective temporary and permanent repairs.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

The Contractor shall provide immediate corrective action when any part or parts of the system fail to function properly. Two (2) far side heads facing each approach shall be considered the minimum acceptable signal operation pending permanent repairs. When repairs at a signalized intersection require that the controller be disconnected, and power is available, the Contractor shall place the traffic signal installation on flashing operation. The signals shall flash RED for all directions unless a different indication has been specified by the Engineer. The Contractor shall be required to place at least 1 STOP sign (R1-1-36) at each approach of the intersection as a temporary means of regulating traffic. At approaches where a yellow flashing indication is necessary, as directed by the Engineer, STOP signs will not be required. The Contractor shall furnish and equip all their signal maintenance vehicles with a sufficient number of STOP signs as specified herein. The Contractor shall maintain a sufficient number of spare STOP signs in stock at all times to replace those which may be damaged or stolen.

The Contractor shall provide the Engineer with a 24-hour telephone number for traffic signal maintenance. The Contractor, or his representative, shall be available on a 24-hour basis to respond to emergency calls by the Traffic Engineer or other parties.

Traffic signal equipment which is lost or not returned to the County for any reason shall be replaced with new equipment meeting the requirements of these Specifications.

The Contractor shall respond to all emergency calls from the County or others within one hour after notification and provide immediate corrective action. When equipment has been damaged or becomes faulty beyond repair, the Contractor shall replace it with new and identical equipment. The cost of furnishing and installing the replaced equipment shall be borne by the Contractor at no additional charge to the County. The Contractor may institute action to recover damages from a responsible third party. If at any time the Contractor fails to perform all work as specified herein to keep the traffic signal installation in proper operating condition or if the Engineer cannot contact the Contractor's designated personnel, the Engineer shall have the County's Traffic Signal Maintenance Contractor perform the maintenance work required. The County's Traffic Signal Maintenance Contractor shall bill the Contractor for the total cost of the work. The Contractor shall pay this bill within thirty (30) days of the date of receipt of the invoice or the cost of such work will be deducted from the amount due the Contractor. The Contractor shall allow the County's Traffic Signal Maintenance Contractor to make reviews of the existing traffic signal installation that has been transferred to the Contractor for maintenance.

The Engineer may require the Contractor to transfer maintenance of a signal back to the County's Traffic Signal Maintenance Contractor (or other electrical contractor) for a short time. This may become necessary due to other signal projects in the area, or if the County needs to perform work at the signal. Any costs incurred by the Contractor for maintenance transfer inspections of this type shall be included in cost of pay item MAINTENANCE OF EXISTING

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

TRAFFIC SIGNAL INSTALLATION.

Any proposed activity in the vicinity of a highway-rail grade crossing must adhere to the guidelines set forth in the current edition of the Manual on Uniform Traffic Control Devices (MUTCD) regarding work in temporary traffic control zones in the vicinity of highway-rail grade crossings which states that lane restrictions, flagging, or other operations shall not create conditions where vehicles can be queued across the railroad tracks. If the queuing of vehicles across the tracks cannot be avoided, a uniformed law enforcement officer or flagger shall be provided at the crossing to prevent vehicles from stopping on the tracks, even if automatic warning devices are in place.

Basis of Payment. This work shall be paid for at the contract unit price each for MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION.

TEMPORARY TRAFFIC SIGNAL INSTALLATION

Add the following to Section 890 of the "Standard Specifications":

Only an approved equipment vendor will be allowed to assemble the temporary traffic signal cabinet. Also, an approved equipment vendor shall assemble and test a temporary railroad traffic signal cabinet. (Refer to the "Inspection of Electrical Systems" specification) A representative of the approved control equipment vendor shall be present at the temporary traffic signal turn-on inspection.

Only controllers compatible with "Centracs" software (NTCIP) or "Aries" software, currently in use by LCDOT, will be approved for use at temporary signal locations. Controller software compatibility requirements are based upon the controller's location in the communication system, and shall be as shown on the plans. All controllers used for temporary traffic signals shall be fully-actuated NEMA microprocessor based with RS232 data entry ports compatible with existing monitoring software, installed in NEMA TS-1 or TS-2 cabinets with 8 phase back panels, capable of supplying 255 seconds of cycle length and individual phase length settings up to 99 seconds. On projects with one lane open and two way traffic flow, such as bridge deck repairs, the temporary bridge signal controller shall be capable of providing an adjustable all red clearance setting of up to 30 seconds in length. All controllers used for temporary traffic signals shall meet or exceed the requirements of Section 857 of the "Standard Specifications" with regards to internal time base coordination and preemption.

All temporary traffic signal cabinets shall have a closed bottom made of aluminum alloy. The bottom shall be sealed along the entire perimeter of the cabinet base to ensure a water, dust and insect-proof seal. The bottom shall provide a minimum of two (2) 4-inch diameter holes to run the electric cables through. The 4-inch diameter holes shall have a bushing installed to protect the electric cables and shall be sealed after the electric cables are installed.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

The stand which supports the temporary traffic signal cabinet shall be constructed of lumber and plywood that has been pressure-treated to protect against rot, mold, and insects.

Grounding shall be provided for the temporary traffic signal cabinet meeting or exceeding the applicable portions of the National Electrical Code, Section 806 of the "Standard Specifications" and the "Grounding of Traffic Signal Systems" section of these special provisions.

All traffic signal head sections shall be twelve (12) inches. Traffic signal sections shall be LED with expandable view, unless otherwise approved by the Engineer. The temporary traffic signal heads shall be placed as indicated on the temporary traffic signal plan or as directed by the Traffic Engineer. The Contractor shall furnish enough cable slack to relocate heads to any position on the span wire or at locations illustrated on the plans for construction staging. The temporary traffic signal shall remain in operation during all signal head relocations. Each temporary traffic signal head shall have its own cable from the controller cabinet to the signal head.

All temporary traffic signal installations shall have vehicular detection installed as shown on the plans or as directed by the Engineer. Pedestrian push buttons shall be provided for all pedestrian signal heads/phases as shown on the plans or as directed by the Engineer. All approaches shall have vehicular detection provided by vehicle detection system as shown on the plans or as directed by the Engineer. The Contractor shall install, wire, and adjust the alignment of the video vehicle detection system in accordance to the manufacturer's recommendations and requirements. The Contractor shall be responsible for adjusting the alignment of the video vehicle detection system for all construction staging changes and for maintaining proper alignment throughout the project. A representative of the approved control equipment vendor shall be present and assist the contractor in setting up and maintaining the video vehicle detection system. An in-cabinet video monitor shall be provided with all video vehicle detection systems and shall be included in the item Temporary Traffic Signal Installation. When called for in the plans, the UPS cabinet shall be mounted to the temporary traffic signal cabinet and meet the requirements of UNINTERRUPTABLE POWER SUPPLY of these Special Provisions.

For temporary traffic signal installations within closed loop system(s), the controller shall be compatible with the existing traffic signal system master controller. The existing system interconnect is to be maintained as part of the Temporary Traffic Signal Installation specified on the plan. The interconnect shall be installed into the temporary controller cabinet as per the notes or details on the plans. Refer to the INTERRUPTION OF COMMUNICATION requirements described earlier. All labor and equipment required to install and maintain the existing interconnect shall be included in the cost of the item TEMPORARY TRAFFIC SIGNAL

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

INSTALLATION.

All emergency vehicle priority equipment (light detectors, light detector amplifiers, confirmation beacons, etc.) as shown on the temporary traffic signal plans shall be provided by the Contractor. It shall be the Contractor's responsibility to contact the municipality or fire district to verify the brand of emergency vehicle priority equipment to be installed prior to the contract bidding. The equipment must be completely compatible with all components of signal equipment currently in use by the County. All light operated systems shall operate at a uniform rate of 14.035 hz \pm 0.002, or as otherwise required by the Engineer. All labor and material required to install and maintain the Emergency Vehicle Priority system shall be included in the cost of the item TEMPORARY TRAFFIC SIGNAL INSTALLATION.

When directed by the Engineer, this item shall also include operational items such as: controller database changes, timing changes, activation/deactivation of phases, relocation of signal heads, relocation / reconfiguration of detectors (microwave and/or video), and bagging / unbagging signal heads. On temporary traffic signal installations with detector loops, coilable non-metallic conduit shall be used for detector loop raceways from the saw-cut to 10 feet up the wood pole, unless otherwise shown on the plans. Coilable non-metallic conduit shall meet the requirements of NEC Article 343 and meet the requirements of COILABLE NON-METALLIC CONDUIT of the Special Provisions.

All existing street name and intersection regulatory signs shall be removed from existing poles and relocated to the temporary signal span wire. If new mast arm assemblies and posts are specified for the permanent signals, the signs shall be relocated to the new equipment at no extra cost.

The Contractor shall not be required to pay the energy charges for the operation of the existing traffic signal installation. If the installation replaces an existing signal, the Contractor shall not be required to pay the energy charges for the operation of the temporary traffic signal. The Contractor shall pay the energy charges for all other temporary traffic signal installations.

The Contractor shall furnish all control equipment for the temporary traffic signals(s) unless otherwise stated in the plans. On projects with multiple temporary traffic signal installations, all controllers shall be of the same manufacturer and model number with current software installed. Maintenance shall meet the requirements of the "Standard Specifications" and the "Maintenance of Existing Traffic Signal Installation" section of these special provisions. Maintenance of temporary signals and of the existing signals shall be included in the cost of this item. When temporary traffic signals are to be installed at locations where existing signals are presently operating, the Contractor shall be fully responsible for the maintenance of the existing signal installation as soon as he begins any physical work on any portion of the project. Maintenance responsibility of the existing signals shall be incidental to the item TEMPORARY

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

TRAFFIC SIGNAL INSTALLATION. In addition, a minimum of seven (7) days prior to assuming maintenance of the existing traffic signal installation(s) under this contract, the Contractor shall contact the Traffic Engineer **(847) 377-7000** to request an inspection of the installation(s).

Temporary Traffic Signals for bridge projects shall follow the State Standards, "Standard Specifications", LCDOT Traffic Signal Special Provisions, and any plans for Bridge Temporary Traffic Signals included in the plans. The installation shall meet the above requirements for **TEMPORARY TRAFFIC SIGNAL INSTALLATION**. In addition, all electric cable shall be aerially suspended, at a minimum height of 18 feet, on temporary wood poles (Class 5 or better) of 45 feet minimum height. The signal heads shall be span-wire-mounted or bracket-mounted to the wood pole or as directed by the Engineer. The Controller cabinet shall be mounted to the wood pole or as directed by the Engineer. All approaches for temporary traffic signals for bridge projects shall have microwave vehicle sensors or video vehicle detection, as shown on the plans or as approved by the Engineer.

Basis of Payment: This work shall be paid for at the contract unit price each for **TEMPORARY TRAFFIC SIGNAL INSTALLATION** which shall include all costs for the installation, vehicular detection system, UPS, modification, maintenance, operational items, complete removal of the temporary traffic signal, and all material required to complete the work.

REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT

Add the following to Article 895.05 of the "Standard Specifications":

The traffic signal equipment, which is to be removed and will become the property of the Contractor, shall be disposed of by the Contractor outside the right-of-way at his/her own expense.

The Contractor shall safely store and arrange for delivery of all equipment that will remain the property of LCDOT. The Contractor shall deliver, unload and stack the equipment at the owner's facility, as directed by the Engineer, within 30 days of removing it from the traffic signal installation. The Contractor shall provide three (3) copies of a list of equipment that is to remain the property of LCDOT including model and serial numbers where applicable. The Contractor shall also provide a copy of the contract plan or special provisions showing the quantities and type of equipment to be delivered. Controllers and peripheral equipment from the same location shall be boxed together (equipment from different locations may not be mixed) and all boxes and controller cabinets shall be clearly marked or labeled with the location from which they were removed. The Contractor shall be responsible for the condition of the traffic signal equipment from the time of removal until the acceptance of a receipt written by the owner indicating that the items have been returned in good condition.

Traffic signal equipment which is lost or not returned to the County for any reason shall be replaced with new equipment meeting the requirements of these Specifications.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

RESTORATION OF WORK AREA

Add to Section 801 of the "Standard Specifications":

Restoration of the traffic signal work area shall be included in the related pay item such as foundation, conduit, handhole, trench and backfill, etc. and no extra compensation shall be allowed. All roadway surfaces such as shoulders, medians, sidewalks, pavement, etc. shall be restored to match the previously existing conditions. All damage to mowed lawns shall be replaced with an approved sod, and all damage to unmowed fields shall be seeded, in accordance with Section 250 and 252 of the "Standard Specifications" respectively.

CABINET NEATNESS

The Contractor shall assure that all wiring and peripheral equipment in any new traffic signal cabinet is in a neat and orderly fashion that is acceptable to the Engineer. This applies to controller cabinets, master cabinets, railroad cabinets, communication cabinets, electrical service cabinets, or any other new cabinet called for in the project plans.

All conduit entrances into the cabinet shall be sealed with a pliable waterproof material. Electrical cables inside the cabinet shall be neatly trained along the base and back of the cabinet. Each conductor shall be connected individually to the proper terminal, and the spare conductors shall be bound into a neat bundle. All cables, including those for signals, vehicle detection, pushbuttons, emergency vehicle preemption, video transmission, and communication shall be neatly arranged and bundled within the cabinet to the satisfaction of the Engineer. Each cable shall be marked with an identification number which corresponds to the number and description on the cabinet cable log.

In the case of an existing cabinet that is being modernized or modified, the new cables being installed shall be trained, bundled and labeled to the satisfaction of the Engineer. When working inside an existing cabinet, the Contractor shall minimize disturbance to existing cables and cabinet wiring. Any existing cables and cabinet wiring disturbed by the Contractor shall be re-trained, bundled, and/or labeled to the satisfaction of the Engineer.

The County shall not accept maintenance of the traffic signal installations until the requirements of this specification are satisfied.

VENDOR REPRESENTATION

Under this provision, the Engineer reserves the right to request the equipment vendor be present at the activation of new traffic equipment. Equipment covered under this provision includes signal heads, cabinets, controllers, amplifiers, preemption, video detection/monitoring, communication/transmission, fiber-optic/telemetry, radio, microwave, infrared, illuminated signs, streetlights, push buttons, lighted crosswalks, uninterruptable power supplies, and any other

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

new equipment being installed and activated.

This provision is in addition to the requirement contained herein that the Contractor provide a representative from the control equipment vendor to attend the traffic signal inspection for both permanent and temporary traffic signal "turn-ons".

Any costs associated with equipment vendor representation shall not be paid for separately, but shall be included in the cost of the associated traffic equipment being activated. Any unforeseen costs incurred by the Contractor to provide this representation shall not be the responsibility of the County.

INTERRUPTION OF COMMUNICATION

The interruption of communication with County equipment shall be kept to an absolute minimum. This includes communication such as controller telemetry, video transmission, camera control signals, Highway Advisory Radio, wireless interconnect, telephone (POTS/ISDN/DSL), high speed Internet, or any other County communication equipment. This provision applies to cable types including copper, multimode fiber optic, singlemode fiber optic, telephone cables, Internet cables, or any other cable used by the County to monitor and maintain its various signal and ITS equipment.

The contractor shall plan ahead, and shall stage his construction work accordingly, so that he can interrupt communication, and then restore communication, with as little down time as possible. For example, when a section of existing interconnect is being relocated, the new handholes and conduits should be installed prior to disconnecting the interconnect cable. The interconnect cable can then be disconnected, pulled out of the existing conduit, pulled through the new conduit, and re-connected. In addition, when an existing fiber optic cable is to be re-used, the contractor shall be prepared to immediately replace any fiber splices and/or terminations that become damaged.

Prior to disconnecting any LCDOT communication link, the contractor shall contact the Traffic Engineer for approval of his planned construction method.

ELECTRIC SERVICE INSTALLATION

Revise Section 805 of the "Standard Specifications" to read:

Description. This work shall consist of all materials and labor required to install, modify, or extend the electric service installation. All installations shall meet the requirements of the details in the "IDOT District 1 Standard Traffic Signal Design Details" and applicable portions of the Specifications.

General. The electric service installation shall be the electric service disconnecting means and it

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

shall be identified as suitable for use as service equipment.

The electric utility contact information is noted on the plans and represents the current information at the time of contract preparation. The Contractor must request in writing for service and/or service modification within 10 days of contract award and must follow-up with the electric utility to assure all necessary documents and payment are received by the utility. The Contractor shall forward copies of all correspondence between the contractor and utility company to the Engineer of Traffic.

Materials.

- a. General. The completed control panel shall be constructed in accordance with UL Std. 508, Industrial Control Panel, and carry the UL label. Wire terminations shall be UL listed.
- b. Enclosures. All electrical service enclosures shall be UL 50, single door design, fabricated from Type 5052 H-32 aluminum or stainless steel. All seams shall be continuous welded and ground smooth, and the cabinet shall be sized to adequately house all required components with extra space for arrangement and termination of wiring. Enclosures shall meet the following additional requirements:
 1. Pole Mounted Cabinet. The cabinet shall be NEMA Type 4X. Stainless steel screws and clamps shall secure the cover and assure a watertight seal. The cover shall be removable by pulling the continuous stainless steel hinge pin. The cabinet shall have an oil-resistant gasket and a lock kit shall be provided with an internal O-ring in the locking mechanism assuring a watertight and dust-tight seal. A minimum size of 14-inches high, 9-inches wide and 8-inches deep is required. The cabinet shall be channel mounted to a wooden utility pole using assemblies recommended by the manufacturer.
 2. Ground Mounted Cabinet. The cabinet shall be NEMA Type 3R with back panel. The cabinet frame and door shall be 0.125-inch thick, the top 0.250-inch thick, and the bottom 0.500-inch thick. The door and door opening shall be double flanged. The door shall be approximately 80% of the front surface, with a full-length tamperproof stainless steel .075-inch thick hinge bolted to the cabinet with stainless steel carriage bolts and nylock nuts. The locking mechanism shall be slam-latch type with a keyhole cover. A minimum size of 40-inches high, 16-inches wide, and 15-inches deep is required. The cabinet shall be mounted upon a square Type A concrete foundation as indicated on the plans. The foundation is paid for separately.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

- c. Surge Protector. Overvoltage protection, with LED indicator, shall be provided for the 120-volt load circuit by the means MOV and thermal fusing technology. The response time shall be <5n seconds and operate within a range of -40C to +85C. The surge protector shall be UL 1449 Listed.
 - d. Circuit Breakers. Circuit breakers shall be standard UL listed molded case, thermal-magnetic bolt-on type, with trip-free indicating handles. 120-volt circuit breakers shall have an interrupting rating of not less than 65,000 rms symmetrical amperes. Unless otherwise indicated, the main disconnect circuit breaker for the traffic signal controller shall be rated 60 amperes, 120 V and the auxiliary circuit breakers shall be rated 10 amperes, 120 V.
 - e. Fuses, Fuseholders and Power Indicating Light. Fuses shall be small-dimensional cylindrical fuses of the dual element time-delay type. The fuses shall be rated for 600 V AC and shall have a UL listed interrupting rating of not less than 10,000 rms symmetrical amperes at rated voltage. The power indicating light shall be LED type with a green colored lens and shall be energized when electric utility power is present.
 - f. Ground and Neutral Bus Bars. A single copper ground and neutral bus bar, mounted on the equipment panel shall be provided. Ground and neutral conductors shall be separated on the bus bar. Compression lugs, plus 2 spare lugs, shall be sized to accommodate the cables with the heads of the connector screws painted green for ground connections and white for neutral connections.
 - g. Utility Services Connection. The Contractor shall notify the Utility Company marketing representative a minimum of 30 working days prior to the anticipated date of hook-up. This 30-day advance notification will begin only after the Utility Company marketing representative has received service charge payments from the Contractor. Prior to contacting the Utility Company for service connection, the service installation controller cabinet and cable must be installed for inspection by the Utility Company.
-
- h. Ground Rod. Ground rods shall be copper-clad steel, a minimum of 10-feet in length, and 3/4-inch in diameter. Ground rod resistance measurements to ground shall be 25 ohms or less. If necessary additional rods shall be installed to meet resistance requirements at no additional cost to the contract.

Installation

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

- a. General. The Contractor shall confirm the orientation of the traffic service installation and its door side with the Engineer, prior to installation. All conduit entrances into the service installation shall be sealed with a pliable waterproof material.
- b. Pole Mounted. Brackets designed for pole mounting shall be used. All mounting hardware shall be stainless steel. Mounting height shall be as noted on the plans or as directed by the Engineer.
- c. Ground Mounted. The service installation shall be mounted plumb and level on the foundation and fastened to the anchor bolts with hot-dipped galvanized or stainless steel nuts and washers. The space between the bottom of the enclosure and the top of the foundation shall be caulked at the base with silicone.

The service installation shall be paid for at the contract unit price each for SERVICE INSTALLATION of the type specified which shall be payment in full for furnishing and installing the service installation complete. The type A foundation which includes the ground rod shall be paid for separately. SERVICE INSTALLATION, POLE MOUNTED shall include the 3/4-inch grounding conduit, ground rod, and pole mount assembly. Any changes by the utility companies shall be approved by the Engineer and paid for as an addition to the contract according to Article 109.05 of the "Standard Specifications".

GROUNDING OF TRAFFIC SIGNAL SYSTEMS

Revise Section 806 of the "Standard Specifications" to read:

General. All traffic signal systems, equipment and appurtenances shall be properly grounded in strict conformance with the NEC. See "IDOT District One Standard Traffic Signal Design Details" for additional information.

The grounding electrode system shall include a ground rod installed in all foundations, and the service installation. An additional ground rod will be required at locations where measured resistance to ground exceeds 25 ohms. Ground rods are included in the associated pay items and will not be paid for separately. Testing shall be according to Article 801.13.

- a) ~~The grounded conductor (neutral conductor) shall be white color-coded. This conductor shall be bonded to the equipment-grounding conductor only at the Electric Service Installation. All power cables shall include one neutral conductor of the same size.~~
- b) The equipment-grounding conductor shall be green color-coded. The following is in addition to Article 1087.01 of the "Standard Specifications".
 - 1) Equipment-grounding conductors shall be XLP insulated No. 6, unless otherwise noted on the plans, and bonded to the grounded conductor (neutral conductor) only at the

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

electric service installation. The Earth shall not be used as the equipment-grounding conductor, and no splices shall be allowed in the cable between ground rods. The equipment-grounding conductor is paid for separately.

- 2) Equipment-grounding conductors shall be bonded, using a UL listed grounding connector, to all traffic signal mast arm poles, traffic signal posts, pedestrian posts, pull boxes, handhole frames and covers and other metallic enclosures throughout the traffic signal wiring system, except where noted herein. A UL listed electrical joint compound shall be applied to all conductors' terminations, connector threads and contact points.
 - 3) All metallic and non-metallic raceways containing traffic signal circuit runs shall have a continuous equipment-grounding conductor, with the following exceptions: Raceways containing only detector loop lead-in circuits, circuits under 50 volts and/or fiber optic cable will not be required to include an equipment-grounding conductor.
- c) The grounding electrode conductor shall be similar to the equipment-grounding conductor in color coding (green) and size. The grounding electrode conductor is used to connect the ground rod to the equipment-grounding conductor and is bonded to ground rods via exothermic welding, UL listed pressure connectors, UL listed clamps or other UL approved listed means.

GROUNDING EXISTING HANDHOLE FRAME AND COVER

This work shall consist of all materials and labor required to bond the equipment-grounding conductor to the existing handhole frame and handhole cover. All installations shall meet the requirements of the details in the "IDOT District One Standard Traffic Signal Design Details" and applicable portions of the Specifications.

The equipment-grounding conductor shall be bonded to the handhole frame and to the handhole cover. Two (2) 1/2-inch diameter x 1 1/4-inch long hex-head stainless steel bolts, spaced 1.75-inches apart center-to-center shall be fully welded to the frame and to the cover to accommodate a heavy duty Listed grounding compression terminal (Burndy type YGHA or approved equal). The grounding compression terminal shall be secured to the bolts with stainless steel split-lock washers and nylon-insert locknuts.

Welding preparation for the stainless steel bolt hex-head to the frame and to the cover shall include thoroughly cleaning the contact and weldment area of all rust, dirt and contaminants. The Contractor shall assure a solid strong weld. The welds shall be smooth and thoroughly cleaned of flux and spatter. The grounding installation shall not affect the proper seating of the cover when closed.

Mechanical connections to the frame and cover may be approved in lieu of the listed welding

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

procedures. The contractor shall submit a detailed plan indicating the proposed connectors and installation procedures for review and approval by the Engineer prior to the start of any work on this item.

The grounding cable shall be paid for separately.

Basis of Payment: This work shall be paid for at the contract unit price each for GROUNDING EXISTING HANDHOLE FRAME AND COVER, which shall be payment in full for grounding one handhole complete, regardless of the type of handhole or its location.

UNDERGROUND CONDUIT

The conduit shall meet the requirements of Section 810 of the "Standard Specifications", except for the following:

Delete Article 810.01 of the "Standard Specifications" and add the following:

Description. This item shall consist of furnishing and installing galvanized steel conduit, fittings and accessories in the ground, either pushed, trenched, plowed, or directionally bored, with fittings complete as specified herein and as shown on the Contract drawings.

Add the following to Article 810.04 of the "Standard Specifications":

Pavement, driveways, and curbs shall not be removed to install electrical conduits. All buried conduits shall be placed at a minimum depth of 30 inches, except under railroad tracks, where the minimum depth shall meet the written requirements of the railroad company. All conduit couplings shall be threaded. Conduits terminating in junction and pull boxes shall be terminated with galvanized steel bushings.

When empty conduit is installed for future traffic signal interconnects(s), the Contractor shall provide a pull line within the conduit.

Revise Article 810.07 of the "Standard Specifications" to read:

Basis of Payment: This work will be paid for at the contract unit price per foot for UNDERGROUND CONDUIT of the type and size specified, which price shall be payment in full for furnishing and installing the conduit either pushed, trenched, plowed, or directionally bored with fittings, complete. Trenching, backfilling and area restoration are included in the cost of this item.

CONCRETE FOUNDATIONS

Add the following to Article 878.03 of the "Standard Specifications":

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

All anchor bolts shall be according to Article 1006.09, except all anchor bolts shall be hot dipped galvanized the full length of the anchor bolt including the hook.

Concrete Foundations, Type A for Traffic Signal Posts shall provide anchor bolts with the bolt pattern specified within the "IDOT District 1 Standards Traffic Signal Design Details". All Type A foundations shall be a minimum depth of forty-eight (48) inches.

Concrete Foundations, Type C (Special) for Traffic Signal Cabinets with Uninterruptable Power Supply (UPS / Battery Back-Up) cabinet installations shall be constructed a minimum of forty-eight (48) inches long by thirty-one (31) inches wide, and shall have a minimum depth of forty-eight (48) inches. An integral concrete pad foundation for the UPS cabinet shall be constructed a minimum of thirty-one (31) inches long by twenty (20) inches wide by ten (10) inches deep. The UPS cabinet pad foundation shall be integral to the side of the signal cabinet foundation, and shall be constructed on the same side as the signal cabinet power panel. An L-Shaped concrete apron shall be constructed along the entire front of the signal cabinet foundation, the entire side of the UPS cabinet foundation, and the entire front of the UPS cabinet foundation. This concrete apron shall be a minimum of thirty-six (36) inches wide by four (4) inches deep. Anchor bolts shall be provided and spaced according to the cabinet manufacturer's specifications.

Concrete Foundations, Type D for Traffic Signal Cabinets shall be constructed a minimum of forty-eight (48) inches long by thirty-one (31) inches wide, and shall have a minimum depth of forty-eight (48) inches. The concrete apron at the signal cabinet shall be constructed a minimum of thirty-six (36) inches wide by forty-eight (48) inches long by four (4) inches deep. Anchor bolts shall be provided and spaced according to the cabinet manufacturer's specifications.

Concrete Foundations, Type E for Mast Arm and Combination Mast Arm Poles shall be 15 ft. minimum depth and in accordance with the latest edition of IDOT standard 878001.

The Resident Engineer shall approve the foundation excavation prior to placing any concrete.

HANDHOLES

Add the following to Section 814 of the "Standard Specifications":

All handholes shall be cast-in-place concrete, with a minimum inside dimension of 21-1/2 inches. Frames and lid openings shall match this dimension. The minimum wall thickness for heavy-duty hand holes shall be 12 inches. The handhole cover shall be labeled "Traffic Signals" with legible raised letters.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

All conduits shall enter the handhole at a minimum depth of thirty (30) inches. However, the depth of conduit from detector loops located less than five (5) feet from the handhole may be less than thirty (30) inches.

All cable hooks shall be hot-dipped galvanized in accordance with AASHTO Specification M111. Hooks shall be a minimum of 3/8-inch diameter and extend into the handhole at least 6 inches. Hooks shall be placed a minimum of 12 inches below the lid, or lower if additional space is required. All cable hooks shall be secured with a retaining nut tightened against the handhole concrete.

COILABLE NON-METALLIC CONDUIT

Description. This work shall consist of furnishing and installing empty coilable non-metallic conduit (CNC) for detector loop raceways.

General. The CNC installation shall be in accordance with Sections 810 and 811 of the Standard Specifications except for the following:

Add the following to Article 810.03 of the Standard Specifications:

CNC meeting the requirements of NEC Article 353 shall be used for detector loop raceways to the handholes.

Add the following to Article 811.03 of the Standard Specifications:

On temporary traffic signal installations with detector loops, CNC meeting the requirements of NEC Article 353 shall be used for detector loop raceways from the saw-cut to 10 feet (3m) up the wood pole, unless otherwise shown on the plans

Basis of Payment. All installations of CNC shall be included in the cost of the contract and not paid for separately.

DETECTOR LOOP

Revise Section 886 of the "Standard Specifications" to read:

A minimum of seven (7) working days prior to the Contractor cutting loops, the Engineer shall mark the location of the proposed loops and contact the Traffic Engineer (847) 377-7000 to inspect and approve the layout. When preformed detector loops are installed, the Contractor shall have them inspected and approved prior to the placement of the concrete surface, using the same notification process as above.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

Loop detectors shall be installed according to the requirements of the "IDOT District 1 Standard Traffic Signal Design Details". Saw-cuts (homeruns on preformed detector loops) from the loop to the edge of pavement shall be made perpendicular to the edge of pavement in order to minimize the length of the saw cut (homerun), unless otherwise directed by the Engineer or as shown on the plans. Polyethylene unit duct shall be used for detector loop raceways to the handholes. Coilable non-metallic conduit shall meet the requirements of NEC Article 343. All coilable non-metallic conduit used for traffic signal loop detector runs shall be included in cost of the detector loop.

The detector loop cable insulation shall be labeled with the cable specifications. Each detector loop lead-in wire shall be labeled in the handhole using a Panduit 250W175C waterproof tag or approved equal. The tag will be secured to each wire with nylon ties.

The resistance to ground for new detector loops shall be a minimum of 500 megaohms under any conditions of weather or moisture. Inductance shall be more than 50 microhenries and less than 700 microhenries. Quality readings shall be more than 5. All new or replacement lead-in cables shall be connected to the loop interface panel using appropriate crimp-on, spade type connectors. Detector loop measurements shall include the saw cut and the length of the loop lead-in to the edge of pavement. The lead-in wire, including all necessary connections for proper operations, from the edge of pavement to the handhole, shall be included in the cost of the detector loop. Coilable non-metallic conduit, trench and backfill, and drilling of pavement or handholes shall be incidental to detector loop quantities.

The location of each dive hole shall be marked on the face of the curb, the edge of pavement or the handhole, with a saw cut 1/4 inch deep by 4 inches long.

- (a) Type I: Each detector loop, which is to be installed in new asphalt pavement, must be placed in the pavement below the surface course. Each detector loop, which is to be installed in an existing asphalt or concrete pavement, shall be located to miss existing pavement cracks, if possible. Loop sealant used to seal new loops shall consist of a two-component thixotropic, chemically-cured polyurethane. The sealant will be Chemque Q-Seal 295, Perol Elastic Cement A/C Grade or an approved equal. The sealant shall be installed 1/8 inch below the pavement surface. Excess sealant, which accumulates on the surface, shall be removed immediately. Loop sealant used to reseal existing loops shall be composed of an asphalt-based compound. The sealant will be Doseal 230 or an approved equal.
- (b) Preformed. This work shall consist of furnishing and installing a rubberized heat resistant preformed traffic signal loop in accordance with the "Standard Specifications", except for the following:

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

Preformed detector loops shall be installed in new pavement constructed of portland cement concrete and shall be placed in the substrate. Loop lead-ins shall be protected to the satisfaction of the Engineer.

Handholes shall be placed next to the shoulder or back of curb when preformed detector loops enter the handhole.

Preformed detector loops shall be factory assembled. Homeruns and interconnects shall be pre-wired and shall be an integral part of the loop assembly. The loop configurations and homerun lengths shall be assembled for the specific application. The loop and homerun shall be constructed using 11/16-inch outside diameter (minimum), 3/8-inch inside diameter (minimum) Class A oil resistant synthetic cord-reinforced hydraulic hose with 250 psi internal pressure rating. Hose for the loop and homerun assembly shall be one continuous piece. No joints or splices shall be allowed in the hose except where necessary to connect homeruns or interconnects to the loops. This will provide maximum wire protection and loop system strength. Hose tee connections shall be heavy-duty high temperature synthetic rubber. The tee shall be of proper size to attach directly to the hose, minimizing glue joints. The tee shall have the same flexible properties as the hose to insure that the whole assembly can conform to pavement movement and shifting without cracking or breaking. The wire used shall be #16 THWN stranded copper. The number of turns in the loop shall be application specific. Homerun wire pairs shall be twisted a minimum of four turns per foot. No wire splices will be allowed in the preformed loop assembly. The loop and homeruns shall be filled and sealed with a flexible sealant to insure complete moisture blockage and further protect the wire.

To minimize the length of time that a signal operates without vehicle detection, detector loops for active traffic signal installations shall be installed in a timely manner as follows:

If in the opinion of the Engineer construction conditions are suitable for loop installation(s), the Engineer shall notify the Contractor to proceed. The detector loops shall be installed and fully operational within fourteen (14) calendar days following notification to proceed by the Engineer. This 14-day period shall be in effect throughout the entire year, including the off season, regardless of the Contractor's working day status. Failure by the Contractor to complete the loop installation(s) within the specified timeframe shall result in liquidated damages in the amount of **\$500.00** per calendar day, per occurrence.

This work shall be paid for at the contract unit price per foot for DETECTOR LOOP, TYPE I or PREFORMED DETECTOR LOOP as specified in the plans, which price shall be payment in full for furnishing and installing the detector loop and all related connections for proper operation.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

ELECTRIC CABLE

Delete "or stranded, and No. 12 or" from the last sentence of Article 1076.04 (a) of the "Standard Specifications".

Add the following to the Article 1076.04(d) of the Standard Specifications:

Service cable may be single or multiple conductor cable.

The electric service cable shall have an XLP jacket. All other cable jackets shall be polyvinyl chloride, meeting the requirements of IMSA 19-1 or IMSA 20-1. The jacket color for signal cable shall be black. The jacket color for lead-in and communications cable shall be gray. All cabling between the signal cabinet and the signal heads shall be solid copper, not multi-stranded. Heat shrink splices shall be used according to the IDOT District 1 "Standard Traffic Signal Design Details".

GROUNDING CABLE

The cable shall meet the requirements of Section 817 of the "Standard Specifications", except for the following:

Add to Article 817.02 of the "Standard Specifications":

Unless otherwise noted on the Plans, the system grounding cable shall be one conductor, #6 gauge copper, with an XLP jacket.

The traffic signal grounding conductor (system grounding cable) shall be bonded, using a Listed grounding connector (Burdny type KC/K2C, as applicable, or approved equal), to all new and existing traffic signal mast arm poles and traffic/pedestrian signal posts, including push button posts. The grounding conductor shall be bonded to all new and existing pull boxes, handhole frames and covers and other metallic enclosures throughout the traffic signal wiring system and noted herein and detailed on the plans. Bonding to existing handhole frames and covers shall be paid for separately.

Add the following to Article 817.05 of the "Standard Specifications":

Basis of Payment. Payment shall be at the Contract unit price, per foot, for ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C, which price includes all associated labor and material including grounding clamps, splicing, exothermic welds/other UL Listed connectors and hardware.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

RAILROAD INTERCONNECT CABLE

The cable shall meet the requirements of Section 873 of the "Standard Specifications", except for the following:

Add the following to Article 873.02 of the "Standard Specifications":

The cable shall be three conductor standard #14 copper cable in a clear polyester binder, shielded with #36 AWG tinned copper braid with 85% coverage, and insulated with .016 inch polyethylene (black, blue, red). The jacket shall be black 0.045 PVC or polyethylene.

Revise Article 873.06 of the "Standard Specifications" to read:

Basis of Payment. This work shall be paid for at the contract unit price per foot for ELECTRIC CABLE IN CONDUIT, RAILROAD, NO. 14 3C, which price shall be payment in full for furnishing, installing, and making all electrical connections in the traffic signal controller cabinet. Connections in the railroad controller cabinet shall be performed by railroad personnel.

ELECTRIC CABLE IN CONDUIT, COAXIAL

This work shall consist of furnishing and installing a Belden 1694A RG-6/U Type Digital Coaxial Cable or approved equal. The cable shall be a 75-ohm coaxial cable with 18 AWG solid bare copper conductor, tinned copper braided shield (95% min), and black polyvinyl chloride jacket. The nominal outside diameter shall be 0.274 inches. Amphenol 31-71032 (or equivalent) BNC plug connectors shall be used at both the PTZ camera and traffic signal cabinet ends of the cable. An Amphenol CLT-2 crimping tool is required for the termination. No splices shall be allowed in the cable between the PTZ camera and the traffic signal cabinet.

Basis of payment. This work will be paid for at the contract unit price per foot for ELECTRIC CABLE IN CONDUIT, COAXIAL, which price shall be payment in full for furnishing the material, making all electrical connections and installing the cable complete, measured as specified herein.

EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C

This work shall consist of furnishing and installing lead-in cable for light detectors installed at existing and/or proposed traffic signal installations as part of an emergency vehicle priority system. The work includes installation of the lead-in cables in existing and/or new conduit. The electric cable shall be shielded and have (3) stranded conductors colored blue, orange, and yellow with a stranded tinned copper drain wire. The cable shall meet the requirements of the manufacturer of the Emergency Vehicle Priority System Equipment.

Basis of Payment. This work will be paid for at the contract unit price per foot for EMERGENCY

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C, which price shall be payment in full for furnishing, installing and making all electrical connections necessary for proper operations.

ELECTRICAL CABLE IN CONDUIT, VIDEO NO 20 4 C

This work shall consist of furnishing and installing a Belden 5402 FE Cable or approved equal. No splices shall be allowed in the cable between the PTZ camera and the traffic signal cabinet.

Basis of payment. This work will be paid for at the contract unit price per foot for ELECTRIC CABLE IN CONDUIT, VIDEO NO. 20 4 C, which price shall be payment in full for furnishing the material, making all electrical connections and installing the cable complete, measured as specified herein.

OUTDOOR RATED NETWORK CABLE

This work shall consist of furnishing and installing a network cable from the traffic signal cabinet to the associated field device shown on the plans.

The outdoor rated network cable shall be a black Category 5e cable, meeting the TIA/EIA 568-B.2 telecommunication standards. The cable shall be composed of 24 AWG solid bare copper conductors, twisted pairs, polyolefin insulation, inner LLPE jacket, overall shield (100% coverage), 24 AWG stranded TC drain wire, industrial grade sunlight- and oil-resistant LLPE jacket. The cable shall be capable of performing from -40 °C to 70 °C.

Each end of the cable shall be terminated with an RJ-45 connector installed according to the TIA/EIA 568B standard. The drain wire at each end shall be terminated with a ring lug and attached to a suitable ground point.

The cable shall be Belden 7937A or approved equivalent.

The work shall be performed according to the applicable portions of Section 873 of the "Standard Specifications", and details as shown on the plans.

Basis of payment. This work will be paid for at the contract unit price per foot for OUTDOOR RATED NETWORK CABLE. The unit price shall include furnishing and installing the cable, and making all connections necessary for proper operation. Furnishing and installing the RJ-45 connectors, ring terminals and grounding the OUTDOOR RATED NETWORK CABLE shall be included in the cost of this pay item.

TRAFFIC-ACTUATED CONTROLLER

Add the following to Section 857 of the "Standard Specifications":

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

The controller shall be the latest model available that is compatible with “Centracs” software or “Aries” software, currently in use by LCDOT, and shall be NEMA TS2 Type 1 compatible, unless specified otherwise on the plans. Controller software compatibility requirements are based upon the controller’s location in the communication system, and shall be as shown on the plans. The controller shall have the latest version of NTCIP software installed, and be equipped with an Ethernet port and a removable data key to save the controller database. Only controllers supplied by approved IDOT District 1 closed-loop equipment manufacturers will be allowed. The traffic signal controller shall provide features to inhibit simultaneous display of circular yellow and yellow arrow indications.

CONTROLLER CABINET AND PERIPHERAL EQUIPMENT

Add the following to Article 1074.03 of the “Standard Specifications”:

Cabinets shall be designed for NEMA TS2 Type 1 operation. All cabinets shall be pre-wired for a minimum of eight (8) phases of vehicular, four (4) phases of pedestrian, and four (4) phases of overlap operation. Individual load switches shall be provided for each vehicle, pedestrian and right turn overlap phase.

- Cabinets – Controller cabinets shall have a footprint of approximately 44 inches wide by 26 inches deep. Type IV cabinets shall be 65 inches high, and shall provide a third shelf for mounting additional equipment. Type V cabinets shall be 77 inches high. Cabinets shall be fabricated of 1/8" thick unpainted aluminum alloy 5052-H32. The surface shall be smooth, free of marks and scratches. All external hardware shall be stainless steel.
- Cabinet Doors – Provide front and rear doors of NEMA type 3R construction with cellular neoprene gasket that is rain tight. Door hinges shall be continuous 14-gauge stainless steel and shall be secured with 1/4-20 stainless steel carriage bolts. Standard equipment shall include a three-point locking system that secures the door at the top, bottom and center. A corbin lock with two keys shall also be furnished. The door shall be equipped with a two-position doorstop, one at 90° and one at 120°.
- Controller Harness – Provide a TS2 Type 2 “A” harness in addition to the TS2 Type 1 harness.
- ~~Surge Protection – Atlantic Scientific ZonelT Model 91391 base station, Model 91375 ZonelT pluggable module (50kA rating) with LED status indicators, or approved equivalent.~~
- BIU – Containment screw required.
- Switch Guards – All switches shall be guarded.
- Back Panel – The back panel wiring shall be securely covered with a piece of plexiglass, minimum thickness 1/8-inch.

- Heating – One (1) 200-watt, thermostatically-controlled, Hoffman electric heater, or approved equivalent.
- Lighting – Four (4) LED light assemblies shall be included along the top and sides of the cabinet. The LED panels shall be controlled by a wall switch. Relume Traffic Control Box LED panels and power supply, or approved equivalent.
- Plan & Wiring Diagrams – 12" x 16" moisture sealed container attached to door.
- The cabinet shall be equipped with a pull-out drawer/shelf assembly. A 1 ½ inch deep drawer shall be provided in the cabinet, mounted directly beneath the controller support shelf. The drawer shall have a hinged top cover and shall be capable of accommodating one (1) complete set of cabinet prints and manuals. This drawer shall support 50 lbs. in weight when fully extended. The drawer shall open and close smoothly. Drawer dimensions shall make maximum use of available depth offered by the controller shelf and be a minimum of 24 inches wide.
- Detector Racks – Full-size rack fully wired to support one BIU, sixteen channels of vehicle detection, and four channels of EVP.
- Field Wiring Labels – All field wiring shall be labeled.
- Field Wiring Termination – Approved channel lugs required.
- Power Supply – Provide a nonconductive shield.
- Circuit Breaker – The signal circuit breaker shall be sized for the proposed load, but shall not be rated less than thirty (30) amps.
- Police Door – Provide wiring and termination for plug-in manual phase advance switch.
- Railroad Pre-Emption Test Switch – Eaton 8830K13 SHA 1250 or approved equivalent.
- MMU – 16 Channel, LCD display, IP addressable (Ethernet) Malfunction Management Unit. The MMU shall be connected to the Ethernet switch with a CAT 5e cable, and configured for proper communication.
- Door Alarm – The front and rear doors shall be equipped with switches wired to the traffic signal controller alarm 1 input for logging and reporting of a door open condition.

FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL

This item shall comply with Sections 857 and 863 of the "Standard Specifications" for Road and Bridge Construction, and shall also comply with the following requirements:

The controller shall meet the requirements for NEMA-TS2 standards for a Type 1 Cabinet. The controller shall be the latest model available that is compatible with "Centracs" software or "Aries" software, currently in use by LCDOT. Controller software compatibility requirements are based upon the controller's location in the communication system, and shall be as shown on the plans. The controller shall have the latest version of NTCIP software installed, and be equipped with an Ethernet port and a removable data key to save the controller database.

The cabinet shall be NEMA TS2 Type 1 design, meeting the requirements of CONTROLLER

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

CABINET AND PERIPHERAL EQUIPMENT.

Basis of payment. This item will be paid for at the contract unit price each for FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL which price shall be payment in full for furnishing and installing the cabinet and controller, complete with necessary connections and equipment for proper operation, at a location designated by the Engineer.

TRAFFIC ACTUATED CONTROLLER & CABINET INTERCONNECTED WITH RAILROADS

Add the following to Articles 1073.01 (c) (2) and 1074.03 (a) (5) (e) of the Standard Specifications:

Controllers and cabinets shall be new and NEMA TS2 Type 1 design.

A method of monitoring and/or providing redundancy to the railroad preemptor input to the controller shall be included as a component of the Railroad, Full Actuated Controller and Cabinet installation and be verified by the traffic signal equipment supplier prior to installation. The cabinet shall be NEMA TS2 Type 1 design, meeting the requirements of CONTROLLER CABINET AND PERIPHERAL EQUIPMENT and FULL ACTUATED CONTROLLER, IN TYPE IV CABINET, (SPECIAL).

Railroad interconnected controllers and cabinets shall be assembled only by an approved traffic signal equipment supplier. All railroad interconnected (including temporary railroad interconnect) controllers and cabinets shall be new, built, tested and approved by the controller equipment vendor, in the vendor's IDOT District 1 facility, prior to field installation. The vendor shall provide the technical equipment and assistance as required by the Engineer to fully test this equipment.

MASTER CONTROLLER

Revise Articles 860.02 and 860.03 of the "Standard Specifications" to read:

The Master Controller shall be the latest model available that is compatible with "Aries" software, currently in use by LCDOT. The minimum baud rate for fiber optic interconnected signal systems shall be 9600 bps.

This item shall also include the installation of an outdoor network interface for termination of the telephone service and a US Robotics 56k modem. The outdoor network interface shall be mounted to the inside of the cabinet in a location suitable to provide access for termination of the telephone service. The outdoor network interface shall be equipped with a standard Three-Electrode Heavy Duty Gas Tube Surge Arrestor.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

INTERSECTION MONITOR

This item shall consist of furnishing and installing an Intersection Monitor at a new or existing traffic signal controller. This item is necessary at isolated (non-interconnected) traffic signals in order to monitor the intersection and controller operations. The Intersection Monitor shall be either an internal module installed in the controller, or an external data key, and shall be the latest model available. The Intersection Monitor shall be fully compatible with "Aries" traffic signal management software, currently in use by LCDOT.

This item shall also include the installation of an outdoor network interface for termination of the telephone service and a US Robotics 56k modem. The outdoor network interface shall be mounted to the inside of the cabinet in a location suitable to provide access for termination of the telephone service. The outdoor network interface shall be equipped with a standard Three-Electrode Heavy Duty Gas Tube Surge Arrestor.

Basis of payment. This item will be paid for at the contract unit price each for INTERSECTION MONITOR, which price shall be payment in full for furnishing and installing the Intersection Monitor (module or data key) complete with all necessary connections and equipment for proper operations.

INDUCTIVE LOOP DETECTOR.

Add the following to Article 1079.01 of the Standard Specifications:

Contracts requiring new cabinets shall provide for rack mounted detector amplifier cards. Detector amplifiers shall provide LCD displays with loop frequency, inductance, and change of inductance readings.

UNINTERRUPTABLE POWER SUPPLY, SPECIAL

This specification sets forth the minimum requirements for an uninterruptable power system (UPS) with battery back-up, for a traffic signal. The system is comprised of the UPS or Inverter unit, bypass switch, batteries, cabinet, and related wiring harnesses.

Revise Article 1074.04(a) (1) of the Standard Specifications to read:

The UPS shall be line interactive or double conversion and provide voltage regulation and power conditioning when utilizing utility power.

The UPS shall be sized appropriately for the intersection's normal traffic signal operating connected load, plus 20 percent (20%). The total connected traffic signal load shall not exceed

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

the published ratings for the UPS. The UPS shall provide a minimum of six (6) hours of normal operation run-time for signalized intersections with LED type signal head optics at 77 °F (25 °C) (minimum 700 W/1000VA active output capacity, with 90 percent minimum inverter efficiency).

Revise Article 1074.04(a) (10) of the Standard Specifications to read:

The UPS shall be compatible with the County's approved traffic controller assemblies utilizing NEMA TS 1 or NEMA TS 2 controllers and cabinet components for full time operation.

Revise Article 1074.04(a) (17) of the Standard Specifications to read:

When the intersection is in battery backup mode, the UPS shall bypass all internal cabinet lights, ventilation fans, cabinet heaters, service receptacles, any lighted street name signs, any automated enforcement equipment and any other devices directed by the Engineer.

Revise Article 1074.04(b) (2)b of the Standard Specifications to read:

Batteries, inverter/charger and power transfer relay shall be housed in a separate NEMA Type 3R cabinet. The cabinet shall be Aluminum alloy, 5052-H32, 0.125-inch thick and have a natural mill finish.

Revise Article 1074.04(b) (2)c of the Standard Specifications to read:

No more than three batteries shall be mounted on individual shelves for a cabinet housing six batteries and no more than four batteries per shelf for a cabinet housing eight batteries.

Add the following to Article 1074.04(b) (2)e of the Standard Specifications:

The door shall be equipped with a two-position doorstop, one at 90° and one at 120°.

Revise Article 1074.04(b) (2)g of the Standard Specifications to read:

The door shall open to the entire cabinet and have a neoprene gasket, an Aluminum continuous piano hinge with stainless steel pin, and a three point locking system. The cabinet shall be provided with a main door lock which shall operate with a traffic industry conventional No. 2 key. Provisions for padlocking the door shall be provided.

Add the following to Article 1074.04(b) (2) of the Standard Specifications:

j. The battery cabinet shall have provisions for an external generator connection.

Add the following to Article 1074.04(c) of the Standard Specifications:

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

- (8) The UPS shall include a tip or kill switch installed in the battery cabinet, which shall completely disconnect power from the UPS when the switch is manually activated.
- (9) The UPS shall incorporate a flanged electric generator inlet for charging the batteries and operating the UPS. The generator connector provided shall be a NEMA L5-15P or NEMA L5-30P locking plug. The connector shall be rated for a minimum of 15/125VAC.
- (10) A power adapter cord shall be provided which converts the supplied NEMA locking connector to a NEMA 5-15P plug. The power adapter cord shall be rated for a minimum of 15A/125VAC and shall be a minimum of 12 inches in length.
- (11) Access to the generator inlet shall be from a secured weatherproof lift cover plate or behind a locked battery cabinet police panel.

Battery System.

Revise Article 1074.04(d) (3) of the Standard Specifications to read:

All batteries supplied in the UPS shall be either gel cell or AGM type, deep cycle, completely sealed, prismatic lead calcium based, silver alloy, valve regulated lead acid (VRLA) requiring no maintenance. All batteries in a UPS installation shall be the same type; mixing of gel cell and AGM types within a UPS installation is not permitted.

Revise Article 1074.04(d) (4) of the Standard Specifications to read:

Batteries shall be certified by the manufacturer to operate over a temperature range of -13 to 160 °F (-25 to + 71 °C) for gel cell batteries and -40 to 140 °F (-40 to + 60 °C) for AGM type batteries.

Add the following to Article 1074.04(d) of the Standard Specifications:

- (9) The UPS shall consist of an even number of batteries that are capable of maintaining normal operation of the signalized intersection for a minimum of six hours. Calculations shall be provided showing the number of batteries of the type supplied that are needed to satisfy this requirement. A minimum of four batteries shall be provided.

Add the following to the Article 1074.04 of the Standard Specifications:

- (e) Warranty. The warranty for an uninterruptable power supply (UPS) shall cover a minimum of two years from date the equipment is placed in operation; however, the batteries of the UPS shall be warranted for full replacement for a minimum of five years from the date the traffic

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

signal and UPS are placed into service.

Basis of payment. This item shall be paid for at the contract unit price, each, for furnishing and installing the UNINTERRUPTABLE POWER SUPPLY, SPECIAL. The price shall include the UPS/Inverter unit, Bypass Switch, Batteries, Cabinet, wiring harnesses, power adapter cord, and all associated equipment and materials necessary for proper operation.

EMERGENCY VEHICLE PRIORITY SYSTEM

Revise Section 887 of the "Standard Specifications" to read:

If not marked in the Contract plans, it shall be the Contractor's responsibility to contact the municipality or fire district to verify the brand of emergency vehicle preemption equipment to be installed prior to the contract bidding. The equipment must be of the latest type manufactured and must be completely compatible with all components of signal equipment currently in use by the County.

All new installations shall be equipped with confirmation beacons as shown on the IDOT District 1 "Standard Traffic Signal Design Details". The confirmation beacon shall consist of a PAR 38 white LED flood lamp (90 watt equivalent, approved by the Engineer) for each direction of traffic. The lamp shall have an adjustable mount with a weatherproof enclosure for cable splicing. All hardware shall be cast aluminum or stainless steel. Holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires. In order to maintain uniformity between communities, the confirmation beacons shall indicate when the control equipment receives the preemption signal. The preemption movement shall be signaled by a flashing indication at the rate specified by Section 4L.01 of "MUTCD". The stopped preempted movements shall be signaled by a continuous indication.

All light operated systems shall operate at a uniform rate of 14.035 hz \pm 0.002 hz, or as otherwise required by the Traffic Engineer, and provide compatible operation with other light systems currently being operated in the County.

This item shall include any required modifications to an existing traffic signal controller as a result of the addition of the EMERGENCY VEHICLE PRIORITY SYSTEM.

Basis of Payment. The work shall be paid for at the contract unit price each for furnishing and installing LIGHT DETECTOR and LIGHT DETECTOR AMPLIFIER. Furnishing and installing the confirmation beacon shall be included in the cost of the Light Detector. Any required modifications to the traffic signal controller shall be included in the cost of the LIGHT DETECTOR AMPLIFIER. The light detector amplifier shall be paid for on a basis of (1) one each per intersection controller and shall provide operation for all movements required in the pre-emption phase sequence.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

STEEL MAST ARM ASSEMBLY AND POLE
STEEL COMBINATION MAST ARM ASSEMBLY AND POLE

Add the following to Article 1077.03 of the "Standard Specifications":

Traffic signal mast arms shall be one-piece construction, unless otherwise approved by the Engineer. All mast arms, mast arm poles, luminaire arms, cast iron bases, and any exposed steel hardware shall be hot-dipped galvanized.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires.

Luminaire arms shall be steel, and of the length shown on the plans. Luminaire arms over fifteen (15) feet in length shall be tapered, monotube style, with AASHTO 2001 wrap-around, gusset style connection.

luminaires shall be "cobra head" style, with a minimum mounting height of forty-five (45) feet, and shall be paid for separately.

Stainless steel mesh screening shall be stainless steel banded to the anchor bolts, with a minimum 2-inch lap, to enclose the void between the top of the foundation and the base plate. The mesh screening shall have ¼-inch maximum opening and a minimum wire diameter of AWG NO. 16.

The base of the mast arm pole shall be protected by a bolt-on galvanized metal shroud or an approved equal. The shroud shall be of sufficient strength to deter pedestrian and vehicular damage. The shroud shall be constructed and designed to allow air to circulate throughout the mast arm but not allow infestation of insects or other animals, and such that it is not hazardous to probing fingers and feet. All mounting hardware shall be stainless steel.

STEEL MAST ARM ASSEMBLY AND POLE (SPECIAL)
STEEL COMBINATION MAST ARM ASSEMBLY AND POLE (SPECIAL)

Add the following to Article 1077.03 of the "Standard Specifications":

Base covers for mast arm poles shall be cast aluminum. All mast arms, mast arm poles, luminaire arms, and any exposed steel hardware shall be hot-dipped galvanized, and then powder-coated black by the supplier/manufacturer, as described below or an approved alternative finishing method. Cast aluminum base covers shall be powder-coated black by the supplier/manufacturer, as described below or an approved alternative finishing method.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

All galvanized and aluminum exterior surfaces shall be coated with chip resistive epoxy resin primer applied via electrostatic spray equipment. The primer is to be applied at a minimum dry film thickness (DFT) of 3.0 mils with a minimum DFT of 6.0 mils applied to the lower 8 feet of the pole. The primer coat must be energy absorptive, and capable of achieving a rating of 10A under testing per ASTM (American Society for Testing and Materials) Procedure D3170, Standard Test Method for Chipping Resistance of Coatings. The primed surfaces shall then be coated with a black semi-gloss TGIC Super Durable Polyester topcoat to a minimum dry film thickness of 3.0 mils. The topcoat must meet the requirements of AAMA (American Architectural Manufacturer's Association) 2604 for color and gloss retention properties.

The manufacturer shall warranty the finish of all components for a period of at least 5 years from the date of shipment. The contractor shall provide a copy of the warranty to the Engineer, upon request.

All chips, scrapes, scratches, etc. in the paint shall be touched-up by the Contractor according to the manufacturer's recommendations, with matching paint supplied by the manufacturer.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires.

Stainless steel mesh screening shall be stainless steel banded to the anchor bolts, with a minimum 2-inch lap, to enclose the void between the top of the foundation and the base plate. The mesh screening shall have 1/4-inch maximum opening and a minimum wire diameter of AWG NO. 16.

All base covers shall fit tightly around the poles, with little or no gap at the top of the base cover. Two-piece base covers shall fit together tightly, with little or no gap between the two pieces. All base covers shall fit securely on top of the foundation, and shall not easily move or wobble. All base covers shall have an access hand hole, with a removable cover, and a minimum opening size of 200 square inches.

Pedestrian pushbutton stations shall be mounted to mast arm base covers according to the following: The top and bottom of the station shall be secured by drilling, tapping, and installing a 3/8-inch stainless steel threaded bolt, lock washer, and hex nut. Do not use self-tapping screws. Spacers made of 3/4-inch aluminum conduit shall be installed behind the pushbutton station, to level and plumb the station.

Luminaire arms shall be steel, and of the length shown on the plans. Luminaire arms over fifteen (15) feet in length shall be tapered, monotube style, with AASHTO 2001 wrap-around, gusset style connection.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

Luminaires shall be installed at a minimum mounting height of forty-five (45) feet, and shall be paid for separately.

All (Special) steel mast arm assemblies and poles (including combination mast arm assemblies) shall be manufactured and/or supplied by Sternberg Vintage Lighting, Union Metal, Valmont, or approved equal, according to the following:

- Round, tapered, 16-sharp fluted pole.
- Round, tapered, smooth, standard-curved, flange-connected, traffic signal mast arm

The two-piece mast arm base cover shall be cast aluminum, and shall be manufactured and/or supplied by the same company as the mast arm assembly and pole. Manufacturer designations for the two-piece mast arm base cover to be used with (SPECIAL) MAST ARM ASSEMBLIES include the following:

- Hamilton 6401SS (Sternberg)
- Lake County AC1 base cover (Valmont)

LUMINAIRE

Add the following to Article 1067.01(e) of the "Standard Specifications":

The luminaire housing shall be cobra head style.

Revise Article 1067.01(i) of the "Standard Specifications" to read:

The luminaire shall be painted black or powder-coated black to match the finish of STEEL COMBINATION MAST ARM ASSEMBLY AND POLE (SPECIAL).

TRAFFIC SIGNAL POST

Add the following to Article 1077.01 (d) of the "Standard Specifications":

Steel posts and cast iron bases shall be hot-dipped galvanized.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires.

TRAFFIC SIGNAL POST (SPECIAL)

Add the following to Article 1077.01 of the "Standard Specifications":

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

All Traffic Signal Posts (Special) shall be sixteen (16) feet in height, extruded aluminum, unless otherwise specified on the plans. All bases for Traffic Signal Post (Special) shall be cast aluminum.

All Traffic Signal Posts (Special) and associated bases shall be assembled and powder-coated black at the factory. The powder-coated finish and warranty shall meet the requirements of STEEL MAST ARM ASSEMBLY AND POLE (SPECIAL). All exposed steel hardware shall be hot-dipped galvanized, and then powder-coated black.

All chips, scrapes, scratches, etc. in the paint shall be touched-up by the Contractor according to the manufacturer's recommendations, with matching paint supplied by the manufacturer.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires.

Pedestrian pushbutton stations shall be mounted to signal posts according to the following: The top and bottom of the station shall be secured by drilling, tapping, and installing a 3/8-inch stainless steel threaded bolt. Self-tapping screws are not allowed. Anti-seize lubricating compound shall be applied to all pushbutton and pushbutton station hardware. Spacers made of 3/4-inch aluminum conduit shall be installed behind the pushbutton station, to level and plumb the station.

All Traffic Signal Posts (Special) and associated bases shall be manufactured and/or supplied by Beacon, Sternberg Vintage Lighting, Union Metal, Valmont, or approved equal, according to the following:

- Round, straight (non-tapered), five (5)-inch diameter, 12-flat fluted post.
- A ball center cap for the top of the post, instead of a tenon.
- The base section of the post shall be approximately forty-three (43) inches tall.

Manufacturer designations for TRAFFIC SIGNAL POST (SPECIAL) include the following:

- MainStreet Series (100SJ) base (Beacon)
- Hamilton Series (5400D) base (Sternberg)

PEDESTRIAN PUSH-BUTTON

Replace Article 1074.02 of the "Standard Specifications" with the following:

Pedestrian Push-button assembly shall be ADA compliant, 3-inch round style, highly vandal resistant, non-moving, pressure activated, with a solid-state Piezo switch actuator that cannot be stuck in an "on" or constant call position. A latching red LED and audible tone shall be provided to confirm an actuation. The housing, or bezel, of the assembly shall be solid

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

aluminum and powder coated yellow. The button shall be stainless steel or nickel-plated aluminum.

Pedestrian Push-button assembly shall be a Campbell Company 4 EVR CL with Enlightened Interface Module (ENIM), a Polara BullDog BDL3-Y with Latching Push Button Control Unit (LPBCU), or approved equivalent.

The pedestrian station shall be a Campbell Company 912H Station, Polara PBF9X12 or approved equivalent.

The station shall be installed with a 9-inch by 12-inch retro-reflective sign, according to the following: Where pedestrian signal heads are used, pedestrian signs shall provide the "Push Button for" legend, with the Walking Man symbol and arrow (R10-3). Where no pedestrian signal heads are used, pedestrian signs shall provide the "Push Button for Green Light" legend with arrow (R10-4 with arrow), or as specified on the plans.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires.

Anti-seize lubricating compound shall be applied to all pushbutton and pushbutton station hardware.

Refer to STEEL MAST ARM ASSEMBLY AND POLE (SPECIAL), STEEL COMBINATION MAST ARM ASSEMBLY AND POLE (SPECIAL), and/or TRAFFIC SIGNAL POST (SPECIAL) for additional installation requirements.

ILLUMINATED SIGN, LIGHT EMITTING DIODE

Delete last sentence of Article 1084.01(a) and add "Mounting hardware shall be black polycarbonate or galvanized steel and similar to mounting Signal Head hardware and bracket specified herein and shall provide tool free access to the interior."

Revise the second paragraph of Article 1084.01(a) of the Standard Specifications to read:

The exterior surface of the housing shall be acid-etched and shop painted with one coat of zinc-chromate primer and two coats of exterior enamel. The housing shall be the same color (yellow or black) to match the existing or proposed signal heads. The painting shall be according to Section 851.

Add the following to Article 1084.01 (b) of the Standard Specifications:

The message shall be formed by rows of LEDs. The sign face shall be 24 inches by 24 inches .

Add the following to Article 1084.01 of the Standard Specifications:

- (e) The light emitting diode (LED) blank out signs shall be manufactured by National Sign & Signal Company, or an approved equal and consist of a weatherproof housing and door, LEDs and transformers.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires.

Basis of payment. This work shall be paid for at the unit price each for ILLUMINATED SIGN, LIGHT EMITTING DIODE.

LED INTERNALLY ILLUMINATED STREET NAME SIGN

This work shall consist of furnishing a street name sign which is internally illuminated with light emitting diodes, and installing the sign on a traffic signal mast arm or span wire.

(a) Description.

The LEDs shall be white in color and utilize InGaN or UV thermally efficient technology. The LED Light Engines shall be designed to fit inside a standard fluorescent illuminated street sign housing in lieu of fluorescent lamps and ballasts. The LED internally-illuminated street name sign shall display the designated street name clearly and legibly in the daylight hours without being energized and at night when energized. The sign assembly shall consist of a four-, six-, or eight-foot aluminum housing. White translucent 3M DG³ reflective sheeting sign faces with the street name applied in 3M/Scotchlite Series 1177 or current 3M equivalent transparent green shall be installed in hinged doors on the side of the sign for easy access to perform general cleaning and maintenance operations. Illumination shall occur with LED Light Engine as specified.

(b) Environmental Requirements.

The LED lamp shall be rated for use in the ambient operating temperature range of -40 to +50°C (-40 to +122°F) for storage in the ambient temperature range of -40 to +75°C (-40 to +167°F).

(c) General Construction.

1. The LED Light Engine shall be a single, self-contained device, for installation in an existing street sign housing. The power supply must be designed to fit and mounted on the inside wall at one end of the street sign housing. The LED Light Engine shall be mounted within the inner top portion of the housing and no components of the light source shall sit between the sign faces.
2. The assembly and manufacturing processes of the LED Light Engine shall be designed to ensure that all LED and electronic components are adequately supported to withstand

mechanical shocks and vibrations in compliance with the specifications of the ANSI, C136.31-2001 standards.

(d) Mechanical Construction.

1. The sign shall be constructed using a weatherproof, aluminum housing consisting of an extruded aluminum top with a minimum thickness of .140" x 10 3/4" deep (including the drip edge). The extruded aluminum bottom is .094" thick x 5 7/8" deep. The ends of the housing shall be cast aluminum with a minimum thickness of .250". A six-foot sign shall be 72 5/8" long and 22 5/16" tall and not weigh more than 77 pounds. An eight-foot sign shall be 96 5/8" long and 22 5/16" tall and not weigh more than 92 pounds. All corners are continuous TIG (Tungsten Inert Gas) welded to provide a weatherproof seal around the entire housing.
2. The door shall be constructed of extruded aluminum. Two corners are continuous TIG welded with the other two screwed together to make one side of the door removable for installation of the sign face. The door is fastened to the housing on the bottom by a full length, .040" x 1 1/8" open stainless steel hinge. The door shall be held secure onto a 1" wide by 5/32" thick neoprene gasket by three (six total for two-way sign) quarter-turn fasteners to form a watertight seal between the door and the housing.
3. The sign face shall be constructed of .125" white translucent polycarbonate. The letters shall be 8" upper case and 6" lower case. The sign face legend background shall consist of 3M/Scotchlite Series 4090T or current equivalent 3M translucent DG³ white VIP (Visual Impact Performance) diamond grade sheeting (ATSM Type 9) and 3M/Scotchlite Series 1177 or current 3M equivalent transparent green acrylic EC (electronic cut-able) film applied to the front of the sign face. The legend shall be framed by a white polycarbonate border. A logo symbol and/or name of the community may be included with approval of the Engineer.
4. All surfaces of the sign shall be etched and primed in accordance to industry standards before receiving appropriate color coats of industrial enamel. The sign frame shall be painted black with a durable powder coated process.
5. All fasteners and hardware shall be corrosion resistant stainless steel. No tools are required for routine maintenance.
6. All wiring shall be secured by insulated wire compression nuts.
7. A wire entrance junction box shall be supplied with the sign assembly. The box may be supplied mounted to the exterior or interior of the sign and provide a weather tight seal.

8. Each sign shall be activated by a photocell mounted/installed on the side of the sign frame.
9. Brackets and Mounting: LED internally-illuminated street name signs will be factory drilled to accommodate mast arm two-point support assembly mounting brackets.

(e) Electrical.

1. Photocell shall be rated 105-305V, turn on at 1.5 fcs. with a 3-5 second delay. A manufacturer's warranty of six (6) years shall be provided. Power consumption shall be no greater than 1 watt at 120V.
2. The LED Light Engine shall operate from a 60 +/- 3 cycle AC line power over a voltage range of 80 to 135 Vac rms. Fluctuations in line voltage over the range of 80 to 135 Vac shall not affect luminous intensity by more than +/- 10%.
3. Total harmonic distortion induced into the AC power line by the LED Light Engine, operated at a nominal operating voltage, and at a temperature of +25°C (+77°F), shall not exceed 20%.
4. The LED Light Engine shall be cycled ON and OFF with a photocell as shown on the detail sheet and shall not exceed the following maximum power values:

4-Foot Sign	60 W
6-Foot Sign	90 W
8-Foot Sign	120 W

The signs shall not be energized when traffic signals are powered by an alternate energy source such as a generator or uninterruptable power source (UPS). The signs shall be connected to the generator or UPS bypass circuitry.

(f) Photometric Requirements.

1. The entire surface of the sign panel shall be evenly illuminated. The average maintained luminous intensity measured across the letters, operating under the conditions defined in Environmental Requirements and Wattage Sections shall be of a minimum value of 100 cd/m².
2. The manufacturer shall make available independent laboratory test results to verify compliance to Voltage Range and Luminous Intensity Distribution Sections.
3. Twelve (12) 1.25 watt LED units shall be mounted on 1-inch x 22-inch metal cone printed circuit boards (MCPCB). The viewing angle shall be 120 degrees. LED shall

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

have a color temperature of 5200k nominal, CRI of 80 with a life expectancy of 75,000 hrs.

(g) Quality Assurance.

The LED Light Engine shall be manufactured in accordance with a vendor quality assurance (QA) program. The production QA shall include statistically controlled routine tests to ensure minimum performance levels of the LED Light Engine build to meet this specification. QA process and test result documentations shall be kept on file for a minimum period of seven (7) years. The LED Light Engine that does not satisfy the production QA testing performance requirements shall not be labeled, advertised, or sold as conforming to these specifications. Each LED Light Engine shall be identified by a manufacturer's serial number for warranty purposes. LED Light Engines shall be replaced or repaired if they fail to function as intended due to workmanship or material defects within the first sixty (60) months from the date of acceptance. LED Light Engines that exhibit luminous intensities less than the minimum value specified in Photometric Section within the first thirty-six (36) months from the date of acceptance shall be replaced or repaired.

The sign shall be mounted on the mast arm three feet to the right of the furthest right signal head, as viewed by the approaching traffic.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires.

The Manufacturer/Vendor shall supply shop drawings of the fixtures, sign, sign message and mounting hardware for approval. All hardware used to install the sign shall be in accordance with the manufacturer's recommendations.

Basis of Payment. This work will be paid for at the contract unit price each for furnishing and installing LED INTERNALLY ILLUMINATED STREET NAME SIGN, of the size specified, complete in place, including photocell and all related hardware, wiring, and connections required for proper operations. The #14 2/C cable from the signal cabinet to the sign shall be paid for separately.

MAST ARM SIGN PANELS

Add the following to Article 720.02 of the Standard Specifications:

Signs attached to poles or posts (such as mast arm signs) shall have mounting brackets and sign channels which are equal to and completely interchangeable with those used by LCDOT. All aluminum signs shall have a white reflectorized legend and border on a green reflectorized background, DG³ type sheeting. The sign face shall not have any holes. 3M Scotch Joining Systems bonding tape or an approved equal shall be used in place of screws or rivets. The Signfix Aluminum Channel Framing System is currently recommended, but other brands of

mounting hardware or bonding tape may be acceptable based upon LCDOT approval.

SIGNAL HEADS

Add the following to Section 1078 of the Standard Specifications to read:

All vehicle signal and pedestrian signal heads shall provide 12-inch displays, with glossy black polycarbonate housings, with the following exception: At locations where existing yellow polycarbonate heads will remain, all new signal heads shall be yellow to match the existing ones. Connecting hardware and mounting brackets shall be polycarbonate, the same color as the heads, or galvanized. A corrosive resistant anti-seize lubricant shall be applied to all metallic mounting bracket joints, and shall be visible to the inspector at the signal turn-on. Where required, incandescent bulbs shall be manufactured by Duratest, Sylvania or an approved equal.

SIGNAL HEAD, LED

This work shall consist of furnishing and installing a traffic signal head with light emitting diodes (LED) of the type specified in the plans, in accordance with Sections 880 and 1078 of the Standard Specifications for Road and Bridge Construction, and the following.

The lens of the LED signal module shall be tinted with a wavelength-matched color to reduce sun phantom effect and enhance on/off contrast. The tinting shall be uniform across the lens face, and shall not affect chromaticity. The lens shall be smooth, with the same uniform appearance as incandescent lenses.

Each individual LED signal module shall be clearly marked with the manufacturer's name, model number, date of manufacture, nominal operating voltage, and power consumption in watts.

The LED signal module shall have a one-piece neoprene gasket.

The LEDs arrow indication shall be a solid display with a minimum of three (3) outlining rows of LEDs and at least one (1) fill row of LEDs.

All LED signal modules shall be warranted for 5 years from the date of traffic signal turn-on against failures due to manufacturing, workmanship, or material defects including modules which exhibit luminous intensities less than the minimum values specified by the Institute for Transportation Engineers (ITE) LED purchase specification, "Vehicle Traffic Control Signal Heads: LED Circular Signal Supplement". Any modules that do not meet these warranty requirements shall be replaced or repaired at no expense to the County. The manufacturer's written warranty for the LED signal modules shall be included in the product submittal to the County.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

PEDESTRIAN SIGNAL HEAD, LED
PEDESTRIAN SIGNAL HEAD, LED, COUNTDOWN

This work shall consist of furnishing and installing a pedestrian countdown signal head, with light emitting diodes (LED) of the type specified in the plans, in accordance with Section 881 and Article 1078.02 of the Standard Specifications for Road and Bridge Construction, and the following.

Pedestrian Countdown Signal Heads shall not be used at signalized intersections where traffic signals and railroad warning devices are interconnected.

The nominal message-bearing surface of pedestrian signal heads shall be 12 in. x 12 in.

Pedestrian Countdown Signal Heads shall consist of two (2) 12-inch by 12-inch modules aligned vertically. The top module of the unit shall be overlapping full "HAND" and full "MAN" symbols. The bottom module of the unit shall be a two digit numerical countdown display ("00" to "99"). The counter shall begin countdown at the beginning of the pedestrian clearance interval as the pictogram of the hand starts flashing. The counter shall execute a countdown of the time, in seconds, of the pedestrian clearance interval synchronized with the controller and ending at (0) at the expiration of the pedestrian clearance interval. The counter shall be blank at all other times.

The visor for each signal shall be the tunnel visor.

The signal module shall have a one-piece neoprene gasket.

The signal module identification labels and warranty shall be according to the SIGNAL HEAD, LED section of these specifications.

SIGNAL HEAD, LED, RETROFIT

This work shall consist of furnishing and installing vehicle or pedestrian LED signal modules in an existing signal head, of the type and mounting specified in the plans, according to the following.

All vehicle and pedestrian LED Retrofit signal modules shall fully comply with the SIGNAL HEAD, LED; PEDESTRIAN SIGNAL HEAD, LED; and PEDESTRIAN SIGNAL HEAD, LED, COUNTDOWN sections of these specifications.

Basis of Payment. This item shall be paid for at the contract unit price each for SIGNAL HEAD, LED, of the type and mounting specified, RETROFIT or PEDESTRIAN SIGNAL HEAD, LED, RETROFIT; or PEDESTRIAN SIGNAL HEAD, LED, COUNTDOWN, RETROFIT, which price

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

shall be payment in full for furnishing the equipment described above including LED(s) modules, all mounting hardware, and installing them in satisfactory operating condition.

TRAFFIC SIGNAL BACKPLATE

Delete the second sentence of the fourth paragraph of Article 1078.03 of the Standard Specifications.

Add the following to the fourth paragraph of Article 1078.03 of the Standard Specifications:

When retro reflective sheeting is specified, it shall be Type ZZ sheeting according to Article 1091.03 and applied in preferred orientation for the maximum angularity according to the manufacturer's recommendations. The retro reflective sheeting shall be installed under a controlled environment at the manufacturer/supplier before shipment to the contractor. The aluminum backplate shall be prepared and cleaned, following recommendations of the retro reflective sheeting manufacturer.

VIDEO VEHICLE DETECTION SYSTEM

This specification sets forth the minimum requirements for a system that monitors vehicles on a roadway via processing of video images and provides detector outputs to a traffic signal controller. This work shall consist of furnishing and installing video cameras, all cables, video processors, controller interface unit, and remote communication module to operate a video vehicle detection system at one signalized intersection.

The video vehicle detection system shall be one of the following or approved equal:

- Autoscope Encore, Terra TIP, Terra TAP
- Iteris RZ-4 WDR, Vantage Edge 2, Vantage TS2-IM, Edge Connect
- Autoscope AIS-IV, Terra RackVision,

All the cables from the detection cameras to the traffic signal cabinet and within the traffic signal cabinet itself shall be included in the cost of this item.

The video vehicle detection system shall also include a LCD monitor in the traffic signal cabinet with BNC connector for video input.

The video detection camera shall be installed on top of the luminaire arm. However, occasionally overhead utility wires obstruct the camera's field of view and prevent proper

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

detector placement. When this occurs, the camera shall be installed on a J-hook below the luminaire arm, instead of the normal mounting bracket. The cost of the J-hook shall be included in the cost of this item.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires.

Surge protection and grounding shall be provided to protect the video detection cameras and components located in the traffic signal cabinet.

In order for the Traffic Engineer to manipulate detection zones and view the video signal over a high-speed connection, the VIDEO VEHICLE DETECTION SYSTEM must be connected to either the LCDOT Gigabit Ethernet network or a VIDEO TRANSMISSION SYSTEM.

If the VIDEO VEHICLE DETECTION SYSTEM is being connected to the Gigabit Ethernet network, the remote communications module shall communicate over 10/100 Base T Ethernet to a LAYER II (DATA LINK) SWITCH and/or a LAYER III (NETWORK) SWITCH. The Layer II and Layer III switches shall be installed according to the plans, and shall be paid for separately.

Basis of Payment. This item will be paid for at the contract unit price each for VIDEO VEHICLE DETECTION SYSTEM which price shall be payment in full for furnishing all associated equipment, cables and hardware required, installing the system at one signalized intersection, and placing the system in operation to the satisfaction of the Engineer.

REMOTE-CONTROLLED VIDEO SYSTEM

This pay item shall include providing and installing a remote-controlled video system at a location designated by the Engineer. The remote-controlled video system shall be a PELCO Spectra IV SE Series Discreet Dome System or approved equal. This pay item shall include a color camera (minimum 35x optical zoom), dome assembly, all mounting hardware, connectors, cables, and related equipment necessary to complete the installation in accordance with the manufacturer's specifications.

The PTZ control, power, and coax cables from the traffic signal cabinet shall be paid for separately.

The camera shall be installed as shown on the plans, either on the luminaire arm near the

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

luminaire, or on the combination mast arm assembly pole, angled toward the center of the intersection. When installed on the pole, the camera shall be mounted with a 14-inch pendant arm with integral transformer / power supply (Pelco IWM24-GY or approved equal). When installed on the luminaire arm, the camera shall be installed with a 30-degree tilt-adjustable bracket, and the external power supply (Pelco WCS1-4 or approved equal) shall be installed on the pole. Cameras and external power supplies shall be installed with stainless steel straps.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires.

The contractor shall contact the Traffic Engineer prior to installing the Pelco camera and associated wiring, to receive final approval on the camera location.

In order for the Traffic Engineer to control the camera remotely and view the video signal over a high-speed connection, the REMOTE-CONTROLLED VIDEO SYSTEM must be connected to either the LCDOT Gigabit Ethernet network or a VIDEO TRANSMISSION SYSTEM.

If the REMOTE-CONTROLLED VIDEO SYSTEM is being connected to the Gigabit Ethernet network, then a LAYER II (DATA LINK) SWITCH and/or a LAYER III (NETWORK) SWITCH will be required. Layer II and Layer III switches shall be installed according to the plans, and shall be paid for separately.

If the REMOTE-CONTROLLED VIDEO SYSTEM is being connected to a new or existing VIDEO TRANSMISSION SYSTEM, then fiber-optic video/data transmitters and receivers may be required. Fiber-optic video/data transmitters and receivers are necessary whenever the REMOTE-CONTROLLED VIDEO SYSTEM and the VIDEO TRANSMISSION SYSTEM are installed at separate signalized intersections. When required, fiber-optic video/data transmitters and receivers shall be installed according to the plans, and shall be included in the cost of this item. The VIDEO TRANSMISSION SYSTEM shall be paid for separately.

Basis of Payment. This item will be paid for at the contract unit price each for REMOTE-CONTROLLED VIDEO SYSTEM, which price shall be payment in full for furnishing all associated equipment required, installing the system complete and in place, and placing the system in operation to the satisfaction of the Engineer.

CAMERA MOUNTING ASSEMBLY

This work shall consist of modifying an existing traffic signal mast arm pole to accommodate an extension pole suitable for mounting a CCTV Camera. The pole extension shall be a 20-foot long, 4-inch diameter, Schedule 80 galvanized steel pipe and fastened to the existing mast arm pole with adjustable, galvanized steel clamps as indicated in the plans. The galvanized clamps shall fit securely around the tapered mast arm and shall be modified as required to maintain a true vertical alignment of the camera mounting assembly pole. The exposed wires shall be trained into a drip loop and protected with black plastic spiral cable wrap.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires.

Basis of payment. This work shall be paid for at the contract unit price each for CAMERA MOUNTING ASSEMBLY, which shall include all necessary mounting hardware, labor, and incidentals necessary to securely fasten the assembly to an existing pole and placing the camera in operation to the satisfaction of the Engineer. The camera, cables, connectors, and related equipment shall be paid for separately as part of REMOTE-CONTROLLED VIDEO SYSTEM.

VIDEO TRANSMISSION SYSTEM

This specification sets forth the minimum requirements for a video transmission system that allows a user to transmit video output from multiple cameras to a remote location, via video transmitter(s) and a high-speed communication link.

The high-speed communication link will be either an ISDN phone line or DSL connection as indicated on the plans.

The VIDEO TRANSMISSION SYSTEM may be installed in either the intersection traffic signal cabinet or in the VIDEO COMMUNICATIONS CABINET. The Cabinet shall be paid for separately.

The VIDEO TRANSMISSION SYSTEM may include the relocation of existing video transmitter(s), ISDN modems, Cisco router, and/or high-speed Internet modem(s) to a new traffic signal cabinet. The relocation of such existing equipment to a new traffic signal cabinet shall be performed as directed by the Engineer and included in the cost of the VIDEO TRANSMISSION SYSTEM. Any item damaged during removal, storage, or reinstallation shall be repaired or replaced in kind to the satisfaction of the Engineer at the Contractor's expense.

System Components:

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

The system shall consist of video transmitter(s) (ADPRO Fast Tx or approved equal) or a high-speed Internet modem(s), a Cisco Router, and related connection cables.

High-Speed Internet Modem:

The high-speed Internet modem shall be provided by the County or the Internet Service Provider.

The Cisco Router shall be procured from Delcan, the County's Passage engineering consultant. Delcan shall program this equipment for the appropriate location in the County's communication network.

Basis of payment. This item will be paid for at the contract unit price each for VIDEO TRANSMISSION SYSTEM, which price shall be payment in full for furnishing and/or relocating all associated equipment required, installing the system complete and in place, and placing the system in operation to the satisfaction of the Engineer

COMMUNICATIONS CABINET

This specification sets forth the minimum requirements for a communications cabinet to be installed at the location(s) shown in the plans.

The Communications Cabinet shall be a Model 332 (Type 170) Controller Cabinet, with heat exchanger, or approved equal. The heat exchanger shall be thermostatically controlled to maintain the temperature between 32°F and 122°F within the enclosure. The cabinet shall be constructed of 0.125"-thickness, alloy-5052 sheet aluminum. The surface shall have a smooth, natural aluminum mill finish. The cabinet shall measure 24" wide x 30" deep x 55" high.

The communications cabinet shall have front and rear doors of NEMA type 3R construction with cellular neoprene gasket that is rain tight. Door hinges shall be continuous 14-gauge stainless steel and shall be secured with 1/4-20 stainless steel carriage bolts. Standard equipment shall include a three-point locking system that secures the door at the top, bottom and center. A corbin lock with two keys shall also be furnished. The front and rear doors shall be equipped with a two-position doorstop, one at 90° and one at 120°. Door locking rods are 1/4" x 3/4" aluminum turned edgeways with 1" nylon rollers. Door handles shall be cast aluminum.

The front and rear doors shall be equipped with alarm switches wired to an I/O module. The I/O module shall be connected to the Layer III network switch to transmit door open and closed alarms to the TMC. The I/O device shall be a Moxa E2210, Advantech ADAM-6050, or approved equal meeting the following requirements:

- 10/100BaseT LAN connection
- Supports Modbus/TCP over a TCP/IP network

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

- Minimum of 8 digital dry-contact inputs (logic level 0 = short to GND, logic level 1 = open)
- -10C to +60C Power: 24VDC nominal
- Mounting: DIN rail

The communications cabinet shall be base mounted and equipped with inside flanges and anchoring holes in the front and back of the cabinet for anchoring to a base.

The communications cabinet shall be equipped with a 19" Electronic Industries Association (EIA) rack using 1.75" hole spacing for the purpose of mounting rack-mountable cabinet equipment. The cabinet shall include a fiber optic connector housing, Corning Cable Systems CCH-04U, or approved equal, and a splice housing, Corning Cable Systems CSH-03U, or approved equal, mounted on the 19" rack.

The communications cabinet shall also be equipped with a 15A rackmount power distribution unit and a pull-out drawer/ shelf assembly.

The heat exchanger handles the air inside the communication cabinet, as necessary, to maintain the equipment within the desired temperature range. Therefore, the cabinet shall be fully enclosed, with no louvers in any doors or side panels. No fans or thermostats shall be installed in the communication cabinet.

A power panel shall be included with the cabinet and shall include the following:

- 50-amp circuit breaker. This circuit breaker shall supply power to all devices in the cabinet.
- The main breaker shall be thermal magnetic type, U.L. listed for HACR service, with a minimum of 20,000 amp interrupting capacity.
- Two 15-amp load breakers with minimum 10,000 amp interrupting capacity.
- Two 20-amp load breakers with minimum 10,000 amp interrupting capacity.
- Atlantic Scientific ZoneIT Model 91391 base station, Model 91375 ZoneIT pluggable module (50kA rating) surge arrestor, with LED status indicators, or approved equivalent.
- A 15-position neutral bus bar capable of connecting three #12 wires per position.
- A 7-position ground bus bar capable of connecting three #12 wires per position.
- A NEMA type 5-15R GFI convenience outlet.

The heat exchanger shall be mounted on the side of the communications cabinet and conform to the following specifications.

- Maximum dimensions of 47 inches high x 15 inches wide x 11 inches deep
- The unit shall provide closed-loop system cooling and heating. (Heater option shall be included with the unit.)
- Unit shall be fully gasketed and maintain the NEMA 3R enclosure rating
- Shall utilize a high efficiency, convoluted, refrigerant-free, aluminum heat transfer element

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

- Shall operate under maximum enclosure temperature of 150°F and maximum ambient temperature of 131°F
- The unit shall dissipate a minimum of 54 Watts per °F
- Shall operate on 115 VAC, 60 Hz
- The heat exchanger shall be hard-wired to the communications cabinet power supply.
- Unit shall be UL listed

Basis of payment. This item will be paid for at the contract unit price each for COMMUNICATIONS CABINET, which price shall be payment in full for furnishing all associated equipment and labor, and installing the cabinet as shown on the plans and to the satisfaction of the Engineer. The Layer III switch, fiber optic splices and terminations, the video transmission system, if applicable, and the concrete foundation for the cabinet shall be paid for separately.

LAYER II (DATA LINK) SWITCH

This specification sets forth the minimum requirements for a layer II Ethernet switch that will transmit data from one traffic signal cabinet to another traffic signal cabinet containing a layer II switch or a layer III (Network) switch. The layer II switch shall be a Cisco Catalyst 2955 Series Intelligent Ethernet Switch, or approved equal.

The Layer II (Data Link) Switch shall be procured from Delcan, the County's Passage engineering consultant. Delcan shall program this equipment for the appropriate location in the County's communication network.

The layer II switch and its power supply shall be mounted to either a standard DIN rail or an equipment mounting channel in the cabinet. The power supply shall be hard-wired to the cabinet power, not plugged into one of the traffic signal cabinet power outlets.

Basis of Payment. This item will be paid for at the contract unit price each for LAYER II (DATA LINK) SWITCH, which price shall be payment in full for furnishing and installing the switch, and all necessary connectors, cables, fiber optic jumpers, hardware, software, other peripheral equipment, and placing it in operation to the satisfaction of the Engineer. The VIDEO ENCODER, MEDIA CONVERTERS, and TERMINAL SERVERS shall be paid for separately.

LAYER III (NETWORK) SWITCH

This specification sets forth the minimum requirements for a layer III switch that will transmit video data from one traffic signal cabinet to another traffic signal cabinet or to another location having a layer III switch. The layer III switch shall be a Cisco Catalyst 3560 Series Intelligent Ethernet Switch, or approved equal.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

The Layer III (Network) Switch shall be procured from Delcan, the County's Passage engineering consultant. Delcan shall program this equipment for the appropriate location in the County's communication network.

The layer III switch shall be mounted to the 19-inch equipment rack inside the cabinet. The layer III switch shall be plugged into the 15A power distribution unit inside the cabinet.

Basis of Payment. This item will be paid for at the contract unit price each for LAYER III (NETWORK) SWITCH, which price shall be payment in full for furnishing and installing the switch, and all necessary connectors, cables, fiber optic jumpers, hardware, software, other peripheral equipment, and placing it in operation to the satisfaction of the Engineer. The VIDEO ENCODER, LAYER III FIBER OPTIC TRANSCEIVER MODULES, MEDIA CONVERTERS, and TERMINAL SERVERS shall be paid for separately.

FIBER OPTIC TRANSCEIVER MODULE, SFP TYPE, LONG DISTANCE

This specification sets forth the minimum requirements for a fiber optic transceiver module that plugs into a Cisco layer III gigabit ethernet switch. The module shall be a small form pluggable (SFP), long distance, single mode transceiver, Cisco GLC-LH-SM, or approved equivalent. The transceiver shall be installed in the Cisco layer III switch at the location shown on the plans.

Basis of payment. This item will be paid for at the contract unit price each for FIBER OPTIC TRANSCEIVER MODULE, SFP TYPE, LONG DISTANCE, which price shall be payment in full for furnishing and installing the module, and all necessary connectors, cables, hardware, software, other peripheral equipment, and placing it in operation to the satisfaction of the Engineer.

FIBER OPTIC TRANSCEIVER MODULE, SFP TYPE, EXTRA LONG DISTANCE

This specification sets forth the minimum requirements for a fiber optic transceiver module that plugs into a Cisco layer III gigabit ethernet switch. The module shall be a small form pluggable (SFP), extra-long distance, single mode transceiver, Cisco GLC-ZX-SM, or approved equivalent. The transceiver shall be installed in the Cisco layer III switch at the location shown on the plans.

Basis of payment. This item will be paid for at the contract unit price each for FIBER OPTIC TRANSCEIVER MODULE, SFP TYPE, EXTRA LONG DISTANCE, which price shall be payment in full for furnishing and installing the module, and all necessary connectors, cables, hardware, software, other peripheral equipment, and placing it in operation to the satisfaction of the Engineer.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

FIBER OPTIC TRANSCEIVER MODULE, GBIC TYPE, LONG DISTANCE

This specification sets forth the minimum requirements for a fiber optic transceiver module that plugs into a Cisco layer III gigabit ethernet switch. The module shall be a Gigabit Interface Converter (GBIC) type, long distance, single mode transceiver, Cisco WS-G5486, or approved equivalent. The transceiver shall be installed in the Cisco layer III switch at the location shown on the plans. This type of transceiver module is intended for use with earlier models of Cisco layer III switches.

Basis of payment. This item will be paid for at the contract unit price each for FIBER OPTIC TRANSCEIVER MODULE, GBIC TYPE, LONG DISTANCE, which price shall be payment in full for furnishing and installing the module, and all necessary connectors, cables, hardware, software, other peripheral equipment, and placing it in operation to the satisfaction of the Engineer.

FIBER OPTIC TRANSCEIVER MODULE, GBIC TYPE, EXTRA LONG DISTANCE

This specification sets forth the minimum requirements for a fiber optic transceiver module that plugs into a Cisco layer III gigabit Ethernet switch. The module shall be a Gigabit Interface Converter (GBIC) type, extra long distance, single mode transceiver, Cisco WS-G5487, or approved equivalent. The transceiver shall be installed in the Cisco layer III switch at the location shown on the plans. This type of transceiver module is intended for use with earlier models of Cisco layer III switches.

Basis of payment. This item will be paid for at the contract unit price each for FIBER OPTIC TRANSCEIVER MODULE, GBIC TYPE, EXTRA LONG DISTANCE, which price shall be payment in full for furnishing and installing the module, and all necessary connectors, cables, hardware, software, other peripheral equipment, and placing it in operation to the satisfaction of the Engineer.

VIDEO ENCODER

This specification sets forth the minimum requirements for a video encoder that will transmit video data from one traffic signal cabinet to another traffic signal cabinet or to another location having a layer three switch.

The video encoder shall be an Optelecom Model C-50e MPEG-4 video encoder/decoder, or an Optelecom Model C-54e E-MC 4-channel MPEG-4 encoder, as shown on the plans, or approved equivalent. Other video encoder/decoders submitted for approval must be compatible with the Lake County Passage Advanced Traffic Management System (ATMS) software and VideoLAN VLC Media Player Release 0.8.6D or later.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

The VIDEO ENCODER shall be procured from Delcan, the County's Passage engineering consultant. Delcan shall program this equipment for the appropriate location in the County's communication network.

The video encoder shall be mounted on a 16 gauge (min.) aluminum plate, and the plate shall be mounted to the cabinet side rails.

The power supply shall be mounted to either a standard DIN rail or an equipment mounting channel in the cabinet. The power supply shall be hard-wired to the cabinet power, not plugged into one of the traffic signal cabinet power outlets.

Basis of payment. This item will be paid for at the contract unit price each for VIDEO ENCODER, which price shall be payment in full for furnishing and installing the encoder, and all necessary connectors, cables, hardware, software, other peripheral equipment, and placing it in operation to the satisfaction of the Engineer.

MEDIA CONVERTER

This specification sets forth the minimum requirements for an unmanaged Ethernet switch that performs copper-to-fiber media conversion at 10/100Mbps speeds.

The media converter shall be a Ruggedcom RMC40 Series, (Model RMC40-HI-C200) four-port, unmanaged Ethernet switch, or approved equivalent. The power supply shall be the HI voltage type (85-264VAC) and ports 3 and 4 shall be for single-mode fiber with SC connectors.

The media converter shall be mounted to either a standard DIN rail or an equipment mounting channel in the cabinet. The power supply shall be hard-wired to the traffic signal cabinet power, not plugged into one of the traffic signal cabinet power outlets. When the media converter is mounted within a communications cabinet, the power supply shall be connected to the power distribution center.

Basis of payment. This item will be paid for at the contract unit price each for MEDIA CONVERTER, which price shall be payment in full for furnishing and installing the media converter, and all necessary connectors, cables, fiber optic jumpers, hardware, software, other peripheral equipment, and placing it in operation to the satisfaction of the Engineer.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

TERMINAL SERVER

This specification sets forth the minimum requirements for a terminal server that will transmit signal controller data from one or more traffic signal controllers onto the Lake County PASSAGE Gigabit Ethernet network.

The terminal server shall be a Digi PortServer TS Hcc 4 four-port serial-to-Ethernet device, or approved equivalent, installed at the location shown on the plans. The terminal server shall be properly configured for its location within the Lake County PASSAGE Network, and for proper communication with the signal equipment being connected to it.

Basis of payment. This item will be paid for at the contract unit price each for TERMINAL SERVER, which price shall be payment in full for furnishing, installing, and configuring the terminal server, and all necessary connectors, cables, hardware, software, other peripheral equipment, and placing it in operation to the satisfaction of the Engineer.

FIBER OPTIC CABLE

Add the following to Section 871 and Section 1076.02 of the "Standard Specifications":

This work shall consist of furnishing and installing Fiber Optical cable in conduit with all accessories and connectors. The cable shall be of the type, size, and the number of fibers specified with twelve fibers per buffer tube.

The distribution enclosure shall be a Corning Model WIC-04P Wall-Mountable Interconnect Center, or approved equivalent, capable of accommodating the required number of fibers. The distribution enclosure shall be included in the cost of the fiber optic cable, including connections to any existing cables.

All fibers being terminated shall be connected to the distribution enclosure and labeled at the connector and also at the enclosure bulkhead. The label shall include the direction and also the fiber number (e.g. S1, S2, N11, N12).

~~All splices and terminations on the installed fiber optic cable shall be included in the cost of the fiber optic cable. The splicing of the installed fiber optic cable to any existing fiber optic cable shall be included in the cost of this pay item.~~

All terminations and splices required only on existing fiber optic cable shall be paid for separately in accordance with the pay item TERMINATE FIBER IN CABINET or SPLICE FIBER IN CABINET.

The quality of the fiber optic cable, including all splices and terminations, shall be verified by

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

testing and documentation in accordance with Article 801.13(d) of the "Standard Specifications", to the satisfaction of the Engineer.

Multimode: The contractor shall coordinate with the equipment vendor, and shall terminate as many multimode fibers as are necessary to establish proper communications with signal controllers and/or video transmission equipment. In addition, the contractor shall terminate four unused multimode fibers and attach them to the distribution enclosure. All multimode terminations shall be ST compatible connectors with ceramic ferrules.

Singlemode: The contractor shall splice and/or terminate the number of singlemode fibers shown on the project plans, if any. Singlemode fiber terminations shall utilize pre-fabricated, factory-terminated pigtailed fusion spliced to bare fibers. The pre-fabricated pigtailed shall have all of their fibers color coded to match the singlemode fibers in the fiber optic cable. All fusion splices shall be secured on Corning splice trays, Models M67-068, M67-110, or approved equivalent, capable of accommodating the required number of fusion splices. All single-mode connectors shall be SC compatible, with ceramic ferrules.

A minimum of 13 feet of slack cable shall be provided for the controller cabinet. The controller cabinet slack cable shall be stored as directed by the Engineer.

Fiber Optic cable may be gel filled or have an approved water blocking tape.

Basis of Payment. The work shall be paid for at the contract unit price per foot for FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 24 FIBER (12 MULTIMODE AND 12 SINGLEMODE), (FIBER OPTIC CABLE IN CONDUIT, 24 SINGLEMODE) or as specified in plans for the cable in place, including distribution enclosure(s), all connectors, pigtailed, splice trays, connector bulkheads, testing and documentation, and the required number of fiber splices and terminations described in the plans. Additional fiber terminations and/or splices required by the Engineer, (not included in this item), shall be paid for as TERMINATE FIBER IN CABINET and/or SPLICE FIBER IN CABINET.

TERMINATE FIBER IN CABINET

This work shall consist of terminating existing or new fibers in field cabinets or buildings as indicated on the plans or as directed by the Engineer.

All multi-mode connectors shall be ST compatible, with ceramic ferrules. Singlemode fiber terminations shall utilize pre-fabricated, factory-terminated (SC compatible) pigtailed fusion spliced to bare fibers. . The pre-fabricated pigtailed shall have all of their fibers color coded to match the singlemode fibers in the fiber optic cable. All fusion splices shall be secured on Corning splice trays, Models M67-068, M67-110, or approved equivalent, capable of accommodating the required number of fusion splices. Splice trays and connector bulkheads shall be included in the cost of TERMINATE FIBER IN CABINET, and shall not be paid for

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

separately. Connector bulkheads shall be the proper type for the fiber enclosure at the location, and shall be properly secured to the enclosure.

The quality of all fiber splices shall be verified by testing and documentation in accordance with Article 801.13(d) of the "Standard Specifications", to the satisfaction of the Engineer.

Basis of payment. This work shall be paid for at the contract unit price each for each fiber terminated in a field cabinet or inside a building as TERMINATE FIBER IN CABINET, which will be payment in full for terminating each required multimode or singlemode fiber, including all connectors, pigtails, splice trays, bulkheads, testing and documentation. The splicing of pigtails for singlemode fibers is included in the cost of TERMINATE FIBER IN CABINET, and shall not be paid for separately. This pay item shall not be used to pay for fiber terminations and/or splices completed to meet the requirements of FIBER OPTIC CABLE IN CONDUIT.

SPLICE FIBER IN CABINET

This work shall consist of fusion splicing singlemode fibers in a field cabinet or inside a building as indicated on the plans and as directed by the Engineer. Splices shall be secured in fiber optic splice trays within fiber optic distribution enclosures. The splice trays shall be Corning Models M67-068, M67-110, or approved equivalent, capable of accommodating the required number of fusion splices. Splice trays shall be included in the cost of SPLICE FIBER IN CABINET and shall not be paid for separately.

The quality of all fiber splices shall be verified by testing and documentation in accordance with Article 801.13(d) of the "Standard Specifications", to the satisfaction of the Engineer.

All optical fibers shall be spliced to provide continuous runs. Splices shall only be allowed in equipment cabinets except where otherwise shown on the Plans.

All splices shall be made using a fusion splicer that automatically positions the fibers using a system of light injection and detection. The Contractor shall provide all equipment and consumable supplies.

Basis of payment. This work shall be paid for at the contract unit price each for SPLICE FIBER IN CABINET, which will be payment in full for all fusion splicing, fiber optic splice trays, testing and documentation, at a cabinet or building location shown on the plans and as directed by the Engineer. This pay item shall not be used to pay for fiber terminations and/or splices completed to meet the requirements of FIBER OPTIC CABLE IN CONDUIT.

FIBER OPTIC TRACER CABLE

The cable shall meet the requirements of Section 817 of the "Standard Specifications", except for the following:

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

In order to trace the fiber optic cable after installation, an XLP black insulated copper cable No. 14 shall be pulled in the same conduit as the fiber optic cable. The tracer cable shall be continuous, and extend a minimum of 3 feet into the controller cabinet. The tracer cable shall be clearly marked and identified. In order to minimize the number of splices required, the tracer cable shall incorporate maximum lengths of cable supplied by the manufacturer. Splicing of the tracer cable will be allowed at the handholes only. The tracer cable splice shall use a Western Union splice soldered with resin core flux. All exposed surfaces of the solder shall be smooth. Splices shall be soldered using a soldering iron. Blowtorches or other devices which oxidize copper cable shall not be allowed for soldering operations. The splice shall be covered with underwater grade WCSMW 30/100 heat shrink tube, minimum length four (4) inches and with a minimum one (1) inch coverage over the XLP insulation.

Basis of payment. The tracer cable shall be paid for separately as ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C per foot, which price shall include all associated labor and material for installation.

WIRELESS TRANSMISSION SYSTEM SHORT RANGE

This work shall consist of the installation of a new node on the Lake County PASSAGE wireless network. This item includes the directional antenna and power injector, associated cables / wiring, and all mounting hardware.

The WIRELESS TRANSMISSION SYSTEM SHORT RANGE includes:

- One (1) Proxim TsunamiMP.11 5054-R Subscriber unit with Integrated 23dBi Antenna (Model 5054-SUR-US) or approved equivalent.
- Two (2) Proxim Model 76394 surge suppressors, or approved equivalent.
- Power wiring from the radio power injector to the circuit breaker.
- All mounting hardware.

All components of this item shall be installed as shown on the plans. The radio transceiver and antenna shall be installed as high as possible on the mast arm assembly pole. The antenna shall be directed / aimed at another antenna on the County's wireless system, (e.g. aimed at a sector antenna on a water tower), as shown on the plans and as directed by the Engineer. The power injector shall be installed inside the traffic signal cabinet.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires.

The WIRELESS TRANSMISSION SYSTEM SHORT RANGE electronics shall be procured from Delcan, the County's Passage engineering consultant. Delcan shall program this equipment for

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

the appropriate location in the County's communication network.

Basis of payment. This item will be paid for at the contract unit price each for WIRELESS TRANSMISSION SYSTEM SHORT RANGE, which price shall be payment in full for furnishing and installing the power injector, antenna, and all associated connectors, cables, hardware, and other peripheral equipment, and placing it in operation to the satisfaction of the Engineer. The Outdoor Rated Network Cable from the antenna to the traffic signal cabinet shall be paid for separately.

WIRELESS TRANSMISSION SYSTEM LONG RANGE

This work shall consist of the installation of a new node on the Lake County PASSAGE wireless network. This item includes the directional antenna and power injector, associated cables / wiring, and all mounting hardware.

The WIRELESS TRANSMISSION SYSTEM LONG RANGE includes:

- One (1) Proxim TsunamiMP.11 5054-R-LR Subscriber unit for extended range with Integrated 23dBi Antenna (Model 5054-SUR-LR-US) or approved equivalent.
- Two (2) Proxim Model 76394 surge suppressors, or approved equivalent.
- Power wiring from the radio power injector to the circuit breaker.
- All mounting hardware.

All components of this item shall be installed as shown on the plans. The radio transceiver and antenna shall be installed as high as possible on the mast arm assembly pole. The antenna shall be directed / aimed at another antenna on the County's wireless system, (e.g. aimed at a sector antenna on a water tower), as shown on the plans and as directed by the Engineer. The power injector shall be installed inside the traffic signal cabinet.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires.

The WIRELESS TRANSMISSION SYSTEM LONG RANGE electronics shall be procured from Delcan, the County's Passage engineering consultant. Delcan shall program this equipment for the appropriate location in the County's communication network.

Basis of payment. This item will be paid for at the contract unit price each for WIRELESS TRANSMISSION SYSTEM LONG RANGE, which price shall be payment in full for furnishing and installing the power injector, antenna, and all associated connectors, cables, hardware, and

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

other peripheral equipment, and placing it in operation to the satisfaction of the Engineer. The Outdoor Rated Network Cable from the antenna to the traffic signal cabinet shall be paid for separately.

WIRELESS TRANSMISSION SYSTEM EXTRA LONG RANGE

This work shall consist of the installation of a new node on the Lake County PASSAGE wireless network. This item includes the radio, directional antenna and power injector, associated cables / wiring, and all mounting hardware.

The WIRELESS TRANSMISSION SYSTEM EXTRA LONG RANGE includes:

- One (1) Proxim TsunamiMP.11 (Model 5054-SUA-LR-US) Subscriber unit for extended range with type N connector
- One (1) RadioWaves 28dBi Antenna (Model FP2-5-28) or approved equivalent.
- One (1) low loss RF coaxial cable, 3 foot, N to N
- Two (2) Proxim Model 76394 surge suppressors, or approved equivalent.
- Power wiring from the radio power injector to the circuit breaker.
- All mounting hardware.

All components of this item shall be installed as shown on the plans. The radio transceiver and antenna shall be installed as high as possible on the mast arm assembly pole. The antenna shall be directed / aimed at another antenna on the County's wireless system, (e.g. aimed at a sector antenna on a water tower), as shown on the plans and as directed by the Engineer. The power injector shall be installed inside the traffic signal cabinet.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires.

The WIRELESS TRANSMISSION SYSTEM EXTRA LONG RANGE electronics shall be procured from Delcan, the County's Passage engineering consultant. Delcan shall program this equipment for the appropriate location in the County's communication network.

Basis of payment. This item will be paid for at the contract unit price each for WIRELESS TRANSMISSION SYSTEM EXTRA LONG RANGE, which price shall be payment in full for furnishing and installing the power injector, antenna, and all associated connectors, cables, hardware, and other peripheral equipment, and placing it in operation to the satisfaction of the Engineer. The Outdoor Rated Network Cable from the radio to the traffic signal cabinet shall be paid for separately.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

WIRELESS TRANSMISSION SYSTEM POINT TO POINT

This work shall consist of the installation of a new node on the Lake County PASSAGE wireless network. This item includes the directional antenna and power injector, associated cables / wiring, and all mounting hardware.

The WIRELESS TRANSMISSION SYSTEM POINT TO POINT includes:

- One (1) Proxim Tsunami Quick Bridge unit with Integrated 23dBi Antenna (Model QB-8150-LINK-US) or approved equivalent.
- Two (2) Proxim Model 76394 surge suppressors, or approved equivalent.
- Power wiring from the radio power injector to the circuit breaker.
- All mounting hardware.

All components of this item shall be installed as shown on the plans. The radio transceiver and antenna shall be installed as high as possible on the mast arm assembly pole. The antenna shall be directed / aimed at another antenna on the County's wireless system, (e.g. aimed at corresponding antenna at other intersection), as shown on the plans and as directed by the Engineer. The power injector shall be installed inside the traffic signal cabinet.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires.

The WIRELESS TRANSMISSION SYSTEM POINT TO POINT electronics shall be procured from Delcan, the County's Passage engineering consultant. Delcan shall program this equipment for the appropriate location in the County's communication network.

Basis of payment. This item will be paid for at the contract unit price each for WIRELESS TRANSMISSION SYSTEM POINT TO POINT, which price shall be payment in full for furnishing and installing the power injector, antenna, and all associated connectors, cables, hardware, and other peripheral equipment, and placing it in operation to the satisfaction of the Engineer. The Outdoor Rated Network Cable from the antenna to the traffic signal cabinet shall be paid for separately.

WIRELESS TRANSMISSION SYSTEM BACKHAUL

This work shall consist of the installation of a new node on the Lake County PASSAGE wireless network. This item includes the directional antenna and power injector, associated cables / wiring, and all mounting hardware.

The WIRELESS TRANSMISSION SYSTEM BACKHAUL includes:

- One (1) Proxim Tsunami licensed backhaul radio (Model GX-800) or approved

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

equivalent.

- One (1) 2 foot dish antenna or other as specified on plans
- Two (2) Proxim Model 76394 surge suppressors, or approved equivalent.
- Power wiring from the radio power injector to the circuit breaker.
- All mounting hardware.

All components of this item shall be installed as shown on the plans. The radio transceiver and antenna shall be installed as high as possible on the mast arm assembly pole or tower as shown on plans. The antenna shall be directed / aimed at another antenna on the County's wireless system, (e.g. aimed at corresponding antenna at other intersection / tower), as shown on the plans and as directed by the Engineer. The power injector shall be installed inside the traffic signal / grade level cabinet.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires.

The WIRELESS TRANSMISSION SYSTEM BACKHAUL electronics shall be procured from Delcan, the County's Passage engineering consultant. Delcan shall program this equipment for the appropriate location in the County's communication network.

Basis of payment. This item will be paid for at the contract unit price each for WIRELESS TRANSMISSION SYSTEM BACKHAUL, which price shall be payment in full for furnishing and installing the power injector, antenna, and all associated connectors, cables, hardware, and other peripheral equipment, and placing it in operation to the satisfaction of the Engineer. The Outdoor Rated Network Cable from the antenna to the traffic signal cabinet shall be paid for separately.

WIRELESS TRANSMISSION SYSTEM BASE STATION

This work shall consist of the installation of a new node on the Lake County PASSAGE wireless network. This item includes the directional antenna and power injector, associated cables / wiring, and all mounting hardware.

The WIRELESS TRANSMISSION SYSTEM BASE STATION includes:

- One (1) Proxim Tsunami base station long range unit (Model 5054-BSU-R-LR) or approved equivalent.
- One (1) 60 degree sector antenna or other as shown on the plans.
- Two (2) Proxim Model 76394 surge suppressors, or approved equivalent.
- Power wiring from the radio power injector to the circuit breaker.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

- All mounting hardware and poles.

All components of this item shall be installed as shown on the plans. The radio transceiver and antenna shall be installed on a new mounting pole or other as shown on the plans. The antenna shall be directed / aimed according to the azimuth settings listed in the plans and as directed by the Engineer. The power injector shall be installed inside the cabinet.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires.

The WIRELESS TRANSMISSION SYSTEM BASE STATION electronics shall be procured from Delcan, the County's Passage engineering consultant. Delcan shall program this equipment for the appropriate location in the County's communication network.

Basis of payment. This item will be paid for at the contract unit price each for WIRELESS TRANSMISSION SYSTEM BASE STATION, which price shall be payment in full for furnishing and installing the power injector, antenna, and all associated connectors, cables, hardware, and other peripheral equipment, and placing it in operation to the satisfaction of the Engineer. The Outdoor Rated Network Cable from the antenna to the cabinet shall be paid for separately.

RELOCATE EXISTING VIDEO DETECTION SYSTEM (COMPLETE INTERSECTION)

This work shall consist of the removal, storage, and relocation of an existing video detection system (complete intersection) from one traffic signal installation (temporary or permanent) to another traffic signal installation (temporary or permanent). This item shall also include the relocation of the remote-controlled video system according to the plans.

The video detection system (complete intersection) shall be removed and relocated as shown in the plans. Any damage sustained to the video detection system during removal, storage, transport, and/or reinstallation operations shall be repaired or replaced in kind to the satisfaction of the Engineer at the Contractor's expense.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires.

Basis of payment. This item will be paid for at the contract unit price each for RELOCATE EXISTING VIDEO DETECTION SYSTEM (COMPLETE INTERSECTION), which price shall be payment in full for disconnecting the existing video detection system, remote-controlled video system, packaging/storing it, transporting it, and relocating it to the new location complete and

operating to the satisfaction of the Engineer.

RELOCATE EXISTING REMOTE-CONTROLLED VIDEO SYSTEM

This work shall consist of the removal, storage, and relocation of an existing remote-controlled video system from one traffic signal installation (temporary or permanent) to another traffic signal installation (temporary or permanent). This pay item shall be used when only the remote-controlled video system is being relocated. This pay item shall not be used when the remote-controlled video system is being relocated as part of RELOCATE EXISTING VIDEO DETECTION SYSTEM (COMPLETE INTERSECTION).

The remote-controlled video system shall be removed and relocated as shown in the plans. Any damage sustained to the remote-controlled video system during removal, storage, transport, and/or reinstallation operations shall be repaired or replaced in kind to the satisfaction of the Engineer at the Contractor's expense.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent chafing of wires.

Basis of payment. This item will be paid for at the contract unit price each for RELOCATE EXISTING REMOTE-CONTROLLED VIDEO SYSTEM, which price shall be payment in full for disconnecting the existing remote-controlled video system, packaging/storing it, transporting it, and relocating it to the new location complete and operating to the satisfaction of the Engineer.

RELOCATE EXISTING SWITCH

This work shall consist of the removal, storage, and relocation of an existing layer two or layer three switch from one traffic signal installation to another traffic signal installation.

The switch shall be removed and relocated as shown in the plans. Any damage sustained to the switch during removal, storage, transport, and/or reinstallation operations shall be repaired or replaced in kind to the satisfaction of the Engineer at the Contractor's expense.

Basis of payment. This item will be paid for at the contract unit price each for RELOCATE EXISTING SWITCH, which price shall be payment in full for disconnecting the existing switch, packaging/storing it, transporting it, and relocating it to the new location complete and operating to the satisfaction of the Engineer. This item shall also include the relocation and reinstallation of the switch power supply, and all fiber optic jumper cables necessary for proper operation.

TEMPORARY TRAFFIC SIGNAL TIMING

This work shall consist of developing and maintaining appropriate traffic signal timings for the specified intersection for the entirety of the construction project beginning with any changes to the existing traffic patterns including lane shifts or lane reductions. This shall include the period

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

prior to the turn-on of any temporary traffic signal installation. This item can also be utilized to make temporary timing adjustments to existing traffic signals required by detours or other temporary conditions.

All timings and adjustments necessary for this work shall be performed by an approved Consultant who has previous experience in optimizing Closed Loop Traffic signal Systems for District One of the Illinois Department of Transportation. The Contractor shall contact the Traffic Signal Engineer at (847) 705-4424 for a listing of approved Consultants.

The following tasks are associated with TEMPORARY TRAFFIC SIGNAL TIMINGS.

- (a) Consultant shall attend temporary traffic signal inspection (turn-on) and/or detour meeting and conduct on-site implementation of the traffic signal timings. Make fine-tuning adjustments to the timings in the field to alleviate observed adverse operating conditions and to enhance operations.
- (b) Consultant shall provide monthly observation of traffic signal operations in the field.
- (c) Consultant shall provide on-site consultation and adjust timings as necessary for construction stage changes, temporary traffic signal phase changes, and any other conditions affecting timing and phasing, including lane closures, detours, and other construction activities.
- (d) Consultant shall make timing adjustments and prepare comment responses as directed by the Area Traffic Signal Operations Engineer.

Basis of Payment. The work shall be paid for at the contract unit price each for TEMPORARY TRAFFIC SIGNAL TIMING, which price shall be payment in full for performing all work described herein per intersection. When the temporary traffic signal installation is turned on, traffic control is installed, or the detour is implemented, 50 percent of the bid price will be paid. The remaining 50 percent of the bid price will be paid following the removal of the temporary traffic signal installation, traffic control and/or detour.

RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM

Description. This work shall consist of re-optimizing a closed loop traffic signal system according to the following Levels of work.

LEVEL I applies when improvements are made to an existing signalized intersection within an existing closed loop traffic signal system. The purpose of this work is to integrate the improvements to the subject intersection into the signal system while minimizing the impacts to the existing system operation. This type of work would be commonly associated with the addition of signal phases, pedestrian phases, or improvements that do not affect the capacity at an intersection.

LEVEL II applies when improvements are made to an existing signalized intersection within an

existing closed loop traffic signal system and detailed analysis of the intersection operation is desired by the engineer, or when a new signalized or existing signalized intersection is being added to an existing system, but optimization of the entire system is not required. The purpose of this work is to optimize the subject intersection, while integrating it into the existing signal system with limited impact to the system operations. This item also includes an evaluation of the overall system operation, including the traffic responsive program.

For the purposes of re-optimization work, an intersection shall include all traffic movements operated by the subject controller and cabinet.

After the signal improvements are completed, the signal shall be re-optimized as specified by an approved Consultant who has previous experience in optimizing Closed Loop Traffic Signal Systems for District One of the Illinois Department of Transportation. The Contractor shall contact the Traffic Signal Engineer at (847) 377-7000 for a listing of approved Consultants. Traffic signal system optimization work, including fine-tuning adjustments of the optimized system, shall follow the requirements stated in the most recent IDOT District 1 SCAT Guidelines, except as note herein.

All work shall be based upon the LCDOT Countywide Synchro model. The Consultant shall contact the LCDOT at 847-377-7000 to acquire the required portion of the countywide model to be updated for the particular project. Upon completion of the project, the Consultant shall provide the LCDOT with the revised and updated files for inclusion into the Countywide Synchro Model.

The Consultant shall confer with the Traffic Signal Engineer prior to optimizing the system to determine if any extraordinary conditions exist that would affect traffic flows in the vicinity of the system, in which case, the Consultant may be instructed to wait until the conditions return to normal or to follow specific instructions regarding the optimization.

(a) LEVEL I Re-Optimization

1. The following tasks are associated with LEVEL I Re-Optimization.
 - a. Appropriate signal timings shall be developed for the subject intersection and existing timings shall be utilized for the rest of the intersections in the system.
 - b. Proposed signal timing plan for the new or modified intersection(s) shall be forwarded to the County for review prior to implementation.
 - c. Consultant shall conduct on-site implementation of the timings at the turn-on and make fine-tuning adjustments to the timings of the subject intersection in the field to alleviate observed adverse operating conditions and to enhance operations.
 - d. All patterns associated with Transit Signal Priority and Incident Response Plans are to be reviewed and adjusted as required.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

2. The following deliverables shall be provided for LEVEL I Re-Optimization.
 - a. Consultant shall furnish to the County a cover letter describing the extent of the re-optimization work performed.

(b) LEVEL II Re-Optimization

1. In addition to the requirements described in the LEVEL I Re-Optimization above, the following tasks are associated with LEVEL II Re-Optimization.
 - a. Traffic counts shall be taken at the subject intersection after the traffic signals are approved for operation by the Area Traffic Signal Operations Engineer. Manual turning movement counts shall be conducted from 6:30 a.m. to 9:30 a.m., 11:00 a.m. to 1:00 p.m., and 3:30 p.m. to 6:30 p.m. on a typical weekday from midday Monday to midday Friday. The turning movement counts shall identify cars, and single-unit, multi-unit heavy vehicles, and transit buses.
 - b. Traffic responsive program operation shall be evaluated to verify proper pattern selection and lack of oscillation and a report of the operation shall be provided to IDOT.
 - c. All patterns associated with Transit Signal Priority and Incident Response Plans are to be reviewed and adjusted as required.
2. The following deliverables shall be provided for LEVEL II Re-Optimization.
 - a. Consultant shall furnish to the County one (1) copy of a technical memorandum for the optimized system. The technical memorandum shall include the following elements:
 1. Brief description of the project
 2. Printed copies of the analysis output from Synchro (or other appropriate approved optimization software file)
 3. Printed copies of the traffic counts conducted at the subject intersection
 - b. Consultant shall furnish to the County two (2) CDs for the optimized system. The CDs shall include the following elements:
 1. Electronic copy of the technical memorandum in PDF format
 2. Revised Synchro files (or other appropriate, approved optimization software file) including the new signal and the rest of the signals in the closed loop system or as identified by the Engineer
 3. Traffic counts conducted at the subject intersection
 4. The CD case shall include a clearly readable label displaying the same information securely affixed to the side and front.

Basis of Payment. This work shall be paid for at the contract unit price each for RE-OPTIMIZE

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

TRAFFIC SIGNAL SYSTEM – LEVEL I or RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM – LEVEL II, which price shall be payment in full for performing all work described herein per intersection. Following completion of the timings and submittal of specified deliverables, 100 percent of the bid price will be paid. Each intersection will be paid for separately.

OPTIMIZE TRAFFIC SIGNAL SYSTEM

Description. This work shall consist of optimizing a closed loop traffic signal system.

OPTIMIZE TRAFFIC SIGNAL SYSTEM applies when a new or existing closed loop traffic signal system is to be optimized and a formal Signal Coordination and Timing (SCAT) Report is to be prepared. The purpose of this work is to improve system performance by optimizing traffic signal timings, developing a time of day program and a traffic responsive program.

After the signal improvements are completed, the signal system shall be optimized as specified by an approved Consultant who has previous experience in optimizing Closed Loop Traffic Signal Systems for District One of the Illinois Department of Transportation. The Contractor shall contact the Traffic Signal Engineer at (847) 377-7000 for a listing of approved Consultants. Traffic signal system optimization work, including fine-tuning adjustments of the optimized system, shall follow the requirements stated in the most recent IDOT District 1 SCAT Guidelines, except as note herein.

All work shall be based upon the LCDOT Countywide Synchro model. The Consultant shall contact the LCDOT at 847-377-7000 to acquire the required portion of the countywide model to be updated for the particular project. Upon completion of the project, the Consultant shall provide the LCDOT with the revised and updated files for inclusion into the Countywide Synchro Model.

The Consultant shall confer with the Traffic Signal Engineer prior to optimizing the system to determine if any extraordinary conditions exist that would affect traffic flows in the vicinity of the system, in which case, the Consultant may be instructed to wait until the conditions return to normal or to follow specific instructions regarding the optimization.

(a) ~~The following tasks are associated with OPTIMIZE TRAFFIC SIGNAL SYSTEM.~~

1. Appropriate signal timings and offsets shall be developed for each intersection and appropriate cycle lengths shall be developed for the closed loop signal system or as identified by Engineer.
2. All patterns associated with Transit Signal Priority and Incident Response Plans are to be developed as required.
3. Traffic counts shall be taken at all intersections after the permanent traffic signals are approved for operation by the Area Traffic Signal Operations Engineer. Manual turning

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

movement counts shall be conducted from 6:30 a.m. to 9:30 a.m., 11:00 a.m. to 1:00 p.m., and 3:30 p.m. to 6:30 p.m. on a typical weekday from midday Monday to midday Friday. The turning movement counts shall identify cars, and single-unit and multi-unit heavy vehicles.

4. A traffic responsive program shall be developed, which considers both volume and occupancy. A time-of-day program shall be developed for used as a back-up system.
5. Proposed signal timing plan for the new or modified intersection shall be forwarded to the County for review prior to implementation.
6. Consultant shall conduct on-site implementation of the timings and make fine-tuning adjustments to the timings in the field to alleviate observed adverse operating conditions and to enhance operations.
7. Speed and delay studies shall be conducted during each of the count periods along the system corridor in the field before and after implementation of the proposed timing plans for comparative evaluations. These studies should utilize specialized electronic timing and measuring devices.

(b) The following deliverables shall be provided for OPTIMIZE TRAFFIC SIGNAL SYSTEM.

1. Consultant shall furnish to the County one (1) copy of a SCAT Report for the optimized system. The SCAT Report shall include the following elements:

<p>Cover Page in color showing a System Map</p> <p>Figures</p> <ol style="list-style-type: none"> 1. System overview map – showing system number, system schematic map with numbered system detectors, oversaturated movements, master location, system phone number, cycle lengths, and date of completion. 2. General location map in color – showing signal system location in the metropolitan area. 3. Detail system location map in color – showing cross street names and local controller addresses. 4. Controller sequence – showing controller phase sequence diagrams.
<p>Table of Contents</p> <p>Tab 1: Final Report</p> <ol style="list-style-type: none"> 1. Project Overview 2. System and Location Description (Project specific) 3. Methodology 4. Data Collection 5. Data Analysis and Timing Plan Development 6. Implementation <ol style="list-style-type: none"> a. Traffic Responsive Programming (Table of TRP vs. TOD Operation) 7. Evaluation <ol style="list-style-type: none"> a. Speed and Delay runs
<p>Tab 2. Turning Movement Counts</p> <ol style="list-style-type: none"> 1. Turning Movement Counts (Showing turning movement counts in the intersection diagram for each period, including truck percentage)
<p>Tab 3. Synchro Analysis</p> <ol style="list-style-type: none"> 1. AM: Time-Space diagram in color, followed by intersection Synchro report (Timing report) summarizing the implemented timings. 2. Midday: same as AM 3. PM: same as AM
<p>Tab 4: Speed, Delay Studies</p> <ol style="list-style-type: none"> 1. Summary of before and after runs results in two (2) tables showing travel time and delay time. 2. Plot of the before and after runs diagram for each direction and time period.
<p>Tab 5: Environmental Report</p> <ol style="list-style-type: none"> 1. Environmental impact report including gas consumption, NO2, HCCO, improvements.
<p>Tab 6: Electronic Files</p> <ol style="list-style-type: none"> 1. Two (2) CDs for the optimized system. The CDs shall include the following elements: <ol style="list-style-type: none"> a. Electronic copy of the SCAT Report in PDF format b. Copies of the Synchro files for the optimized system c. Traffic counts for the optimized system d. New or updated intersection graphic display files for each of the system intersections and the system graphic display file including system detector locations and addresses.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

Basis of Payment. The work shall be paid for at the contract unit each for OPTIMIZE TRAFFIC SIGNAL SYSTEM, which price shall be payment in full for performing all work described herein for the entire traffic signal system. Following the completion of traffic counts, 25 percent of the bid price will be paid. Following the completion of the Synchro analysis, 25 percent of the bid price will be paid. Following the setup and fine tuning of the timings, the speed-delay study, and the TRP programming, 25 percent of the bid price will be paid. The remaining 25 percent will be paid when the system is working to the satisfaction of the engineer and the report and CD have been submitted.

LAKE COUNTY D.O.T. TRAFFIC CONTROL AND PROTECTION SPECIAL PROVISION

Traffic Control Plan (L.C.-T- Section 700), Effective 06/01/2012

Traffic Control shall be according to with the applicable sections of the "Standard Specifications", the "Supplemental Specifications", the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways, the "Quality Standard for Work Zone Traffic Control Devices", any special details and Highway Standards as shown on the plans and the special provisions contained herein.

Special attention is called to Articles 105.03(b), 105.05, and 107.09, and to Sections 701, 704, and 782 of the "Standard Specifications", and to the following Highway Standards, Details, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

The Contractor shall contact the Engineer at least 72 hours in advance of beginning work.

STANDARDS

901001, 701006, 701301, 701311, 701501, 701701, 701801, 701901

DETAILS

LC7003 – URBAN LANE CLOSURE MULTILANE INTERSECTION

LC7004 – TRAFFIC CONTROL AND PROTECTION FOR SIDEROADS, INTERSECTIONS
AND DRIVEWAYS

LC7005 – TYPICAL LANE CLOSURE 3 LANE ROAD SECTION

LC7800 – TYPICAL PAVEMENT MARKINGS FOR COUNTY HIGHWAYS

RECURRING SPECIAL PROVISIONS

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

LRS3 Special Provision for Work Zone Traffic Control Surveillance

DETOURS

Detours and road closures on county maintained roads within Lake County, Illinois shall be according to with the applicable Articles and Sections of the "Standard Specifications", the "Supplemental Specifications", the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", the Lake County Division of Transportation's Detour Procedures and Guidelines, any special details and Highway Standards as shown on the Detour Plan and the Special Provisions contained herein. The LCDOT's Detour Procedures and Guidelines are available from the LCDOT, Traffic Engineering Section upon request.

Traffic Control and Protection (L.C.-T- Section 700), Effective 06/01/2012

The Traffic Control and Protection shall meet the requirements of Division 700. Work Zone Traffic Control and Protection, Signing and Pavement Marking of the "Standard Specifications" except as follows:

Article 701.01 Description shall be replaced with the following:

701.01 Description. This item of work shall consist of furnishing, installing, maintaining, replacing, relocating and removing all traffic control devices used for the purpose of regulating, warning or directing traffic during the construction or maintenance of this improvement.

Article 701.02 Materials shall be modified by adding the following paragraph:

Traffic control devices include signs and their supports, signals, pavement markings, barricades and their approved weights, channeling devices, warning lights, arrow boards, flaggers, or any other device used for the purpose of regulating, detouring, warning or guiding traffic through or around the construction zone.

Article 701.04 General shall be modified by adding the following as the first paragraph:

Traffic Control and Protection shall be provided as called for in the plans, these special provisions, applicable Highway Standards, applicable sections of the "Standard Specifications", or as directed by the Engineer.

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

Article 701.04 General shall be modified by adding the following to the fourth paragraph:

The Contractor shall dispatch men, materials, and equipment to correct any such deficiencies. The Contractor shall respond to any call from LCDOT concerning any request for improving or correcting traffic control devices and begin making the requested repairs within two (2) hours from the time of notification.

Article 701.10 Surveillance shall be replaced with the following:

The Contractor is required to conduct routine inspections of the work site at a frequency that will allow for the timely replacement of any traffic control device that has become displaced, worn or damaged to the extent that it no longer conforms to the shape, dimensions, color and operational requirements of the MUTCD, the Traffic Control Standards, the IDOT Quality Standard For Work Zone Traffic Control Devices, or will no longer present a neat appearance to motorists. A sufficient quantity of replacement devices, based on vulnerability to damage, shall be readily available to meet this requirement.

The Contractor shall ensure that all the traffic control devices he/she installs are operational, functional and effective 24 hours a day, 7 days a week, including holidays.

Article 701.13 Flaggers (a) shall be modified by revising the seventh paragraph, subparagraph (a) by adding the following:

The Engineer will determine when a side road or entrance shall be closed to traffic. The flagger shall be positioned as shown on the plans or as directed by the Engineer.

Article 701.14 Signs (a) Road Construction Ahead Signs shall be modified by changing the following to the first paragraph:

"ROAD WORK AHEAD" signs shall be required in lieu of "ROAD CONSTRUCTION AHEAD" SIGNS

Article 701.14 Signs (b) Work Zone Speed Limit Signs shall be revised to read:

- (b) Work Zone Speed Limit Signs. The Lake County Division of Transportation will specify whether a project meets the criteria for a Work Zone Speed Limit. When specified, the work zone speed limit signs shall be installed as shown on the LCDOT Work Zone Speed Limit Signing Diagram, LC7203, at a maximum of 20

feet lateral distance of the locations shown on the plans. Failure to install and maintain the required amount of signs at the proper sign spacing shall result in an immediate traffic control deficiency.

All permanent "SPEED LIMIT" signs located within the work zone shall be removed or covered. If the speed limit sign is to be covered, it shall be done in a manner that no part of the legend shall be visible in any lighting condition. This work shall be completed by the contractor after the method of covering the speed limit signs has been approved by the Engineer.

The work zone speed limit signs and the end work zone speed limit signs in advance of and at the end of the lane closure(s) shall be used for the duration of the closure(s).

The work zone speed limit signs will be removed when roadway conditions return to normal or when the construction project is suspended for over 30 days.

Article 701.14 Signs shall be modified by adding the following section (c),

- (c) Temporary Construction Information Signs. When indicated in the traffic control plan or as directed by the Engineer the Contractor shall furnish, install, maintain, relocate, and remove for various stages of construction Temporary Construction Information Signs.

Temporary Construction Information Signs may include:

Driveway	White Legend on Green Background
Caution-New Lanes Open	Black Legend on Orange Background

The signs, as shown on Lake County Detail LC7201 shall be installed in accordance with the traffic control plan and as directed by the Engineer.

~~**Article 701.15 Traffic Control Devices** (b) Type I, II and III Barricades shall be deleted and replaced with the following:~~

Type II barricades shall be used at all locations that call for Type I, or Type II barricades.

Type II barricades are used to channelize traffic; to delineate unattended obstacles, patches, excavations, drop-offs, and other hazards; and as check barricades

Any drop off greater than 3 inches, but less than 6 inches, located within 8 feet of the pavement edge shall be protected by Type II barricades equipped with mono-directional steady burn lights. The barricades shall be placed at a spacing of 100 feet center to center. For any drop off within 8 feet of the pavement edge that exceeds 6 inches, the Type II barricades equipped with mono-directional steady burn lights shall be placed at a spacing of 50 feet center to center. Barricades that must be placed in excavated areas shall have leg extensions installed so that the top of the barricade is in compliance with the height requirements of IDOT Standard 701901.

Check barricades shall be placed in work areas perpendicular to traffic every 1,000 feet, at one per lane and one per shoulder, to prevent motorists from using work areas as a traveled way. Two additional check barricades shall be placed in advance of each patch excavation or any other hazard in the work area. The first will be placed at the edge of the open traffic lane and the second centered on the closed lane. Check barricades shall be Type II and equipped with flashing amber light.

Type III barricades are used to close traffic lanes and to close roads.

Article 701.15 Traffic Control Devices (e) Direction Indicator Barricades shall be modified by adding the following paragraphs.

The direction indicator barricades shall meet the requirements for Type II barricades as stated in this special provision. The top panel, which faces traffic, shall be as shown in IDOT Highway Standard 701901. The top panel, facing away from traffic shall have a 12 inch x 24 inch orange and white diagonal panel. The bottom panels shall be 8 inches x 24 inches with orange and white diagonal sheeting, as shown in LCDOT's Special Detail LC7200.

Article 701.15 Traffic Control Devices (j) Portable Changeable Message Signs shall be modified by adding the following paragraphs:

The PCMS shall be compatible and fully functional with the Lake County Division of Transportation's Transportation Management Center PASSAGE PCMS Control Software. A list of approved PCMS's manufacturers and traffic control vendors is available upon request from the Lake County Division of Transportation. The PCMS shall be tested and approved by the Lake County Division of Transportation and can be sufficiently controlled by the Lake County Division of Transportation NTCIP compliant software. If the PCMS has not been tested or approved by either the Illinois State Toll Highway Authority or The Lake

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

County Division of Transportation then the PCMS will need to be tested and certified by the Delcan Corporation at the contractor's expense.

Lake County Division of Transportation (PASSAGE)
Software Developer:
Delcan
650 East Algonquin Road, Suite 101
Schaumburg, IL 60173

In case of a Traffic Incident Management (TIM) event or other County or State declared Emergency Management event, the use of the PCMS may be preempted from the contractor's use by the Lake County Transportation Management Center for the duration of the incident. If the PCMS must be moved from the limits of the work site to an offsite location to better facilitate the use of the PCMS during the incident, the contractor will be compensated for the labor and equipment to move the PCMS to the designated location and back, in accordance with Article 109.04 (b) of the Standard Specifications for Road and Bridge Construction. In order to facilitate the movement of the PCMS in a timely manner, the Lake County Division of Transportation may use County Forces to move the PCMS to the designated location and/or back, at no additional cost to the contractor.

When the sign(s) are displaying messages, they shall be considered a traffic control device. At all times when no message is displayed, they shall be considered equipment.

Basis of Payment. Changeable message signs will be paid for at the contract unit price per calendar month for each sign as CHANGEABLE MESSAGE SIGN, as stated in Article 701.20 of this special provision.

Article 701.17 Specific Construction Operations (c) Surface Courses and Pavement (1)
Prime Coat shall be replaced by the following:

- (1) Prime Coat. "FRESH OIL" signs (W21-2) shall be used when the prime coat is applied to pavement that is open to traffic. The signs are to remain in place until tracking of the prime ceases. These signs shall be erected a minimum of 500 feet preceding the start of the prime and on all side roads within the posted area. The signs on the side roads shall be posted a minimum of 200 feet from the mainline pavement. These signs are excluded from the time requirements of Article 701.04 of the "Standard Specifications" as modified by this special provision (above).

Non-compliance with the provisions of this section, by the Contractor, shall result in an immediate traffic control deficiency deduction. All signs shall have an amber flashing light attached.

Article 701.17 Specific Procedures (c) Surface Courses and Pavement (2) Cold Milling shall be replaced by the following:

- (2) Cold Milling. "ROUGH GROOVED SURFACE" signs (W8-I107) shall be used when the road has been cold milled and is open to traffic. The signs shall remain in place until the milled surface condition no longer exists. These signs shall be erected a minimum of 500 feet preceding the start of the milled pavement and on all side roads within the posted area. The signs on the side roads shall be posted a minimum of 200 feet from the mainline pavement. Non-compliance with the provisions of this section, by the Contractor, shall result in an immediate traffic control deficiency deduction. All signs shall have an amber flashing light attached.

Article 701.17 Specific Procedures (c) Surface Course and Pavement shall be modified by adding the following paragraph:

- (6) Area Reflective Crack Control Treatment Fabric. "SLIPPERY WHEN WET" signs (W8-5) shall be used when crack control fabric is applied to pavement that is open to traffic. These signs shall remain in place until the binder course is laid. The signs shall be erected a minimum of 500 feet preceding the start of the crack control treatment and on all side roads within the posted area. The signs on the side roads shall be posted a minimum of 200 feet from the mainline pavement. These signs are excluded from the time requirements of Article 701.04 of the "Standard Specifications" as modified by this special provision (above). Non-compliance with the provisions of this section, by the Contractor, shall result in an immediate traffic control deficiency deduction. All signs shall have an amber flashing light attached.

Article 701.18 Highway Standards Application (b) Standard 701316 and 701321 (2) g. Detector Loops, shall be replaced with the following:

- g. Detection. Microwave Vehicle Sensors shall be installed as directed by the Engineer. LCDOT shall approve the proposed microwave vehicle sensor before the Contractor may furnish or install it. The Contractor shall install, wire and adjust the alignment of the sensor in accordance to the manufacturer's recommendations and requirements. The Engineer

shall approve the installation. An alternate method of detection may be used if it has been demonstrated and approved by the department.

The microwave vehicle sensor shall meet the following requirements:

- Detection Range: Adjustable to 60 feet
- Detection Angle: Adjustable, horizontal and vertical
- Detection Pattern: 16 degree beam width minimum. [at 50 feet the pattern shall be approximately 15.5 feet wide]
- Mounting: Heavy-duty bracket, predrilled and slotted for pole mounting
- LED Indicator Light: for detection verification

Article 701.18 Highway Standards Application (j) Urban Traffic Control, Standards 701501, 701502, 701601, 701602, 701606, 701701, and 701801 (1) General, shall be modified by adding the following paragraphs:

Whenever a lane is closed to traffic using IDOT standard 701601, 701606, or 701701, the pavement width transition sign (W4-2R or W4-2L) shall be used in lieu of the "WORKERS" sign (W21-1 or W21-1a)

Whenever any vehicle, equipment, workers or their activities infringe on the shoulder or within 15 feet of the traveled way, and the traveled way remains unobstructed, then the applicable Traffic Control Standard shall be 701006, 701011, 701101, or 701701. The "SHOULDER WORK AHEAD" sign (W21-5(0)-48) shall be used in lieu of the "WORKERS" sign (W21-1 or W-21-1a).

Article 701.18 Highway Standards Application shall be modified by adding the following section (l):

(l) IDOT standard 701331. When IDOT standard 701331 is specified on two-lane, two-way roadways, a "LANE SHIFT AHEAD" sign shall be added 500 feet in advance of W1-3 or 4 sign. The Road Work sign (W20-1) shall be extended to a total of 1500' from the start of the lane shift.

Article 701.19 Method of Measurement shall be replaced completely with the following:

701.19 Method of Measurement.

These items of work will be measured on a lump sum basis for furnishing

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

installing, maintaining, replacing, relocating and removing the traffic control devices required in the plans and these special provisions.

Article 701.20 Basis of Payment shall be replaced completely with the following:

701.20 Basis of Payment

This work will be paid for at the contract unit price per lump sum for TRAFFIC CONTROL AND PROTECTION (SPECIAL). The payment will be in full for all labor, materials, transportation, and incidentals necessary to furnish, install, maintain, replace, relocate and remove all traffic control devices indicated in the plans and specifications, except for the following items, which will be paid for separately.

- 1) Temporary Bridge Traffic Signals
- 2) Temporary Rumble Strips [where each is defined as 25 feet].
- 3) Temporary Raised Pavement Markers.
- 4) Construction Speed Limit Trailer
- 5) Sand module impact attenuators
- 6) Portable Changeable Message Signs
- 7) Temporary Concrete Barrier
- 8) Temporary Pavement Marking-Letters and Symbols
- 9) Temporary Pavement Marking-Line at width specified

The salvage value of the materials removed shall be reflected in the bid price for this item.

Any delays or inconveniences incurred by the Contractor while complying with these requirements shall be considered as part of TRAFFIC CONTROL AND PROTECTION (SPECIAL) and no additional compensation will be allowed.

~~Any traffic control devices required by the Engineer to implement the Traffic Control Plan as shown in the plans and specifications of the contract shall be considered incidental to the pay item TRAFFIC CONTROL AND PROTECTION (SPECIAL).~~

If the Engineer requires additional work involving a substantial change of location and/or work which differs in design and/or work requiring a change in the type of construction, as stated in Article 104.02(d) of the "Standard Specifications" the standards and/or the designs, other than

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

those required in the plans, will be made available to the Contractor at least one week in advance of the change in traffic control. Payment for any additional traffic control required for the reasons listed above will be in accordance with Article 109.04 of the "Standard Specifications".

Revisions in the phasing of construction or maintenance operations, requested by the Contractor, may require traffic control to be installed in accordance with standards and/or designs other than those included in the plans. The Contractor shall submit revisions or modifications to the traffic control plan shown in the contract to the Engineer for approval. No additional payment will be made for a Contractor requested modification.

In the event the sum total of all work items for which traffic control and protection is required is increased or decreased by more than ten percent (10%), the contract bid price for TRAFFIC CONTROL AND PROTECTION will be adjusted as follows:

$$\text{Adjusted Contract Price} = 0.25P + 0.75P [1 \pm (X-0.1)]$$

P = the contract price for TRAFFIC CONTROL AND PROTECTION

$$X = \frac{\text{Difference between original and final value of work for which traffic control and protection is required.}}{\text{Original value of work for which traffic control and protection is required.}}$$

The value of the work items used in calculating the increase and decrease will include only items that have been added to or deducted from the contract under Article 104.02 of the "Standard Specifications" and only items that require the use of TRAFFIC CONTROL AND PROTECTION (SPECIAL).

~~In the event LGDOT cancels or alters any portion of the contract that result in the elimination or incompleteness of any portion of the work, payment for partially completed work will be made in accordance with Article 104.02 of the "Standard Specifications".~~

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

DETECTABLE WARNINGS (LCDOT STANDARD)

Effective: February 13, 2007
Revised: November 22, 2011

Description: This work shall consist of furnishing and installing detectable warnings in accessibility ramps. **This special provision only applies to ramps at Hart Road and Cedar Lake Road.**

Materials: The detectable warnings shall be cast iron panels of the sizes shown on the plans and shall meet the following material specification:

The detectable warning plate shall be constructed of gray iron meeting the requirements of Article 1006.14 of the "Standard Specifications" and ASTM A48, CLASS 35B; or cast ductile iron meeting the requirements of Article 1006.15 of the "Standard Specifications".

The coating system shall consist of a rust inhibiting epoxy primer and a finish coat.

The epoxy primer shall have the following properties:

Property	Test Method	Performance
Humidity	ASTM D1735	1000 Hours Minimum
Water Immersion	ASTM D870	250 Hours Minimum
Corrosion Resistance (Salt Spray)	ASTM B117	1000 Hours Minimum

Cold Rolled Steel Lab Panels

The finish coat shall be a powder coat and shall have the following properties:

Property	Test Method	Performance
Color	---	Federal Yellow
Corrosion Resistance (Salt Spray)	ASTM B117	1000 Hours Minimum

Cold Rolled Steel Lab Panels

The gray iron plate (concrete ramps only) shall be supplied from one of the following manufacturers, or an approved equal:

Neenah Foundry
545 Kimberly Drive
Carol Stream, IL 60188
Phone # 630-653-5440
<http://www.neenahfoundry.com/>

East Jordan Iron Works
310 Garnet Drive
New Lenox, IL 60451-3502
Phone # 1-800-626-4653
<http://www.ejiw.com>

Village of Round Lake
FAU 201 Hart Road
Section No.: 00-00025-00-FP
County: Lake
Contract No.: 63868

The ductile iron plate (concrete or HMA ramps) shall be supplied from the following manufacturer, or an approved equal:

Pioneer Detectable, LLC
N8060 Maple Street
Ixonia, WI 53036
Phone # 262-370-5355
<http://www.pioneerdetectable.com/ind>

General: The installation of detectable warnings shall meet the requirements of Article 424.09 of the "Standard Specifications". Grey iron plates shall be installed in concrete accessibility ramps only. Ductile iron plates may be installed in either concrete or hot-mix asphalt (HMA) accessibility ramps.

Method of Measurement: This work will be measured for payment in place installed, in square feet. *The concrete area under the detectable warnings will be measured for payment as PORTLAND CEMENT CONCRETE SIDEWALK of the thickness specified, with no deductions made for the detectable warnings panels located within the ramp.*

Basis of Payment: This work will be paid for at the contract unit price per square foot of DETECTABLE WARNINGS. *The unit price shall include all equipment, materials and labor required to install the panels.*

DSH 10/25/2013
I:\Crystal Lake\ROULK\071749\40-Design\Work\Special Provisions\071749_SPECIAL PROVISIONS.docx

IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION (TPG)

Effective: August 1, 2012

In addition to the Contractor's equal employment opportunity affirmative action efforts undertaken as elsewhere required by this Contract, the Contractor is encouraged to participate in the incentive program to provide additional on-the-job training to certified graduates of IDOT's community college pre-apprenticeship programs outlined by this Special Provision.

It is the policy of IDOT to fund IDOT pre-apprenticeship training programs based at Illinois Community Colleges throughout Illinois, by Intergovernmental Agreement with the Illinois Community College Board, to provide training and skill-improvement opportunities to assure the increased participation of minority groups, disadvantaged persons and women in all phases of the highway construction industry. The intent of this IDOT Training Program Graduate (TPG) Special Provision is to place certified graduates of these IDOT funded pre-apprentice training programs on IDOT project sites when feasible, and provide the graduates with meaningful on-the-job training intended to lead to journey-level employment. IDOT and its sub-recipients, in carrying out the responsibilities of a state contract, shall determine which state funded construction contracts shall include "Training Program Graduate (TPG) Special Provisions." To benefit from the incentives to encourage the participation in the additional on-the-job training under this Training Program Graduate (TPG) Special Provision, the Contractor shall make every reasonable effort to employ certified graduates of the IDOT funded Pre-apprenticeship Training Program to the extent such persons are available within a reasonable recruitment area.

Participation pursuant to IDOT's requirements by the Contractor or subcontractor in this Training Program Graduate (TPG) Special Provision entitles the Contractor or subcontractor to be reimbursed at \$10.00 per hour for training given a certified graduate trainee on this contract. As approved by the Department, reimbursement will be made for training persons as specified herein. This reimbursement will be made even though the Contractor or subcontractor may receive additional training program funds from other sources for other trainees, provided such other source does not specifically prohibit the Contractor or subcontractor from receiving other reimbursement. For purposes of this Special Provision the Contractor is not relieved of requirements under the Illinois Prevailing Wage Act and is not eligible for other training fund reimbursements in addition to the Training Program Graduate (TPG) Special Provision reimbursement.

No payment shall be made to the Contractor if the Contractor or subcontractor fails to provide the required training. It is normally expected that a TPG will begin training on the project as soon as feasible after start of work utilizing the skill involved and remain on the project through completion of the contract, so long as training opportunities exist in his work classification or until he has completed his training program. Should the TPG's employment end in advance of the completion of the contract, the Contractor shall promptly notify the designated IDOT staff member under this Special Provision that the TPG's involvement in the contract has ended and supply a written report of the reason for the end of the involvement, the hours completed by the

TPG under the Contract and the number of hours for which the incentive payment provided under this Special Provision will be or has been claimed for the TPG.

The Contractor will provide for the maintenance of records and furnish periodic reports documenting its performance under this Special Provision.

METHOD OF MEASUREMENT: The unit of measurement is in hours.

BASIS OF PAYMENT: This work will be paid for at the contract unit price of \$10.00 per hour for TRAINEES TRAINING PROGRAM GRADUATE. The estimated total number of hours, unit price and total price have been included in the schedule of prices.

The Contractor shall provide training opportunities aimed at developing full journeyworker in the type of trade or job classification involved. The initial number of TPGs for which the incentive is available under this contract is 2. During the course of performance of the Contract the Contractor may seek approval from the Department for additional incentive eligible TPGs. In the event the Contractor subcontracts a portion of the contract work, it shall determine how many, if any, of the TPGs are to be trained by the subcontractor, provided however, that the Contractor shall retain the primary responsibility for meeting the training requirements imposed by this Special Provision. The Contractor shall also insure that this Training Program Graduate Special Provision is made applicable to such subcontract if the TPGs are to be trained by a subcontractor and that the incentive payment is passed on to each subcontractor.

For the Contractor to meet the obligations for participation in this TPG incentive program under this Special Provision, the Department has contracted by Intergovernmental Agreement with the Illinois Community College Board to provide screening, tutoring and pre-training to individuals interested in working in the applicable construction classification and has certified those students who have successfully completed the program and are eligible to be TPGs. A designated IDOT staff member, the Director of the Office of Business and Workforce Diversity (OBWD), will be responsible for providing assistance and referrals to the Contractor for the applicable TPGs. For this contract, the Director of OBWD is designated as the responsible IDOT staff member to provide the assistance and referral services related to the placement for this Special Provision. For purposes of this Contract, contacting the Director of OBWD and interviewing each candidate he/she recommends constitutes reasonable recruitment.

Prior to commencing construction, the Contractor shall submit to the Department for approval the TPGs to be trained in each selected classification. Furthermore, the Contractor shall specify the starting time for training in each of the classifications. No employee shall be employed as a TPG in any classification in which he/she has successfully completed a training course leading to journeyman status or in which he/she has been employed as a journeyman. Notwithstanding the on-the-job training purpose of this TPG Special Provision, some offsite training is permissible as long as the offsite training is an integral part of the work of the contract and does not comprise a significant part of the overall training.

Training and upgrading of TPGs of IDOT pre-apprentice training programs is intended to move said TPGs toward journeyman status and is the primary objective of this Training Program

Graduate Special Provision. Accordingly, the Contractor shall make every effort to enroll TPGs by recruitment through the IDOT Illinois Community College Program to the extent such persons are available within a reasonable area of recruitment. The Contractor will be responsible for demonstrating the steps that it has taken in pursuance thereof, prior to a determination as to whether the Contractor is in compliance and entitled to the Training Program Graduate TPG Special Provision \$10.00 an hour incentive.

The Contractor or subcontractor shall provide each TPG with a certification showing the type and length of training satisfactorily completed.



DEPARTMENT OF THE ARMY
CHICAGO DISTRICT, CORPS OF ENGINEERS
231 SOUTH LA SALLE STREET
CHICAGO, ILLINOIS 60604-1437

REPLY TO
ATTENTION OF:

October 28, 2013

Technical Services Division
Regulatory Branch
LRC-2013-00418

SUBJECT: Request Authorization to Impact 0.048 Acres of Wetland for Improvements to Hart Road from East of Illinois Route 134 (Round Lake Road/Railroad Avenue) to Cedar Lake Road in Village of Round Lake, Lake County, Illinois

Ron Kroop
Village of Round Lake
751 West Townline Road
Round Lake, Illinois 60073

Dear Mr. Kroop:

The U.S. Army Corps of Engineers, Chicago District, has completed its review of your notification for authorization under the Regional Permit Program (RPP), submitted on your behalf by Baxter & Woodman. This office has verified that your proposed activity complies with the terms and conditions of Regional Permit 3 & 8 and the overall RPP under Category I of the Regional Permit Program dated April 1, 2012. The activity may be performed without further authorization from this office provided the activity is conducted in compliance with the terms and conditions of the RPP.

This verification expires three (3) years from the date of this letter and covers only your activity as described in your notification and as shown on the plans entitled "State of Illinois, Department of Transportation, Division of Highways, Plans for Proposed Federal Aid Highway, FAU 201 (Hart Road), FAU 186 (IL Route 134) to FAU 192 (Cedar Lake Road) Reconstruction Section 00-00025-00-FP, Project: M-9003(482), Job No. C-91-070-10, Village of Round Lake, Lake County, Sheets 1-98". Caution must be taken to prevent construction materials and activities from impacting waters of the United States beyond the scope of this authorization. If you anticipate changing the design or location of the activity, you should contact this office to determine the need for further authorization.

This authorization is contingent upon implementing and maintaining soil erosion and sediment controls in a serviceable condition throughout the duration of the project. You shall comply with the Lake County Stormwater Management Commission (LCSMC)'s written and verbal recommendations regarding the soil erosion and sediment control (SESC) plan and the installation and maintenance requirements of the SESC practices on-site. You shall notify this office and the SMC of any changes or modifications to the approved plan set. Please be aware

that field conditions during project construction may require the implementation of additional SESC measures for further protection of aquatic resources. If you fail to implement corrective measures, this office may require more frequent site inspections to ensure the installed SESC measures are acceptable.


You shall complete the following requirements:

1. You shall schedule a preconstruction meeting with LCSMC to discuss the SESC plan and the installation and maintenance requirements of the SESC practices on the site.
2. You shall notify the LCSMC of any changes or modifications to the approved plan set. Field conditions during project construction may require the implementation of additional SESC measures. If you fail to implement corrective measures, this office may require more frequent site inspections to ensure the installed SESC measures are acceptable.

This verification does not obviate the need to obtain all other required Federal, state, or local approvals before starting work. Please note that Section 401 Water Quality Certification has been issued by IEPA for this RP. Enclosed are the IEPA Section 401 Water Quality Certification conditions. If you have any questions regarding Section 401 certification, please contact Mr. Dan Heacock at IEPA Division of Water Pollution Control, Permit Section #15, by telephone at (217) 782-3362.

For a complete copy of the RPP program or any additional information on the RPP program, please access our website: www.lrc.usace.army.mil/co-r. Once you have completed the authorized activity, please sign and return the enclosed compliance certification. If you have any questions, please contact Melyssa R. Navis of my staff by telephone at 312-846-5533, or email at melyssa.r.navis@usace.army.mil.

Sincerely,




Kathleen G. Chernich
Chief, East Section
Regulatory Branch

Enclosures

Copy Furnished w/out Enclosures:

Lake County Stormwater Management Commission (Kurt Woolford)
Baxter & Woodman (Dave Hemmerich)



PERMIT COMPLIANCE

CERTIFICATION

Permit Number: LRC-2013-00418
Permittee: Village of Round Lake
Date: October 28, 2013

I hereby certify that the work authorized by the above-referenced permit has been completed in accordance with the terms and conditions of said permit and if applicable, compensatory wetland mitigation was completed in accordance with the approved mitigation plan.¹

PERMITTEE

DATE

Upon completion of the activity authorized by this permit and any mitigation required by the permit, this certification must be signed and returned to the following address:

U.S. Army Corps of Engineers
Chicago District, Regulatory Branch
231 South LaSalle Street, Suite 1500
Chicago, Illinois 60604-1437

Please note that your permitted activity is subject to compliance inspections by Corps of Engineers representatives. If you fail to comply with this permit, you may be subject to permit suspension, modification, or revocation.

¹ If compensatory mitigation was required as part of your authorization, you are certifying that the mitigation area has been graded and planted in accordance with the approved plan. You are acknowledging that the maintenance and monitoring period will begin after a site inspection by a Corps of Engineers representative or after thirty days of the Corps' receipt of this certification. You agree to comply with all permit terms and conditions, including additional reporting requirements, for the duration of the maintenance and monitoring period.



US Army Corps of Engineers®
Chicago District

**GENERAL CONDITIONS
APPLICABLE TO THE 2012
REGIONAL PERMIT PROGRAM**

The permittee shall comply with the terms and conditions of the Regional Permits and the following general conditions for all activities authorized under the RPP:

1. State 401 Water Quality Certification - Water quality certification under Section 401 of the Clean Water Act may be required from the Illinois Environmental Protection Agency (IEPA). The District may consider water quality, among other factors, in determining whether to exercise discretionary authority and require an Individual Permit. Please note that Section 401 Water Quality Certification is a requirement for projects carried out in accordance with Section 404 of the Clean Water Act. Projects carried out in accordance with Section 10 of the Rivers and Harbors Act of 1899 do not require Section 401 Water Quality Certification

On March 2, 2012, the IEPA granted Section 401 certification, with conditions, for all Regional Permits, except for activities in certain waterways noted under RPs 4 and 8. The following conditions of the certification are hereby made conditions of the RPP:

1. The applicant shall not cause:
 - a) a violation of applicable water quality standards of the Illinois Pollution Control Board Title 35, Subtitle C: Water Pollution Rules and Regulations;
 - b) water pollution defined and prohibited by the Illinois Environmental Protection Act;
 - c) interference with water use practices near public recreation areas or water supply intakes;
 - d) a violation of applicable provisions of the Illinois Environmental Protection Act.
2. The applicant shall provide adequate planning and supervision during the project construction period for implementing construction methods, processes and cleanup procedures necessary to prevent water pollution and control erosion.
3. Except as allowed under condition 9, any spoil material excavated, dredged or otherwise produced must not be returned to the waterway but must be deposited in a self-contained area in compliance with all State statutes, regulations and permit requirements with no discharge to waters of the State unless a permit has been issued by the Illinois EPA. Any backfilling must be done with clean material placed in a manner to prevent violation of applicable water quality standards.
4. All areas affected by construction shall be mulched and seeded as soon after construction as possible. The applicant shall undertake necessary measures and procedures to reduce erosion during construction. Interim measures to prevent soil erosion during construction shall be taken and may include the installation of sedimentation basins and temporary mulching. All construction within the waterway shall be conducted during zero or low flow conditions. The applicant shall be responsible for obtaining a NPDES Stormwater Permit prior to initiating construction if the construction activity associated with the project will result in the disturbance of (1) one or more acres, total land area. A NPDES Stormwater Permit may be obtained by submitting a properly completed Notice of Intent (NOI) form by certified mail to the Illinois EPA's Division of Water Pollution Control, Permit Section.
5. The applicant shall implement erosion control measures consistent with the Illinois Urban Manual (IEPA/USDA, NRCS; 2011, <http://aiswcd.org/IUM/index.html>).
6. The applicant is advised that the following permits(s) must be obtained from the Illinois EPA: The applicant must obtain permits to construct sanitary sewers, water mains, and related facilities prior to construction.
7. Backfill used in the stream-crossing trench shall be predominantly sand or larger size material, with less than 20% passing a #230 U.S. sieve.
8. Any channel relocation shall be constructed under dry conditions and stabilized to prevent erosion prior to the diversion of flow.
9. Backfill used within trenches passing through surface waters of the State, except wetland areas, shall be clean course aggregate, gravel or other material which will not cause siltation, pipe damage during placement, or chemical corrosion in place. Excavated material may be used only if:
 - a) particle size analysis is conducted and demonstrates the material to be at least 80% sand or larger size material, using #230 U.S. sieve; or
 - b) excavation and backfilling are done under dry conditions.
10. Backfill used within trenches passing through wetland areas shall consist of clean material which will not cause siltation, pipe damage during placement, or chemical corrosion in place. Excavated material shall be used to the extent practicable, with the upper six (6) to twelve (12) inches backfilled with the topsoil obtained during trench excavation.
11. Any applicant proposing activities in a mined area or previously mined area shall provide to the IEPA a written determination regarding the sediment and materials used which are considered "acid-producing material" as defined in 35 Il. Adm. Code,

Subtitle D. If considered "acid-producing material," the applicant shall obtain a permit to construct pursuant to 35 Ill. Adm. Code 404.101.

12. Asphalt, bituminous material and concrete with protruding material such as reinforcing bar or mesh shall not be 1) used for backfill, 2) placed on shorelines/stream banks, or 3) placed in waters of the State.
13. Applicants that use site dewatering techniques in order to perform work in waterways for construction activities approved under Regional Permits 1 (Residential, Commercial and Institutional Developments), 2 (Recreation Projects), 3 (Transportation Projects), 7 (Temporary Construction Activities), 9 (Maintenance) or 12 (Bridge Scour Protection) shall maintain flow in the stream during such construction activity by utilizing dam and pumping, fluming, culverts or other such techniques.
14. In addition to any action required of the Regional Permit 13 (Cleanup of Toxic and Hazardous Materials Projects) applicant with respect to the "Notification" General Condition 22, the applicant shall notify the Illinois EPA Bureau of Water, of the specific activity. This notification shall include information concerning the orders and approvals that have been or will be obtained from the Illinois EPA Bureau of Land (BOL) for all cleanup activities under BOL jurisdiction, or for which authorization or approval is sought from BOL for no further remediation. This Regional Permit is not valid for activities that do not require or will not receive authorization or approval from the BOL.

2. Threatened and Endangered Species - If the District determines that the activity may affect Federally listed species or critical habitat, the District will initiate section 7 consultation with the U.S. Fish and Wildlife Service (USFWS) in accordance with the Endangered Species Act of 1973, as amended (Act). Applicants shall provide additional information that would enable the District to conclude that the proposed action will have no effect on federally listed species.

The application packet shall indicate whether resources (species, their suitable habitats, or critical habitat) listed or designated under the Act, may be present within areas affected (directly or indirectly) by the proposed project. Applicants shall provide a section 7 species list for the action area using the on-line process at the USFWS website. You can access "U.S. Fish and Wildlife Service Endangered Species Program of the Upper Midwest" website at www.fws.gov/midwest/Endangered. Click on the section 7 Technical Assistance green shaded box in the lower right portion of the screen and follow the instructions to completion. Review all documentation pertaining to the species list, provide the rationale for your effects determination for each species, and send the information to this office for review.

If no species, their suitable habitats, or critical habitat are listed, then a "no effect" determination can be made, and section 7 consultation is not warranted. If species or critical habitat appear on the list or suitable habitat is present within the action area, then a biological assessment or biological evaluation will need to be completed to determine if the proposed action will have "no effect" or "may effect" the species or suitable habitat. The District will request initiation of section 7 consultation with the USFWS upon agreement with the applicant on the effect determinations in the biological assessment or biological evaluation. If the issues are not resolved, the analysis of the situation is complicated, or impacts to listed species or critical habitat are found to be greater than minimal, the District will consider reviewing the project under the Individual Permit process.

Projects in Will, DuPage, or Cook Counties that are located in the recharge zones for Hine's emerald dragonfly critical habitat units may be reviewed under the RPP, with careful consideration due to the potential impacts to the species. All projects reviewed that are located within 3.25 miles of a critical habitat unit will be reviewed under Category II of the RPP. Please visit the following website for the locations of the Hine's emerald dragonfly critical habitat units in Illinois.
<http://www.fws.gov/midwest/endangered/insects/hed/FRHinesFinalRevisedCH.html>

3. Historic Properties - In cases where the District determines that the activity may affect properties listed, or eligible for listing, in the National Register of Historic Places, the activity may require an Individual Permit. A determination of whether the activity may be authorized under the RPP instead of an Individual Permit will not be made until the requirements of Section 106 of the National Historic Preservation Act (NHPA) have been satisfied.

Federal permittees should follow their own procedures for complying with the requirements of Section 106 of the National Historic Preservation Act. Federal permittees must provide the District with the appropriate documentation to demonstrate compliance with those requirements.

Non-Federal permittees must include notification to the District if the authorized activity may have the potential to cause effects to any historic properties listed, determined to be eligible for listing on, or potentially eligible for listing on the National Register of Historic Places, including previously unidentified properties. For such activities, the permit application must state which historic properties may be affected by the proposed work or include a vicinity map indicating the location of the historic properties or the potential for the presence of historic properties. Assistance regarding information on the location of or potential for the presence of historic resources can be sought from the State Historic Preservation Officer or Tribal Historic Preservation Officer, as appropriate, and the National Register of Historic Places (see 33 CFR 330.4(g)). When reviewing permit submittals, the District will comply with the current procedures for addressing the requirements of Section 106 of the National Historic Preservation Act. Based on the information submitted and these efforts, the District shall determine whether the proposed activity has the potential to cause an effect on the historic properties. Where the non-Federal applicant has identified historic properties which the activity may have the potential to cause effects and so notified the District, the non-Federal applicant shall not begin the activity until notified by the District either that the activity has no potential to cause effects or that consultation under Section 106 of the NHPA has been completed.

The District will take into account the effects on such properties in accordance with 33 CFR Part 325, Appendix C, and 36 CFR 800. If all issues pertaining to historic properties have been resolved through the consultation process to the satisfaction of the District, Illinois Historic Preservation Agency (IHPA) and Advisory Council on Historic Preservation, the District may, at its discretion, authorize the activity under the RPP instead of an Individual Permit.

Applicants are encouraged to obtain information on historic properties from the IHPA and the National Register of Historic Places at the earliest stages of project planning. For information, contact:

Illinois Historic Preservation Agency
1 Old State Capitol Plaza
Springfield, IL 62701-1507
(217) 782-4836
www.illinoishistory.gov

If you discover any previously unknown historic, cultural or archeological remains and artifacts while accomplishing the activity, you must immediately notify this office of what you have found, and to the maximum extent practicable, stop activities that would adversely affect those remains and artifacts until the required coordination has been completed. We will initiate the Federal, Tribal and State coordination required to determine if the items or remains warrant a recovery effort or if the site is eligible for listing in the National Register of Historic Places.

4. Soil Erosion and Sediment Control - Measures shall be taken to control soil erosion and sedimentation at the project site to ensure that sediment is not transported to waters of the U.S. during construction. Soil erosion and sediment control measures shall be implemented before initiating any clearing, grading, excavating or filling activities. All temporary and permanent soil erosion and sediment control measures shall be maintained throughout the construction period and until the site is stabilized. All exposed soil and other fills, and any work below the ordinary high water mark shall be permanently stabilized at the earliest practicable date.

Applicants are required to prepare a soil erosion and sediment control (SESC) plan including temporary BMPs. The plan shall be designed in accordance with the Illinois Urban Manual, 2011 (<http://aiswcd.org/IUM/index.html>). Practice standards and specifications for measures outlined in the soil erosion and sediment control plans will follow the latest edition of the "Illinois Urban Manual: A Technical Manual Designed for Urban Ecosystem Protection and Enhancement." Additional Soil Erosion and Sediment Control (SESC) measures not identified in the Illinois Urban Manual may also be utilized upon District approval.

At the District's discretion, an applicant may be required to submit the SESC plan to the local Soil and Water Conservation District (SWCD), or the Lake County Stormwater Management Commission (SMC) for review. When the District requires submission of an SESC plan, the following applies: An activity may not commence until the SESC plan for the project site has been approved; The SWCD/SMC will review the plan and provide a written evaluation of its adequacy; A SESC plan is considered acceptable when the SWCD/SMC has found that it meets technical standards. Once a determination has been made, the authorized work may commence unless the SWCD/SMC has requested that they be notified prior to commencement of the approved plans. The SWCD/SMC may attend pre-construction meetings with the permittee and conduct inspections during construction to determine compliance with the plans. Applicants are encouraged to begin coordinating with the appropriate SWCD/SMC office at the earliest stages of project planning. For information, contact:

Kane-DuPage SWCD
2315 Dean Street, Suite 100
St. Charles, IL 60174
(630) 584-7961 ext.3
www.kanedupageswcd.org

McHenry-Lake County SWCD
1648 South Eastwood Dr.
Woodstock, IL 60098
(815) 338-0099 ext.3
www.mchenryswcd.org

North Cook SWCD
899 Jay Street
Elgin, IL 60120
(847) 468-0071
www.northcookswcd.org

Lake County SMC
500 W. Winchester Rd, Suite 201
Libertyville, IL 60048
(847) 377-7700
www.lakecountyil.gov/stormwater

5. Total Maximum Daily Load - For projects that include a discharge of pollutant(s) to waters for which there is an approved Total Maximum Daily Load (TMDL) allocation for any parameter, the applicant shall develop plans and BMPs that are consistent with the assumptions and requirements in the approved TMDL. The applicant must incorporate into their plans and BMPs any conditions applicable to their discharges necessary for consistency with the assumptions and requirements of the TMDL within any timeframes established in the TMDL. The applicant must carefully document the justifications for all BMPs and plans, and install, implement and maintain practices and BMPs that are consistent with all relevant TMDL allocations and with all relevant conditions in an implementation plan. Information regarding the TMDL program, including approved TMDL allocations, can be found at the following website: www.epa.state.il.us/water/tmdl/

6. Floodplain - Discharges of dredged or fill material into waters of the United States within the 100-year floodplain (as defined by the Federal Emergency Management Agency) resulting in permanent above-grade fills shall be avoided and minimized to the maximum extent practicable. When such an above-grade fill would occur, the applicant may need to obtain approval from the Illinois

Department of Natural Resources, Office of Water Resources, (IDNR-OWR) which regulates activities affecting the floodway and the local governing agency (e.g., Village or County) with jurisdiction over activities in the floodplain. Compensatory storage may be required for fill within the floodplain. Applicants are encouraged to obtain information from the IDNR-OWR and the local governing agency with jurisdiction at the earliest stages of project planning. For information on floodway construction, contact:

IDNR/OWR
2050 Stearns Road
Bartlett, IL 60103
(847) 608-3100
<http://dnr.state.il.us/owr/>

For information on floodplain construction, please contact the local government and/or the Federal Emergency Management Agency. Pursuant to 33 CFR 320.4(j), the District will consider the likelihood of the applicant obtaining approval for above-ground permanent fills in floodplains in determining whether to issue authorization under the RPP.

7. Navigation - No activity may cause more than a minimal adverse effect on navigation. Any safety lights and signals prescribed by the U.S. Coast Guard, through regulations or otherwise, must be installed and maintained at the permittee's expense on authorized facilities in navigable waters of the United States. The permittee understands and agrees that, if future operations by the United States require the removal, relocation, or other alteration, of the structure or work herein authorized, or if, in the opinion of the Secretary of the Army or his authorized representative, said structure or work shall cause unreasonable obstruction to the free navigation of the navigable waters, the permittee will be required, upon due notice from the Corps of Engineers, to remove, relocate, or alter the structural work or obstructions caused thereby, without expense to the United States. No claim shall be made against the United States on account of any such removal or alteration.
8. Proper Maintenance - Any authorized structure or fill shall be properly maintained, including that necessary to ensure public safety.
9. Aquatic Life Movements - No activity may substantially disrupt the movement of those species of aquatic life indigenous to the waterbody, including species that normally migrate through the area, unless the activity's primary purpose is to impound water.
10. Equipment - Soil disturbance and compaction shall be minimized through the use of matting for heavy equipment, low ground pressure equipment, or other measures as approved by the District.
11. Wild and Scenic Rivers - No activity may occur in a component of the National Wild and Scenic River System or in a river officially designated by Congress as a "study river" for possible inclusion in the system, while the river is in an official study status. Information on Wild and Scenic Rivers may be obtained from the appropriate land management agency in the area, such as the National Park Service and the U.S. Forest Service.
12. Tribal Rights - No activity or its operation may impair reserved tribal rights, such as reserved water rights, treaty fishing and hunting rights.
13. Water Supply Intakes - No discharge of dredged or fill material may occur in the proximity of a public water supply intake except where the discharge is for repair of the public water supply intake structures or adjacent bank stabilization.
14. Shellfish Production - No discharge of dredged or fill material may occur in areas of concentrated shellfish production.
15. Suitable Material - No discharge of dredged or fill material may consist of unsuitable material and material discharged shall be free from toxic pollutants in toxic amounts (see Section 307 of the Clean Water Act). Unsuitable material includes trash, debris, car bodies, asphalt, and creosote treated wood.
16. Spawning Areas - Discharges in spawning areas during spawning seasons shall be avoided to the maximum extent practicable.
17. Obstruction of High Flows - Discharges shall not permanently restrict or impede the passage of normal or expected high flows. All crossings shall be culverted, bridged or otherwise designed to prevent the restriction of expected high water flows, and shall be designed so as not to impede low water flows or the movement of aquatic organisms.
18. Impacts From Impoundments - If the discharge creates an impoundment of water, adverse impacts on aquatic resources caused by the accelerated passage of water and/or the restriction of its flow shall be avoided to the maximum extent practicable.
19. Waterfowl Breeding Areas - Discharges into breeding areas for migratory waterfowl shall be avoided to the maximum extent practicable.
20. Removal of Temporary Fills - Any temporary fill material shall be removed in its entirety and the affected area returned to its pre-existing condition.
21. Mitigation - All appropriate and practicable steps must first be taken to avoid and minimize impacts to aquatic resources. For unavoidable impacts, compensatory mitigation is required to replace the loss of wetland, stream, and/or other aquatic resource functions (33 CFR 332). The proposed compensatory mitigation shall utilize a watershed approach and fully consider the ecological needs of the watershed. Where an appropriate watershed plan is available, mitigation site selection should consider recommendations in the plan. The applicant shall describe in detail how the mitigation site was chosen and will be developed, based on the specific

resource need of the impacted watershed. Permit applicants are responsible for proposing an appropriate compensatory mitigation option to offset unavoidable impacts. However, the District is responsible for determining the appropriate form and amount of compensatory mitigation required when evaluating compensatory mitigation options, and determining the type of mitigation that would be environmentally preferable. In making this determination, the District will assess the likelihood for ecological success and sustainability, the location of the compensation site relative to the impact site and their significance within the watershed. Methods of providing compensatory mitigation include aquatic resource restoration, establishment, enhancement, and in certain circumstances, preservation. Compensatory mitigation will be accomplished by establishing a minimum ratio of 1.5 acres of mitigation for every 1.0 acre of impact to waters of the U.S. Furthermore, the District has the discretion to require additional mitigation to ensure that the impacts are no more than minimal. Further information is available at www.lrc.usace.army.mil/Missions/Regulatory/Illinois/Mitigation.aspx

22. Notification - The applicant shall provide written notification (i.e., a complete application) for a proposed activity to be authorized under the RPP prior to commencing a proposed activity. The District's receipt of the complete application is the date when the District receives all required notification information from the applicant (see below). If the District informs the applicant within 60 calendar days that the notification is incomplete (i.e., not a complete application), the applicant shall submit to the District, in writing, the requested information to be considered for review under the Regional Permit Program. A new 60 day review period will commence when the District receives the requested information. Applications that involve unauthorized activities that are completed or partially completed by the applicant are not subject to the 60-day review period.

For all activities, notification shall include:

- a. A cover letter providing a detailed narrative of the proposed activity describing all work to be performed, a clear project purpose and need statement, the Regional Permit(s) to be used for the activity, the area (in acres) of waters of the U.S. to be impacted (be sure to specify if the impact is permanent or temporary, and identify which area it affects), and a statement that the terms and conditions of the RPP will be followed.
- b. A completed joint application form for Illinois signed by the applicant or agent. The application form is available at www.lrc.usace.army.mil/Portals/36/docs/regulatory/forms/appform.pdf. If the applicant does not sign the joint application form, notification shall include a signed, written statement from the applicant designating the agent as their representative.
- c. A delineation of waters of the U.S., including wetlands, for the project area, and for areas adjacent to the project site (off-site wetlands shall be identified through the use of reference materials including review of local wetland inventories, soil surveys and the most recent available aerial photography), shall be prepared in accordance with the current U.S. Army Corps of Engineers methodology (www.usace.army.mil/Missions/CivilWorks/RegulatoryProgramandPermits/reg_supp.aspx) and generally conducted during the growing season.* Our wetland delineation standards are available at www.lrc.usace.army.mil/Portals/36/docs/regulatory/pdf/Delineations.pdf. For sites supporting wetlands, the delineation shall include a Floristic Quality Assessment (Swink and Wilhelm. 1994, latest edition, Plants of the Chicago Region). The delineation shall also include information on the occurrence of any high-quality aquatic resources (see Appendix A), and a listing of waterfowl, reptile and amphibian species observed while at the project area. The District reserves the right to exercise judgment when reviewing submitted wetland delineations. Flexibility of the requirements may be determined by the District on a case-by-case basis only.
- d. A street map showing the location of the project area.
- e. Latitude and longitude for the project in decimal degrees format (i.e. 41.88377N, -87.63960W).
- f. Preliminary engineering drawings sized 11" by 17" (full-sized may be requested by the project manager and you may also submit plans in PDF format on a disc) showing all aspects of the proposed activity and the location of waters of the U.S. to be impacted and not impacted. The plans shall include grading contours, proposed and existing structures such as buildings footprints, roadways, road crossings, stormwater management facilities, utilities, construction access areas and details of water conveyance structures. The plans shall also depict buffer areas, outlots or open space designations, best management practices, deed restricted areas and restoration areas, if required under the specific RP.
- g. Submittal of soil erosion and sediment control (SESC) plans that identify all SESC measures to be utilized during construction of the project.
- h. The application packet shall indicate whether resources (species, their suitable habitats, or critical habitat) listed or designated under the Endangered Species Act of 1973, as amended, may be present within areas affected (directly or indirectly) by the proposed project. Applicants shall provide a section 7 species list for the action area using the on-line process at the USFWS website. You can access "U.S. Fish and Wildlife Service Endangered Species Program of the Upper Midwest" website at www.fws.gov/midwest/Endangered. Click on the section 7 Technical Assistance green shaded box in the lower right portion of the screen and follow the instructions to completion. Print all documentation pertaining to the species list, include the rationale for your effects determination for each species, and forward the information to this office for review.

* If a wetland delineation is conducted outside of the growing season, the District will determine on a case-by-case basis whether sufficient evidence is available to make an accurate determination. If the District finds that the delineation lacks sufficient evidence, the application will not be considered complete until the information is provided. This may involve re-delineating the project site during the growing season.

In the event there are no species, their suitable habitats, or critical habitat, then a "no effect" determination can be made and section 7 consultation is not warranted. If species or critical habitat appear on the list, or suitable habitat is present within the action area, then a biological assessment or biological evaluation will need to be completed to determine if the proposed action will have "no effect" or "may effect" on the species or suitable habitat. The District will request initiation of section 7 consultation with the USFWS upon agreement with the applicant on the effect determinations in the biological assessment or biological evaluation. If the issues are not resolved, the analysis of the situation is complicated, or impacts to listed species or critical habitat are found to be greater than minimal, the District will consider reviewing the project under the Individual Permit process.

- i. A determination of the presence or absence of any State threatened or endangered species. Please contact the Illinois Department of Natural Resources (IDNR) to determine if any State threatened and endangered species could be in the project area. You can access the IDNR's Ecological Compliance Assessment Tool (EcoCAT) at the following website: <http://dnrecocat.state.il.us/ecopublic/>. Once you complete the EcoCAT and consultation process, forward all resulting information to this office for consideration. The report shall also include recommended methods as required by the IDNR for minimizing potential adverse effects of the project.
- j. A statement about the knowledge of the presence or absence of Historic Properties, which includes properties listed, or properties eligible to be listed in the National Register of Historic Places. A letter from the Illinois Historic Preservation Agency (IHPA) can be obtained indicating whether your project is in compliance with Section 106 of the National Historic Preservation Act of 1966, as amended. The permittee shall provide all pertinent correspondence with the IHPA documenting compliance. The IHPA has a checklist of documentation required for their review located here: www.illinoishistory.gov/PS/rcdocument.htm.
- k. Where an appropriate watershed plan is available, the applicant shall address in writing how the proposed activity is aligned with the relevant water quality, hydrologic, and aquatic resource protection recommendations in the watershed plan.
- l. A discussion of measures taken to avoid and/or minimize impacts to aquatic resources on the project site.
- m. A compensatory mitigation plan for all impacts to waters of the U.S. (if compensatory mitigation is required under the specific RP).
- n. A written narrative addressing all items listed under the specific RP.

For Category II activities, the District will provide an Agency Request for Comments (ARC) which describes the proposed activity. The ARC will be sent to the following agencies: United States Fish & Wildlife Service (USFWS), United States Environmental Protection Agency (USEPA), Illinois Department of Natural Resources (IDNR), Illinois Department of Natural Resources/Office of Water Resources (IDNR/OWR), Illinois Environmental Protection Agency (IEPA), Illinois Historic Preservation Agency (IHPA), Illinois Nature Preserves Commission (INPC) and U.S. Coast Guard (Section 10 activities only). Additional entities may also be notified as needed. These agencies have ten (10) calendar days from the date of the ARC to contact the District and either provide comments or request an extension not to exceed fifteen (15) calendar days. The District will fully consider agency comments received within the specified time frame. If the District determines the activity complies with the terms and conditions of the RPP and impacts on aquatic resources are minimal, the District will notify the applicant in writing and include special conditions if deemed necessary. If the District determines that the impacts of the proposed activity are more than minimal, the District will notify the applicant that the project does not qualify for authorization under the RPP and instruct the applicant on the procedures to seek authorization under an Individual Permit.

23. Compliance Certification - Any permittee who has received authorization under the RPP from the District shall submit a signed certification regarding the completed work and any required mitigation. The certification will be forwarded by the District with the authorization letter and will include: a) a statement that the authorized work was done in accordance with the District's authorization, including any general or specific conditions; b) a statement that any required mitigation was completed in accordance with the permit conditions and; c) the signature of the permittee certifying the completion of the work and mitigation.

24. Multiple use of Regional Permits - In any case where a Regional Permit is combined with any other Regional Permit to cover a single and complete project (except where prohibited under specific Regional Permits), the applicant shall notify the District in accordance with General Condition 22. If multiple Regional Permits are used, the total impact may not exceed the maximum allowed by the Regional Permit with the greatest impact threshold.

25. Other Restrictions - Authorization under the RPP does not obviate the need to obtain other Federal, State or local permits, approvals, or authorizations required by law nor does it grant any property rights or exclusive privileges, authorize any injury to the property or rights of others or authorize interference with any existing or proposed Federal project.

Approved by:

//ORIGINAL SIGNED//

Frederic A. Drummond, Jr.
Colonel, U.S. Army
District Commander

February 24, 2012

Date

LAKE COUNTY
DIVISION OF TRANSPORTATION

PERMIT TO PERFORM WORK WITHIN A
COUNTY HIGHWAY RIGHT-OF-WAY

BOND AND INSURANCE REQUIREMENTS

In order to receive a permit for the work within the right-of-way the following items must be submitted and approved:

- Acceptable Proof of Insurance adding the Lake County Division of Transportation, its employees and its agents, and the County of Lake, its employees and its agents, as additional insured to the Contractor's general liability insurance, per Chapter 10 of the Utility and Facility Ordinance (see attached). The LCDOT must be the certificate holder and named insured.
- Acceptable Performance Guarantee in the amount of \$10,000.00 for an eighteen month (minimum) term. Enclosed is the format of the Irrevocable Letter of Credit.
- Name, address, 24-hour telephone number of the Person in Charge for this project. This person must be responsible for the traffic control. This must come from the Person in Charge, written on his letterhead.

FORM DOT HIGHWAY RIGHT-OF-WAY LETTER OF CREDIT

(FINANCIAL HOUSE LETTERHEAD)

Irrevocable Letter of Credit No. _____
Re: [Project Name]
LCDOT Highway Permit No. _____
Amount: _____
Expiration Date: _____

Treasurer, County of Lake
Attention: Lake County Division of Transportation
County Engineer
600 Winchester Road
Libertyville, IL 60048

Gentlemen:

We hereby establish our irrevocable credit in the amount of _____ (specify amount)

(\$ _____) in favor of the Treasurer, County of Lake, Illinois, on behalf of (applicant name) _____ d/b/a (name) _____. We understand that this irrevocable credit is to be used to insure that all work proposed by, or on behalf of (applicant name) _____ for _____ (location) _____, is performed in compliance with the engineering plans as approved by the Lake County Division of Transportation and with the terms of the highway permit throughout the term of the project, and to insure the completion of said work and complete restoration of any damaged or disturbed portions of the County highway right-of-way as required by the Lake County Highway Temporary Closure and Utility and Facility Placement Ordinance, the approved engineering plans and specifications for that project, and Highway Permit No. _____.

This irrevocable credit established by us shall be in force until _____ and shall remain in effect without regard to any default in payment of sums owed by the owner and/or applicant and without regard to other claims which we may have against the owner and/or applicant.

This irrevocable credit shall in no event expire until 60 days after written notification of such expiration has been given by the issuing bank to the County Engineer by way of certified mail.

This Letter of Credit may be drawn upon by the Lake County Engineer at any time in the event that the above-described work or restoration is not being satisfactorily implemented in accordance with the Lake County Highway Temporary Closure and Utility and Facility Placement Ordinance and the highway permit. This Letter of Credit may also be drawn upon in the event that the above-described work or restoration has not been completed within the times set out in the time schedule provided in Chapter 6, of the Lake County Highway Temporary Closure and Utility and Facility Placement Ordinance and the highway permit. A written statement, signed by the County Engineer, in substantially the same form as that attached hereto as Exhibit "A", stating that the proposed work or restoration is not being satisfactorily implemented and/or has not been completed within the time set out in

Rev 3/10

EXHIBIT A"
FORM DEMAND LETTER

(DOT Letterhead)
(Date)

To: [Financial Institution Name and Address]
Attention: [Financial Institution Officer]

Re: (Financial Institution Name) Irrevocable Letter of Credit No. _____
Expiration Date: _____
(Project name)
LCDOT Highway Permit No. _____

"Drawn on (Financial Institution Name)
Letter of Credit No. _____"

Dear Sir or Madam:

This is a demand for payment, drawn on (financial institution name) Letter of Credit No. _____ of \$ _____ United States Dollars.

This demand is made in compliance with the conditions specified in the credit, to wit:

[T]his irrevocable credit is to be used to insure that all work proposed by, or on behalf of (applicant name), for (location), is performed in compliance with the engineering plans as approved by the Lake County Division of Transportation and the terms of the highway permit throughout the term of the project, and to insure the completion of said work and complete restoration of any damaged or disturbed portions of the County highway right-of-way as required by the Lake County Highway Temporary Closure and Utility and Facility Placement Ordinance, the approved engineering plans and specifications for that project, and Highway Permit No. _____.

* * *

[The] Letter of Credit may be drawn upon by the Lake County Engineer at any time in the event that the above-described work or restoration is not being satisfactorily implemented in accordance with the Lake County Highway Temporary Closure and Utility and Facility Placement Ordinance and the highway permit. This Letter of Credit may also be drawn upon in the event that the above-described work or restoration has not been completed within the times set out in the time schedule provided in Chapter 6 of the Lake County Highway Temporary Closure and Utility and Facility Placement Ordinance and the highway permit...

Rev 3/10

The aforementioned work or restoration is not being satisfactorily implemented and/or has not been completed within the time set out in the aforementioned time schedule.

Pursuant to the terms of the Letter of Credit, this demand for payment shall be honored no later than the close of the seventh banking day following receipt of this demand for payment.

The draft shall be payable to "Treasurer, County of Lake" and delivered to the County Engineer, Lake County Division of Transportation, 600 Winchester Road, Libertyville, Illinois 60048.

Sincerely,

County Engineer, County of Lake
Lake County Division of Transportation

Rev 3/10

EXHIBIT "B"

FORM SIGHT DRAFT

[NAME OF FINANCIAL HOUSE]
IRREVOCABLE LETTER OF CREDIT NO. _____

SIGHT DRAFT

DRAWN ON [NAME OF FINANCIAL HOUSE] LETTER OF CREDIT NO. _____.

\$_____.

[DRAW DATE]

AT SIGHT PAY TO THE ORDER OF TREASURER, COUNTY OF LAKE, ILLINOIS
[DOLLAR AMOUNT OF DRAW] AND ___/100 UNITED STATES DOLLARS
(US\$_____).

COUNTY ENGINEER, COUNTY OF LAKE
LAKE COUNTY DIVISION OF
TRANSPORTATION

[print name of County Engineer]

TO: [FINANCIAL HOUSE NAME AND ADDRESS]

CHAPTER 10 Indemnification

The County Engineer shall determine the minimum acceptable amounts for the following types of insurance--(1) Bodily Injury Liability and (2) Property Damage Liability. There shall be no restrictions on occurrence limits.

The permittee shall cease, or cause to be ceased, operations, work, and construction of an improvement if the insurance is canceled or reduced below the required minimum amount of coverage as determined by the County Engineer.

10.1 Certificates of Insurance

Certificates of Insurance, for all forms of insurance required by this Ordinance, shall be provided to the LCDOT prior to the issuance of a utility or facility permit for the construction or reconstruction of all types of utilities or facilities as provided for in this Ordinance. The County Engineer may, at his sole and exclusive discretion, upon receipt of written application from the permittee substantiating good and reasonable cause, allow the indemnification to be provided by someone other than the permittee for a single family homeowner, not for profit organization, or local agency. The Certificate of Insurance must include the Permit Number or the Project Name and County Highway location on the Certificate.

Certificates of Insurance acceptable to the LCDOT shall be filed with the LCDOT prior to the issuance of a permit. A copy of one type of acceptable insurance certificate can be found on the Division's website and will also be provided upon request.

The Certificate(s) shall contain a provision that coverages afforded under the policies will not be canceled or, non-renewed, and that restrictive modification cannot be added until at least 30 days after written notice has been given to LCDOT. A mere intent to notify LCDOT of cancellation IS NOT ACCEPTABLE.

Insurance coverages which are to remain in force and effect after completion of the construction will require an additional Certificate(s) evidencing continuation of such coverages.

Such additional Certificate(s) shall be submitted upon completion and acceptance of the construction improvements and upon one year thereafter. If any information concerning reduction of coverage is not furnished by the insurer, it shall be furnished by the permittee with reasonable promptness in accordance with the permittee's information and belief. Any acceptance of insurance certificates by the LCDOT shall in no way limit or relieve the permittee of the duties and responsibilities assumed by the permittee. Acceptance of insurance certificates not in compliance with the provisions of these requirements by LCDOT shall not affect a waiver of these requirements.

10.2 Additional Insured Endorsements

With respect to Commercial General Liability Policies and/or its equivalent form, the County of Lake and its officers, agents, and employees, and the Lake County Division of Transportation, and its officers, agents and employees, shall be designated by endorsement as an additional insured under said policy(ies). The Additional Insured endorsement must be approved by the County Engineer, or a person designated by the County Engineer to approve said endorsement. The endorsement must demonstrate, in a manner acceptable to LCDOT, that the endorsement has been bound by the insurance company. Examples of Additional Insured endorsements may be found on the Division's website and will also be provided upon request.

10.3 General Insurance Conditions for all Required Policies

With respect to all forms of insurance required per this Ordinance, the permittee shall purchase from and maintain in a company or companies lawfully authorized to do business in the State of Illinois, with an A.M. Best's Rating of at least A-Class VIII, such insurance as which will protect the owner from claims set forth below which may

arise out of or result from the permittee's operations under the permit and for which the permittee may be legally liable, whether such operations be by the permittee or by a contractor or subcontractor or by anyone directly or indirectly employed by any of them, or for anyone for whose acts any of them may be liable.

Any deductible and/or self-insured retention shall be the responsibility of the permittee.

All policies shall contain a provision that coverages afforded under the policies will not be canceled or, non-renewed, and that restrictive modification cannot be added until at least 30 days after written notice has been given to LCDOT. A mere intent to notify LCDOT of cancellation IS NOT ACCEPTABLE.

10.4 Workman's Compensation Insurance

Prior to the issuance of a permit by the LCDOT, the permittee shall furnish to the LCDOT certificates of insurance covering Workman's Compensation, or satisfactory evidence that this liability is otherwise taken care of in accordance with Section 4. (a) of the "Workman's Compensation Act of the State of Illinois" as amended.

10.4.1 Duration of Coverage

Such insurance, or other means of protection as herein provided, shall be kept in force until all work to be performed under the terms of the permit has been completed and accepted, and it is hereby understood and agreed that the maintenance of such insurance or other protection, until acceptance of the improvement by the LCDOT, is part of the permit. Failure to maintain such insurance, cancellation by the Industrial Commission of its approval of such other means of protection as might have been elected, or any other act which results in lack of protection under the said "Workman's Compensation Act" may result in the revocation of the permit.

10.5 Employer's Liability

The permittee shall obtain and maintain "Employer's Liability Insurance" to respond to claims because of bodily injury, occupational sickness or disease or death of the permittee's employees.

10.5.1 Duration of Coverage

The insurance described in Section 10.5 above shall be maintained for the duration of the operations performed by or on behalf of the permittee.

10.6 Commercial General Liability Insurance

The permittee shall obtain and maintain commercial general liability (C.G.L.) insurance on an occurrence basis as provided by the Commercial General Liability Coverage Form CG 00 01 (12 04), Insurance Services Office, Inc. or its equivalent or successor form or an equivalent policy of insurance. The Lake County Risk Management Department may, at its sole and exclusive discretion, determine what form(s) and policy(ies) are equivalent to the CGL ISO form. No restrictive endorsements pertaining to premises/operations insurance, contractual liability insurance, products and completed operations insurance or independent contractor's coverage may apply. The policy should respond to claims for damages because of "Bodily Injury" including death, "Property Damage," "Ongoing Operations," "Completed Operations" "Personal Injury" and "Advertising Injury."

10.6.1 Duration of C.G.L. Coverage

The insurance described above shall be maintained for the duration of the operations performed by or on behalf of the permittee. In addition, the permittee shall continue to carry "Complete Operations" liability insurance for at least twenty-four (24) months after the construction is complete. The permittee shall furnish the LCDOT evidence of such insurance at completion of construction and one year thereafter after its acceptance by the LCDOT.

10.6.2 C.G.L. Insurance Conditions

The Lake County Division of Transportation and its officers, agents and employees; Lake County and its officers, agents and employees shall be named as additional insureds by endorsement per the requirements of Section 10.2 set forth above. Said insurance shall be written on an occurrence basis. The permittee's insurance shall be primary and non-contributory. The policy shall contain the standard Separation of Insureds condition. The policy shall be endorsed to allow the General Aggregate Limit under LIMITS OF INSURANCE of the policy to apply separately to each project and each location.

10.7 Automobile Liability

The permittee shall obtain and maintain business auto liability insurance as provided by the Business Auto Coverage Form CG 00 01 (12 07), Insurance Services Office, Inc., or its equivalent or successor form. The policy should respond to claims for damages because of bodily injury, death of a person or property damage arising out of the ownership, maintenance or use of a motor vehicle. This policy shall be written to cover any auto whether owned, leased, hired, or borrowed.

10.7.1 Duration of Coverage

The insurance described in Section 10.7 above shall be maintained for the duration of the operations performed by or on behalf of the permittee.

10.7.2 Insurance Conditions

The policy shall contain the standard Severability of Interests provisions.

10.8 Minimum Limits of Liability

The permittee's commercial general liability insurance, business automobile liability insurance and employer's liability insurance as required by the preceding paragraphs shall be written with limits of insurance not less than the following:

Commercial General Liability Insurance:

General Aggregate Limit*	\$2,000,000
Products-Completed Operations Aggregate Limit	\$2,000,000
Personal & Advertising Injury Limit	\$1,000,000
Each Occurrence Limit	\$1,000,000

*The policy shall be endorsed for the general aggregate on a "per project" basis as well as a "per location" basis.

Employer's Liability Insurance:

Bodily Injury by Accident (Each Accident)	\$1,000,000
Bodily Injury by Disease (Each Employee)	\$1,000,000
Bodily Injury by Disease (Policy Limit)	\$1,000,000

Automobile Liability Insurance:

Bodily Injury, Property Damage and Covered Pollution Cost or Expense (Each Occurrence Limit)	\$1,000,000
--	-------------

10.9 Self-Insurance

Any organization seeking a permit under the Ordinance which is self-insured, must meet and/or exceed the requirements of the Illinois Department of Insurance and the Illinois statute(s) for self-insurers. Qualified legal counsel must provide a provision to be inserted within any self-insured documents and/or trust, which provides that the protection afforded the Lake County Division of Transportation, its officers, agents and employees and Lake County, its officers, agents and employees will be the equivalent of the insurance protection required of those organizations which do purchase the required insurance coverages.

LCDOT is not obligated to accept self-insurance by an organization in lieu of any or all of the insurance policies or coverages delineated above. The decision to accept or reject an organization's self-insurance shall be made solely and exclusively by the County Engineer at the County Engineer's discretion.

POLICY NUMBER:

COMMERCIAL GENERAL LIABILITY
CG 20 12 07 98

THIS ENDORSEMENT CHANGES THE POLICY. PLEASE READ IT CAREFULLY.

**ADDITIONAL INSURED –
STATE OR POLITICAL SUBDIVISIONS – PERMITS**

This endorsement modifies insurance provided under the following:

COMMERCIAL GENERAL LIABILITY COVERAGE PART

SCHEDULE

State Or Political Subdivision:

(If no entry appears above, information required to complete this endorsement will be shown in the Declarations as applicable to this endorsement.)

Section II – Who Is An Insured is amended to include as an insured any state or political subdivision shown in the Schedule, subject to the following provisions:

1. This insurance applies only with respect to operations performed by you or on your behalf for which the state or political subdivision has issued a permit.
2. This insurance does not apply to:
 - a. "Bodily injury," "property damage" or "personal and advertising injury" arising out of operations performed for the state or municipality; or
 - b. "Bodily injury" or "property damage" included within the "products-completed operations hazard".

POLICY NUMBER:

COMMERCIAL GENERAL LIABILITY

THIS ENDORSEMENT CHANGES THE POLICY. PLEASE READ IT CAREFULLY.

ADDITIONAL INSURED – DESIGNATED PERSON OR ORGANIZATION

This endorsement modifies insurance provided under the following:

COMMERCIAL GENERAL LIABILITY COVERAGE PART.

SCHEDULE

Name of Person or Organization:

(If no entry appears above, information required to complete this endorsement will be shown in the Declarations as applicable to this endorsement.)

WHO IS AN INSURED (Section II) is amended to include as an insured the person or organization shown in the Schedule as an insured but only with respect to liability arising out of your operations or premises owned by or rented to you.



STORMWATER MANAGEMENT COMMISSION

October 25, 2013

Mr. Ron Kroop
Village of Round Lake
751 Townline Road
Round Lake, IL 60073

Subject: Hart Road Reconstruction, Round Lake
IL Route 134 to Cedar Lake Road & Sunset Drive from Hart to Long Lake Drive
Watershed Development Permit #PC13-38-077
PERMIT ISSUANCE

Dear Mr. Kroop:

Accompanying this letter is the required Watershed Development Permit. This approval is based on the plans entitled:

PLANS FOR PROPOSED FEDERAL AID HIGHWAY FAU 201 (HART ROAD) FAU 186 (IL ROUTE 134) TO FAU 192 (CEDAR LAKE ROAD) RECONSTRUCTION, VILLAGE OF ROUND LAKE, LAKE COUNTY, BY BAXTER & WOODMAN CONSULTING ENGINEERS. DATED AUGUST 12, 2013, RECEIVED BY SMC SEPTEMBER 20, 2013, 53 SHEETS

This approval is subject to the conditions on the back of the permit including the following:

- Providing the permit review fee of \$3,280, a refundable pre-construction meeting deposit of \$240, and a refundable inspection deposit of \$720.
- Providing prior notification to Brian Cook (of the SMC) of the pre-construction meeting at least 5 calendar days in advance to enable SMC attendance. The refund for the \$240 pre-construction meeting deposit will be made after the meeting.
- Providing as-built plans for any significant deviation from the permitted plan set. The inspection deposit of \$720 may be reduced after permanent site stabilization, approval of the as-built submittal (if necessary), and resolution of other permit conditions. Typical as-built requirements are summarized on the attached checklist.
- Keeping copies of the native vegetation seed tags and/or landscaper invoices clearly showing the species of native vegetation that were planted. This information will be required during the as-built review stage.
- Appropriate soil erosion and sedimentation control measures shall be installed to prevent sediment-laden runoff from entering downstream water bodies and wetlands.
- **No work in the LCDOT right-of-way and USACE-jurisdiction wetlands shall be allowed until necessary authorizations from LCDOT and USACE have been issued.**

500 W. Winchester Road, Suite 201 • Libertyville, Illinois 60048 • 847/377-7700 • FAX 847/984-5747

U:\Regulatory Program\Permits\13 Permits\13-38-077\CORRESPONDENCE\102513_jcpermit.doc

Revised 10/30/13

378

Mr. Ron Kroop
October 25, 2013
Page 2 of 2

We would like to be of assistance. If you have any questions, or would like to set up the pre-construction meeting, please call Brian Cook at (847) 377-7702 or e-mail at bcook@lakecountyl.gov. If you have any additional concerns that have not been addressed by the regulatory staff, you may contact Chief Engineer Kurt Woolford kwoolford@lakecountyl.gov or Executive Director Michael Warner mwarner@lakecountyl.gov at (847) 377-7700.

If you would like to provide feedback regarding the SMC permit/inspection process please go to: (password – survey)


<http://www.lakecountyl.gov/Stormwater/Pages/PermitProcessSurvey.aspx>
<http://www.lakecountyl.gov/Stormwater/Pages/InspectionProcessSurvey-.aspx>

Sincerely,

LAKE COUNTY STORMWATER MANAGEMENT COMMISSION



Joanna S. Colletti, P.E., CFM
Regulatory Engineering Supervisor



Kurt Woolford, P.E., CFM, LEED AP
Chief Engineer

- Encl: Watershed Development Permit
As-Built Review Checklist
- C: Melyssa Navis – USACE
Betsy Duckert – LCDOT
Russ Kraly – Village of Round Lake
Kurt Baumann – Baxter & Woodman
Thomas Ganfield – Baxter & Woodman
Dave Hemmerich – Baxter & Woodman

This document was digitally transmitted. Please print out a copy of the document and retain for your records. If you are unable to print the document, or desire a hard copy mailed to you, please notify me at your earliest convenience.



STORMWATER MANAGEMENT COMMISSION

WATERSHED DEVELOPMENT PERMIT HAS BEEN SECURED WD PERMIT NUMBER PC13-38-077

Project: Hart Road Reconstruction, Village of Round Lake

Address: Hart Rd. between IL 134 & Cedar Lake Road PIN No.: N/A

Date Issued: 10/25/2013

Issued By: Joanna S. Colletti, PE, CFM
Regulatory Engineering Supervisor

Kurt A. Woolford, PE, CFM, LEED AP
Chief Engineer

CONDITIONS:

- Providing the permit review fee of \$3,280, a refundable pre-construction meeting deposit of \$240, and a refundable inspection deposit of \$720.
- Providing prior notification to Brian Cook (of the SMC) of the pre-construction meeting at least 5 calendar days in advance to enable SMC attendance. The refund for the \$240 pre-construction meeting deposit will be made after the meeting.
- Providing as-built plans for any significant deviation from the permitted plan set. The inspection deposit of \$720 may be reduced after permanent site stabilization, approval of the as-built submittal (if necessary), and resolution of other permit conditions. Typical as-built requirements are summarized on the attached checklist.
- Keeping copies of the native vegetation seed tags and/or landscaper invoices clearly showing the species of native vegetation that were planted. This information will be required during the as-built review stage.
- Appropriate soil erosion and sedimentation control measures shall be installed to prevent sediment-laden runoff from entering downstream water bodies and wetlands.
- **No work in the LCDOT right-of-way and USACE-jurisdiction wetlands shall be allowed until necessary authorizations from LCDOT and USACE have been issued.**

NOTICE TO CONTRACTORS AND OWNERS

POST THIS CARD AT THE SITE, VISIBLE FROM THE STREET AND SO LOCATED AS TO PERMIT THE INSPECTOR TO RECORD THE INDICATED INSPECTIONS ON THE PLACARD. DO NOT POST IN THE INTERIOR OF A BUILDING.

INSPECTORS AND SHERIFF'S DEPUTIES ARE INSTRUCTED TO STOP ALL WORK WHERE THIS PERMIT CARD IS NOT DISPLAYED.

ALWAYS MENTION THE WATERSHED DEVELOPMENT PERMIT NUMBER WHEN REFERRING TO THIS PROJECT. IF THIS CARD BECOMES MISLAID OR LOST PLEASE CONTACT LAKE COUNTY STORMWATER MANAGEMENT COMMISSION FOR A REPLACEMENT.

Lake County Stormwater Management Commission (847) 377-7705