

EARTHWORK – STAGE 2

LOCATION		20200100	20300100	20300200	EARTH EXCAVATION ADJUST SHRINKAGE 25% EARTH	EMBANKMENT (FILL)	20400800	21101505
		EARTH EXCAVATION (CUT)	CHANNEL EXCAVATION	ROCK EXCAVATION IN CHANNEL			EARTHWORK BALANCE WASTE (+) SHORTAGE (-) *	TOPSOIL EXCAVATION AND PLACEMENT
STATION TO STATION		CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
STAGE 2								
IL 173 - RT								
1022+20.19	1027+00	586	0	0	439	1704	-1264	220
1027+00	1033+00	77	0	0	58	2947	-2889	211
1033+00	1039+00	3158	0	0	2369	434	1935	176
1039+00	1045+00	3804	0	0	2853	1	2852	197
1045+00	1051+00	1394	0	0	1045	257	789	127
1051+00	1057+00	254	0	0	191	1636	-1445	229
1057+00	1063+00	122	0	0	92	3502	-3410	233
1063+00	1069+00	1784	0	0	1338	2954	-1616	496
1069+00	1072+00	190	0	0	142	804	-661	224
1072+00	1078+00	619	0	0	464	520	-55	292
CONTINENTAL DRIVE								
87+75	89+00	292	0	0	219	5	214	16
KIMBER DRIVE								
95+68.88	96+44.37	0	0	0	0	0	0	0
97+80	99+00	520	0	0	390	3	387	28
SPEEDWAY NORTH ENTRANCE								
298+37.90	299+00	100	0	0	75	12	63	7
FOREST HILLS ROAD - LT								
376+10	380+00	134	0	0	101	120	-20	65
380+00	385+50	1655	0	0	1241	113	1128	171
385+50	391+50	1200	0	0	900	504	396	84
391+50	397+50	1162	0	0	872	2390	-1519	201
397+50	399+00	281	0	0	211	365	-154	43
451+00	453+00	383	0	0	287	81	206	25
453+00	459+00	362	0	0	272	2733	-2462	188
459+00	465+00	1472	0	0	1104	249	855	201
465+00	469+48	838	0	0	629	157	472	148
OSF ENTRANCE								
38+00	38+50	58	0	0	44	34	10	106
PERRYVILLE ROAD - RT								
248+10.79	249+00	155	0	0	116	144	-28	25
251+50	253+50	461	0	0	346	384	-38	79
CONTRACTORS DRIVE								
5+50	9+00	603	0	0	452	206	246	75
SPEEDWAY EAST ENTRANCE								
97+25	99+00	121	0	0	91	359	-268	43
TOTAL		21784	0	0	16338	22616	-6277	3910

* 20400800 FURNISHED EXCAVATION

FILE NAME = ...\\CADD SHEETS\200793CVR-S012.dgn	USER NAME = Elgin 110	DESIGNED - MJS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES EARTHWORK – STAGE 2				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
THE UPCHURCH GROUP, INC.	PLOT SCALE = 2.0000' / IN.	DRAWN - JAU	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.	303	129R	WINNEBAGO	968	52
	PLOT DATE = 7/22/2013 11:51:19 AM	CHECKED - RLH	REVISED -		CONTRACT NO. 64988											
		DATE -	REVISED -		ILLINOIS FED. AID PROJECT											