

			70300100	70300220	70300280	70301000	78001110	78001130	78001180	78300100	78300200		
LOCATION			TYPE	COLOR	SHORT TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 24"	WORK ZONE PAVEMENT MARKING REMOVAL	PAINT PAVEMENT MARKING - LINE 4"	PAINT PAVEMENT MARKING - LINE 6"	PAINT PAVEMENT MARKING - LINE 24"	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
STATION	STATION	OFFSET			(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(EACH)
FULTON ROAD													
6+58.80	7+08.80	CL	SOLID DOUBLE	YELLOW		50		17					
7+68.80	9+81.70	RT	SOLID	YELLOW		213		71					
7+08.80		RT	SOLID	WHITE			12	24					
9+40.00	9+44.30	LT	SOLID	YELLOW		5		2					
STAGE III													
IL84													
314+30.00	314+47.00	LT	SOLID	WHITE				34					
315+00.00	320+97.00	LT	SOLID	WHITE				1194					
322+19.00	324+47.00	LT	SOLID	WHITE				456					
324+92.00	325+76.00	LT	SOLID	WHITE				168					
314+30.00	317+03.00	RT	SOLID	WHITE				546					
318+45.00	321+36.00	RT	SOLID	WHITE				582					
322+02.00	324+47.00	RT	SOLID	WHITE				490					
324+92.00	325+76.00	RT	SOLID	WHITE				168					
314+30.00		CL											
315+10.00		CL											
315+90.00		CL											
316+70.00		CL											
317+50.00		CL											
314+30.00	321+33.00	CL	DOUBLE SOLID	YELLOW	144			2812					
318+30.00		CL											
321+33.00			SOLID	WHITE					86				
321+39.00			SOLID	WHITE					82				
321+55.00		CL											
322+00.00	325+76.00	CL	DOUBLE SOLID	YELLOW	72			1504					
322+35.00		CL											
323+15.00		CL											
323+95.00		CL											
324+75.00		CL											
325+55.00		CL											
FULTON ROAD													
9+65.00			SOLID	WHITE	22					44			
9+71.00			SOLID	WHITE					100				
9+77.00			SOLID	WHITE					114				
FULTON STREET													
10+22.00			SOLID	WHITE					56				
10+28.00			SOLID	WHITE					44				
SUBTOTAL					238	268	12	114	7,954	482	44	0	0
TOTAL					238	6,150	96	2,249	7,954	482	44	732	11

THE SCHEDULES DO NOT INCLUDE QUANTITIES FOR THE SANITARY LIFT STATION PLANS OR LIGHTING PLANS.



USER NAME = gjameson	DESIGNED -	REVISED
FILE NAME = Z64E08-SHT-500.dgn	CHECKED -	REVISED
PLOT SCALE = 10.0000' / IN.	DRAWN -	REVISED
PLOT DATE = 8/5/2013	CHECKED -	REVISED

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES  
IL ROUTE 84 OVER APPLE RIVER**

SCALE: NTS      SHEET NO. 4 OF 9 SHEETS      STA.      TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
308	103BR-4	JO DAVIESS	159	20
CONTRACT NO. 64E08				
ILLINOIS FED. AID PROJECT				