


40600625      40603310      42001430

LOCATION	OFFSET	LENGTH	WIDTH	AREA	LEVELING BINDER		HMA SURFACE COURSE THICKNESS (INCHES)	LEVELING BINDER (MACHINE METHOD), N50 (TON)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 (TON)	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) (SQ YD)
					THICKNESS (INCHES)	AVERAGE THICKNESS				
STATION	LT/RT	(FT)	(FT)	(SQ FT)	(INCHES)		(INCHES)	(TON)	(TON)	(SQ YD)
IL 84										
PAVEMENT										
321+51.08 TO 321+57.08		6.00	24							16
321+57.08			24		0.00					
321+75.00		17.92	24		0.00	0.00	1.5	0		
322+00.00		25.00	24		2.50	1.25	1.5	5		
322+25.00		25.00	24		4.00	3.25	1.5	13		
322+50.00		25.00	24		2.50	3.25	1.5	13		
322+75.00		25.00	24		1.25	1.88	1.5	8		
323+00.00		25.00	24		0.50	0.88	1.5	4		
323+05.00		5.00	24		0.00	0.25	1.5	1		
321+51.07 TO 323+05		153.93	24				1.5		35	
SHOULDER										
317+40.00 TO 318+29.71	LT	89.71	4.90				1.5		5	
317+45.00 TO 318+38.23	RT	93.23	4.70				1.5		5	
322+19.00 TO 322+95.40	LT	76.40	3.00				1.5		3	
322+95.40 TO 323+05.00	LT	9.60	3.57				1.5		1	
322+01.95 TO 323+05.00	RT	103.05	3.00				1.5		3	
FULTON ROAD										
SHOULDER										
NORTHWEST QUADRANT				28			2.5		1	
FULTON STREET										
SHOULDER										
NORTHEAST QUADRANT				57			2.5		1	
TOTAL								44	54	16

28000510

LOCATION		INLET FILTERS
STATION	OFFSET	EACH
IL 84		
317+45.00	18.36' LT	1
317+83.00	17.07' LT	1
317+82.00	13.39' RT	1
317+82.00	17.30' RT	1
321+94.00	18.54' LT	1
321+97.60	21.30' RT.	1
321+97.60	29' RT	1
322+08.50	15' RT	1
322+08.50	21.30' RT	1
322+50.00	15' LT	1
322+50.00	15' RT	1
322+95.00	19.67' LT	1
FULTON ROAD		
9+33.00	11.95' RT	1
9+53.00	16.95' RT	1
FULTON STREET		
10+39.00	10' LT	1
10+39.00	10' RT	1
TOTAL		16

THE SCHEDULES DO NOT INCLUDE QUANTITIES FOR THE SANITARY LIFT STATION PLANS OR LIGHTING PLANS.



USER NAME = gjameson	DESIGNED -	REVISED
FILE NAME = Z64E08-SHT-S00.dgn	CHECKED -	REVISED
PLOT SCALE = 10.0000' / IN.	DRAWN -	REVISED
PLOT DATE = 8/6/2013	CHECKED -	REVISED

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES  
IL ROUTE 84 OVER APPLE RIVER**

SCALE: NTS      SHEET NO. 5 OF 9 SHEETS      STA.      TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
308	103BR-4	JO DAVIESS	159	21
CONTRACT NO. 64E08				ILLINOIS FED. AID PROJECT