

M001C,01 M001C,01 07P0C,01 M001C,01 02 03 07P0C,01

PAY ITEM #	DESCRIPTION	UNIT	TOTAL	ROADWAY 0004	BRIDGE 0011	LIGHTING 0021	RETAINING WALL 0040		LIFT STATION RELOCATON 0040	
				80% FED 20% STATE	80% FED 20% STATE	VILLAGE OF HANOVER 100% LOCAL	#1	#2 AND #3	80% FED 20% STATE	VILLAGE OF HANOVER 100% LOCAL
						80% FED / 20% STATE				
20200100	EARTH EXCAVATION	CU YD	805	805						
20300100	CHANNEL EXCAVATION	CU YD	1,882	1,882						
20800150	TRENCH BACKFILL	CU YD	285	285						
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,490	585					905	
25200110	SODDING, SALT TOLERANT	SQ YD	1,490	585					905	
25200200	SUPPLEMENTAL WATERING	UNIT	6	6						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	40	40						
28000305	TEMPORARY DITCH CHECKS	FOOT	20	20						
28000400	PERIMETER EROSION BARRIER	FOOT	887	549					338	
28000510	INLET FILTERS	EACH	22	16					6	
28100109	STONE RIPRAP, CLASS A5	SQ YD	488		488					
28200200	FILTER FABRIC	SQ YD	1,341		1,341					
28401700	SLOPE MATTRESS 24"	SQ YD	853		853					
30300124	AGGREGATE SUBGRADE IMPROVEMENT 24"	SQ YD	1,054	1,054						

14