

PAY ITEM #	DESCRIPTION	UNIT	TOTAL	ROADWAY 0004	BRIDGE 0011	LIGHTING 0021	RETAINING WALL 0040		LIFT STATION RELOCATON 0040	
				80% FED	80% FED	VILLAGE OF HANOVER	#1	#2 AND #3	80% FED	VILLAGE OF HANOVER
				20% STATE	20% STATE	100% LOCAL	80% FED / 20% STATE	20% STATE	100% LOCAL	
50500505	STUD SHEAR CONNECTORS	EACH	3,918		3,816		102			
50800105	REINFORCEMENT BARS	POUND	7,350		7,350					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	203,420		183,970		2,570	16,880		
50800515	BAR SPLICERS	EACH	1,455		1,455					
50901750	PARAPET RAILING	FOOT	45				45			
51500100	NAME PLATES	EACH	2		1		1			
51602000	PERMANENT CASING	FOOT	35		35					
* 51603000	DRILLED SHAFT IN SOIL	CU YD	32.8		32.8					
* 51604000	DRILLED SHAFT IN ROCK	CU YD	40.6		40.6					
52000110	PREFORMED JOINT STRIP SEAL	FOOT	101		101					
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12		12					
52100520	ANCHOR BOLT, 1"	EACH	24		24					
52100530	ANCHOR BOLT, 1 1/4"	EACH	12		12					
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	3	3						

14

* specialty items