PAY ITEM #	DESCRIPTION	UNIT	TOTAL	ROADWAY 0004	BRIDGE 0011	LIGHTING 0021	RETAINING WALL 0040		LIFT STATION RELOCATON 0040	
				80% FED 20% STATE	80% FED 20% STATE	VILLAGE OF HANOVER 100% LOCAL	#1	#2 AND #3	80% FED 20% STATE	VILLAGE OF HANOVER 100% LOCAL
							80% FED / 20% STATE			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	15	15						
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	118	118						
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	147	147						
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	43	43						
58700300	CONCRETE SEALER	SQ FT	1,401		1,401					
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	187		91		19	77		
60107600	PIPE UNDERDRAINS 4"	FOOT	36	36						
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1	1						
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1						
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	5	5						
60500060	REMOVING INLETS	EACH	7	7						
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	121	121						
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	676	656					20	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2						

19