

11/11 P P 05/12

| PAY ITEM # | DESCRIPTION | UNIT | TOTAL | ROADWAY 0004 | BRIDGE 0011 | LIGHTING 0021 | RETAINING WALL 0040 | | LIFT STATION RELOCATON 0040 | |
|------------|---|-------|-------|----------------------|----------------------|----------------------------------|---------------------------|-----------|-----------------------------|----------------------------------|
| | | | | 80% FED 20% STATE | 80% FED 20% STATE | VILLAGE OF HANOVER 100% LOCAL | #1 80% FED / 20% STATE | #2 AND #3 | 80% FED 20% STATE | VILLAGE OF HANOVER 100% LOCAL |
| Z0018002 | DRAINAGE SCUPPERS, DS-11 | EACH | 4 | | 4 | | | | | |
| Z0026403 | FURNISHING SOLDIER PILES (BUILT-UP SECTION) | FOOT | 18 | | | | 18 | | | |
| Z0026404 | FURNISHING SOLDIER PILES (W SECTION) | FOOT | 99 | | | | 99 | | | |
| Z0046304 | PIPE UNDERDRAINS FOR STRUCTURES 4" | FOOT | 338 | | 132 | | 66 | 140 | | |
| Z0056608 | STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH | FOOT | 35 | 35 | | | | | | |
| Z0056610 | STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH | FOOT | 153 | 153 | | | | | | |
| Z0056900 | SANITARY SEWER 8" | FOOT | 455 | | | | | | 263 | 192 |
| Z0062456 | TEMPORARY PAVEMENT | SQ YD | 356 | 106 | | | | | 151 | 99 |
| Z0073002 | TEMPORARY SOIL RETENTION SYSTEM | SQ FT | 816 | | 816 | | | | | |
| Z0073100 | TEMPORARY SHORING | EACH | 2 | | 2 | | | | | |
| Z0073500 | TEMPORARY SUPPORT SYSTEM | L SUM | 1 | | 1 | | | | | |
| Z0075496 | CONCRETE RETAINING WALL REMOVAL | FOOT | 11 | 11 | | | | | | |

* SPECIALTY ITEMS

design firm
no. 184001038



| | | |
|--------------------------------|------------|---------|
| USER NAME * gjomason | DESIGNED - | REVISED |
| FILE NAME * 264E08-SHT-SUM.dgn | CHECKED - | REVISED |
| PLOT SCALE * 10.0000' / IN. | DRAWN - | REVISED |
| PLOT DATE * 8/6/2013 | CHECKED - | REVISED |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL ROUTE 84 OVER APPLE RIVER
SCALE: NTS SHEET NO. 10 OF 10 SHEETS STA. TO STA.

| | | | | |
|--------------------|--------------------|----------------------|---------------------------|-----------------|
| F.A.P. RTE. 308 | SECTION 103BR-4 | COUNTY JO DAVIESS | TOTAL SHEETS 159 | SHEET NO. 14 |
| CONTRACT NO. 64E08 | | | ILLINOIS FED. AID PROJECT | |

Rev.