SCHEDULE OF QUANTITIES

66700305 PERMANENT SURVEY MARKERS, TYPE II

LOCATION	EACH	COMMENTS
TO BE DETERMINED IN FIELD	7	LOCATION DETERMINED BY DISTRICT OFFICE-CHIEF OF SURVEYS
TOTAL	7	

78001110 PAINT PAVEMENT MARKING - LINE 4"

LOCATION					FOOT	COMMENTS
STA 317+94	TO	318+56	Yellow	(2 Apl.)	248.00	Double Solid
STA 324+43	TO	324+76	Yellow	(2 Apl.)	132.00	Double Solid
STA 338+91	TO	339+39	Yellow	(2 Apl.)	192.00	Double Solid
STA 372+50	TO	378+00	Yellow	(2 Apl.)	1,375.00	Solid LT, Skip Dash RT
STA 378+89	TO	379+24	Yellow	(2 Apl.)	87.50	Solid LT, Skip Dash RT
STA 383+65	TO	384+07	Yellow	(2 Apl.)	21.00	Skip Dash Center
STA 393+45	TO	393+83	Yellow	(2 Apl.)	19.00	Skip Dash Center
STA 396+76	TO	397+60	Yellow	(2 Apl.)	210.00	Solid RT, Skip Dash LT
STA 462+02	TO	462+71	Yellow	(2 Apl.)	276.00	Double Solid
STA 466+25	TO	467+46	Yellow	(2 Apl.)	484.00	Double Solid
STA 479+20	TO	479+54	Yellow	(2 Apl.)	136.00	Double Solid
STA 491+97	TO	492+66	Yellow	(2 Apl.)	276.00	Double Solid
			TOTAL YELLOW:		3,456.50	
STA 317+94	TO	318+56	White	(2 Apl.)	248.00	LT & RT Edge Lines
STA 324+43	TO	324+76	White	(2 Apl.)	132.00	LT & RT Edge Lines
STA 338+91	TO	339+39	White	(2 Apl.)	192.00	LT & RT Edge Lines
STA 372+50	TO	378+00	White	(2 Apl.)	2,200.00	LT & RT Edge Lines
STA 378+89	TO	379+24	White	(2 Apl.)	140.00	LT & RT Edge Lines
STA 383+65	TO	384+07	White	(2 Apl.)	168.00	LT & RT Edge Lines
STA 393+45	TO	393+83	White	(2 Apl.)	152.00	LT & RT Edge Lines
STA 396+76	TO	397+60	White	(2 Apl.)	336.00	LT & RT Edge Lines
STA 462+02	TO	462+71	White	(2 Apl.)	276.00	LT & RT Edge Lines
STA 466+25	TO	467+46	White	(2 Apl.)	484.00	LT & RT Edge Lines
STA 479+20	TO	479+54	White	(2 Apl.)	136.00	LT & RT Edge Lines
STA 491+97	TO	492+66	White	(2 Apl.)	276.00	LT & RT Edge Lines
			TOTAL WHITE:		4,740.00	
				TOTAL	8,196.50	

78100100 RAISED REFLECTIVE PAVEMENT MARKERS

LOCATION			EACH	COMMENTS
STA 317+50	TO	492+75	15	Two-way amber @ 80' centers, 40' centers around curve per std.
		TOTAL	15	

78200410 GUARDRAIL MARKERS, TYPE A

LOCATION				EACH	COMMENTS
STA 373+71.12	TO	376+30.41	RT	4	
STA 374+33.20	TO	376+92.46	LT	4	
			TOTAL	8	

78200520 BARRIER WALL MARKERS, TYPE B

LOCATION				EACH	COMMENTS
STA 374+76.38	TO	375+86.88	LT & RT	4	2 Markers per side
			TOTAL	4	

78201000 TERMINAL MARKER - DIRECT APPLIED

LOCATION	EACH	COMMENTS
STA 373+21.16 RT	1	
STA 373+83.16 LT	1	
STA 376+80.45 RT	1	
STA 377+42.38 LT	1	
TOTAL	4	

X2501810 SEEDING, CLASS 5 (SPECIAL)

LOCATION				ACRE	COMMENTS
STA 7+75	TO	12+75	LT & RT	0.75	MINERAL CREEK
			TOTAL	0.75	

X0323660 DROP BOX NO.1

LOCATION		EACH	COMMENTS
STA 318+25	RT	1	
	TOTAL	1	

X0323661 DROP BOX NO.2

LOCATION		EACH	COMMENTS
STA 339+15	RT	1	
	TOTAL	1	

X0323662 DROP BOX NO.3

LOCATION		EACH	COMMENTS
STA 397+17	RT	1	
	TOTAL	1	

X0327396 TRANSVERSABLE PIPE GRATES

LOCATION		FOOT	COMMENTS
STA 318+25	LT	198'-8"	12' x 8' BOX CULVERT END SECTION - 4@38'-0" AND 4@11'-8"
STA 318+25	RT	227'-11"	DROP BOX NO.1 - 5@11'-9", 5@22'-2" AND 5@11'-8"
STA 339+15	LT	47'-9"	48" PIPE CULVERT END SECTION - 2@21'-4" AND 1@ 5'-1"
STA 339+15	RT	55'	DROP BOX NO.2 - 2@5'-9", 4@5'-8" AND 2@10'-5"
STA 380+50	RT	124'-8"	6' x 3' BOX CULVERT END SECTION - 22@5'-8"
STA 393+64	LT & RT	64'	6' x 3' BOX CULVERT END SECTION - 4@16'-0"
STA 397+17	LT	16'-10"	36" PIPE CULVERT END SECTION - 1@16'-10"
STA 397+32	RT	14'	DROP BOX NO.3 - 3@4'-8"
STA 466+50	LT & RT	568'	12' x 6' BOX CULVERT END SECTION - 16@29'-8" AND 8@11'-8"
STA 479+36	LT & RT	218'-8"	9' x 6' BOX CULVERT END SECTION - 6@28'-8" AND 4@11'-8"
STA 492+34	LT & RT	218'-8"	9' x 6' BOX CULVERT END SECTION - 6@28'-8" AND 4@11'-8"
	TOTAL	1754'-2"	

Z0004552 APPROACH SLAB REMOVAL

LOCATION			SQ YD	COMMENTS
STA 374+88.31	TO	375+08.30	75.00	
STA 375+55.43	TO	375+75.54	75.00	
		TOTAL	150.00	

Z0020900 ESTABLISHING AND REFERENCING LAND SECTION MARKERS

LOCATION		EACH	COMMENTS
STA 393+86.82	9.89' LT	1	
	TOTAL	1	

Z0025500 PROPERTY MARKERS

LOCATION		EACH	COMMENTS
STA 317+00	LT	1	
STA 375+50	LT & RT	2	
STA 461+67	LT	1	
	TOTAL	4	