



CHANGEABLE MESSAGE SIGN WITH THE FOLLOWING 3 MESSAGE SCREENS:



CHANGEABLE MESSAGE SIGN WITH THE FOLLOWING 3 MESSAGE SCREENS:



SIGN TYPE LEGEND

- M4-1a-2115 (BLACK ON FLUORESCENT ORANGE)
- M1-1-2424
- M4-6-2412 (BLACK ON FLUORESCENT ORANGE)
- M3-4-2412
- M3-2-2412
- M6-1-2115 (BLACK ON FLUORESCENT ORANGE)
- M6-3-2115 (BLACK ON FLUORESCENT ORANGE)
- M6-2(R)-2115 (BLACK ON FLUORESCENT ORANGE)
- W5-2(R)-2115 (BLACK ON FLUORESCENT ORANGE)

- 1 ADJACENT TO THE EXIT "1/2 MILE AHEAD" SIGN
- 2 ADJACENT TO THE GREEN INTERSTATE EXIT SIGN

NOTES:

1. ALL SIGNS SHALL BE INSTALLED PER HIGHWAY STANDARD 720001, 720006, AND 720011. ALL SIGNS SHALL BE INSTALLED ON STEEL POSTS DRIVEN INTO THE GROUND.
2. ALL ALTERNATE ROUTE SIGNS AND CHANGEABLE MESSAGE SIGNS SHALL BE INSTALLED AT PROJECT STARTUP AND SHALL REMAIN UNTIL PROJECT COMPLETION. ALL SIGNS SHOWN SHALL BE NEW OR LIKE NEW CONDITION. THE COST TO INSTALL THESE SIGNS SHALL BE INCLUDED IN THE LUMP SUM PRICE FOR ALTERNATE ROUTE SIGNING.
3. ALL SIGN ASSEMBLIES SHALL BE INSTALLED ADJACENT TO EXISTING ROUTE MARKERS AND AS DIRECTED BY THE ENGINEER.

NOT TO SCALE



FILE NAME = D366998-sht-alt rte.dgn	USER NAME = brianheil	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ALTERNATE ROUTE			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 6000.0000' / in.	CHECKED -	REVISED -					80	(06-2) BR-3,4	BUREAU	133	39
Default	PLOT DATE = 7/30/2013	DATE -	REVISED -	SCALE:	SHEET 1 OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 66998				
ILLINOIS FED. AID PROJECT												