

SEEDING, MULCH, NUTRIENTS, SODDING											
LOCATION			SEEDING, CLASS 2A	SEEDING, CLASS 4	MULCH, METHOD 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	SODDING, SALT TOLERANT	SUPPLEMENTAL WATERING	
STATION +/- TO	STATION +/-	SIDE	ACRE	ACRE	ACRE	POUND	POUND	POUND	SQ YD	UNIT	
URBAN GRUNDY											
IL 47											
6027+00	TO 6045+51	LT	0.26	0.14	0.20	57	57	57	1731	26	
6027+00	TO 6045+51	RT	1.15	0.41	0.82	147	147	147	549	8	
6045+51	TO 6061+51	LT	0.29	0.39	0.21	75	75	75	1101	17	
6045+51	TO 6061+51	CL				21	21	21	1695	25	
6045+51	TO 6061+51	RT	1.06	0.68	0.94	163	163	163	524	8	
6061+51	TO 6098+48	LT	1.89	1.34	1.48	296	296	296	432	6	
6061+51	TO 6098+48	CL	0.69			95	95	95	2708	41	
6061+51	TO 6098+48	RT	2.64	0.53	2.19	290	290	290	411	6	
6098+48	TO 6151+62	LT	3.33	1.02	2.65	391	391	391			
6098+48	TO 6151+62	CL	2.20			198	198	198			
6098+48	TO 6151+62	RT	2.94	0.41	1.47	301	301	301			
6151+62	TO 6205+17	LT	3.45	1.27	2.61	425	425	425			
6151+62	TO 6205+17	CL	2.05			185	185	185			
6151+62	TO 6205+17	RT	4.36	2.08	4.26	579	579	579			
GRANVILLE RD.											
100+52	TO 107+21	LT	0.15	0.14	0.10	27	27	27	74	1	
100+52	TO 107+21	RT	0.19	0.12	0.15	29	29	29	91	1	
PROLOGIS PRKWY.											
1603+15	TO 1605+00	LT & RT	0.06			7	7	7	89	1	
NELSON RD.											
200+49	TO 209+00	LT	0.24	0.16	0.20	35	35	35			
200+49	TO 209+00	RT	0.31	0.10	0.19	37	37	37			
AIRPORT RD.											
300+00	TO 309+00	LT	0.22	0.06	0.16	25	25	25			
300+00	TO 309+00	RT	0.23	0.17	0.19	35	35	35			
MINOOKA RD.											
403+58	TO 408+59	LT	0.15	0.04	0.12	17	17	17			
403+58	TO 408+59	RT	0.17	0.04	0.13	19	19	19			
409+39	TO 416+53	LT	0.18	0.09	0.15	24	24	24			
409+39	TO 416+53	RT	0.22	0.14	0.18	33	33	33			
URBAN GRUNDY SUB-TOTAL			28.50	9.25	18.50	3511	3511	3511	9405	140	
RURAL GRUNDY											
IL 47											
6205+17	TO 6257+48	LT	3.81	2.09	2.91	531	531	531			
6205+17	TO 6257+48	CL	1.24			111	111	111			
6205+17	TO 6257+48	RT	4.25	3.86	6.14	729	729	729			
SHERRILL RD.											
500+88	TO 508+59	LT	0.37	0.06	0.23	38	38	38			
500+88	TO 508+59	RT	0.32	0.07	0.26	35	35	35			
509+39	TO 516+08	LT	0.46	0.08	0.12	48	48	48			
509+39	TO 516+08	RT	0.20	0.09	0.15	25	25	25			
RURAL GRUNDY SUB-TOTAL			10.75	6.25	9.75	1517	1517	1517			
RURAL KENDALL											
IL 47											
6257+48	TO 6277+00	LT	2.31	0.82	1.78	282	282	282			
6257+48	TO 6265+00	CL	0.05			4	4	4			
6257+48	TO 6265+00	RT	0.55	0.38	0.74	84	84	84			
SOUTHBOUND CONNECTOR											
10+00.00	TO 37+09.00	LT	0.59	0.18	0.52	69	69	69			
10+00.00	TO 37+09.00	RT	0.18			16	16	16			
NORTHBOUND CONNECTOR											
50+00.00	TO 65+52.00	RT	1.84	0.25	1.76	188	188	188			
RURAL KENDALL SUB-TOTAL			5.50	1.75	5.00	643	643	643			
TOTAL			44.75	17.25	33.25	5671	5671	5671	9405	140	
SEEDING NUTRIENTS RATE OF APPLICATION: 90 LBS/ACRE SODDING NUTRIENTS RATE OF APPLICATION: 60 LBS/ACRE											
SUPPLEMENTAL WATERING SHALL HAVE 5 APPLICATIONS AT A RATE OF 3 GAL / SY											
AREAS OF MULCH HAVE BEEN DEDUCTED FROM EROSION CONTROL BLANKET LOCATIONS.											

EXPLORATION TRENCH, 52" DEPTH				
STATION	TO	STATION	SIDE	LENGTH FOOT
URBAN GRUNDY				
IL 47				
6026+95.33	TO	6060+61.04	LT	3382
6028+99.94	TO	6044+60.00	RT	1565
6046+02.65	TO	6108+59.45	RT	6283
6062+23.43	TO	6063+25.00	LT	103
6067+00.00	TO	6097+86.12	LT	3086
6099+06.04	TO	6151+05.08	LT	5252
6152+01.03	TO	6204+14.54	LT	5253
6157+46.52	TO	6174+90.15	RT	1746
GRANVILLE RD.				
101+00.84	TO	105+48.89	LT	451
101+04.02	TO	105+25.00	RT	432
NELSON RD.				
200+00.00	TO	207+95.00	LT	799
200+00.00	TO	207+99.04	RT	807
AIRPORT RD.				
299+50.00	TO	308+00.00	RT	856
299+50.00	TO	308+65.00	LT	919
MINOOKA RD.				
402+49.96	TO	407+64.98	LT	519
402+50.01	TO	407+59.98	RT	511
410+42.13	TO	415+49.93	LT	511
410+61.97	TO	415+50.02	RT	493
URBAN GRUNDY SUB-TOTAL				32968
RURAL GRUNDY				
IL 47				
6205+14.61	TO	6256+86.28	LT	5204
SHERRILL RD.				
501+50.00	TO	507+60.00	RT	615
501+50.00	TO	507+65.00	LT	622
510+51.41	TO	515+75.00	RT	528
511+01.74	TO	515+75.00	LT	480
RURAL GRUNDY SUB-TOTAL				7449
RURAL KENDALL				
IL 47				
6258+06.34	TO	6292+00.14	LT	3404
RURAL KENDALL SUB-TOTAL				3404
TOTAL				43821

EROSION CONTROL BLANKET				
LOCATION				AREA
STATION +/- TO	STATION +/-	SIDE	SQ YD	
URBAN GRUNDY				
IL 47				
6028+48	TO 6045+51	LT	1034	
6028+48	TO 6045+51	RT	3604	
6045+51	TO 6061+51	LT	2289	
6045+51	TO 6061+51	RT	3909	
6061+51	TO 6098+48	LT	8418	
6061+51	TO 6098+48	CL	3327	
6061+51	TO 6098+48	RT	4767	
6098+48	TO 6151+62	LT	8328	
6098+49	TO 6151+63	CL	10656	
6098+48	TO 6151+62	RT	8123	
6151+62	TO 6205+17	LT	10330	
6151+63	TO 6205+18	CL	9941	
6151+62	TO 6205+17	RT	10910	
GRANVILLE RD				
100+52	TO 107+21	LT	833	
100+52	TO 107+21	RT	696	
NELSON RD.				
200+49	TO 208+48	LT	948	
200+49	TO 208+48	RT	1056	
AIRPORT RD.				
300+00	TO 308+95	LT	551	
300+00	TO 308+95	RT	945	
MINOOKA RD.				
403+58	TO 408+59	LT	328	
403+58	TO 408+59	RT	334	
409+39	TO 416+53	LT	608	
409+39	TO 416+53	RT	521	
URBAN GRUNDY SUB-TOTAL				92456
RURAL GRUNDY				
IL 47				
6205+17	TO 6257+48	LT	14560	
6205+17	TO 6257+48	CL	5995	
6205+17	TO 6257+48	RT	9294	
SHERRILL RD.				
500+88	TO 508+59	LT	870	
500+88	TO 508+59	RT	521	
509+39	TO 516+08	LT	671	
509+39	TO 516+08	RT	564	
RURAL GRUNDY SUB-TOTAL				32475
RURAL KENDALL				
IL 47				
6257+48	TO 6277+00	LT	6406	
6257+48	TO 6265+00	CL	236	
6257+48	TO 6265+00	RT	1293	
SOUTHBOUND CONNECTOR				
10+00.00	TO 37+09.00	LT	1427	
10+00.00	TO 37+09.00	RT	500	
NORTHBOUND CONNECTOR				
50+00.00	TO 65+52.00	RT	1763	
RURAL KENDALL SUB-TOTAL				11625
TOTAL				136556

RIP RAP				
LOCATION		STONE RIPRAP, CLASS A3	STONE RIPRAP, CLASS A4	FILTER FABRIC
STATION	SIDE	SQ YD	SQ YD	
URBAN GRUNDY				
6098+24.0	RT		102	102
6178+87.9	LT	26		26
URBAN GRUNDY		26	102	128
RURAL GRUNDY				
6248+00.0	RT		49	49
RURAL GRUNDY			49	49
TOTAL		26	151	177