STORM SEWER

STATION	OFFSET	TYPE	INLETS												MANHOLES													
			TYPE A	TYPE B	TYPE B	TYPE A	TYPE B	TYPE A	TYPE A	TYPE B	TYPE A	TYPE B	TYPE A	TYPE B	TYPE A, 4' DIA.					TYPE A, 5' DIA.				TYPE A, 6' DIA.		TYPE A, 7' DIA.		TYPE A, 8' DIA.
			TYPE 1 FRAME OPEN LID		TYPE 1 FRAME, CLOSED LID	TYPE 3 FRAME & GRATE		TYPE 4 FRAME & GRATE	TYPE 8 GRATE		TYPE 11 FRAME & GRATE		WITH MEDIAN INLET (604101)	WITH MEDIAN INLET (604106)	TYPE 1 FRAME OPEN LID	TYPE 1 FRAME, CLOSED LID	TYPE 3 FRAME & GRATE	TYPE 8 GRATE	TYPE 11 FRAME & GRATE	TYPE 1 FRAME, CLOSED LID	TYPE 1 FRAME, OPEN LID	TYPE 3 FRAME & GRATE	TYPE 11 FRAME & GRATE	TYPE 1 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 1 FRAME, CLOSED LID	AUTOMATIC FLAP GATE 15"	TYPE 1 FRAME, CLOSED LID
			EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
6184+80.00	54.00 LT.	INLET				1																						
		SS																										
6185+44.00	54.00 LT.	INLET				1																						
		SS																										
6184+98.00	C.L.	INLET								1																		
		SS																										
6184+57.60	54.00 RT.	M.H.															1											
		SS																										
6184+57.60	69.50 RT.	END SECTION																										
6184+67.60	54.00 RT.	INLET				1																						
		SS																										
LATERALS 6190+00.00 TO 6204+67.00																												
6190+00.00	C.L.	INLET	1																									
		SS																										
6190+00.00	79.30 RT.	END SECTION																										
6195+60.00	C.L.	INLET	1																									
		SS																										
6195+60.00	71.00 RT.	END SECTION																										
GRANVILLE ROAD																												
101+04.50	46.20 RT.	END SECTION																										
		SS																										
101+00.00	32.40 RT.	M.H.															1											
		SS																										
101+00.00	20.00 LT.	M.H.															1											
		SS																										
102+25.00	20.00 LT.	INLET						1																				
		SS																										
102+45.00	20.00 LT.	INLET				1																						
		SS																										
102+47.90	27.90 LT.	END SECTION																										
101+00.00	33.70 LT.	INLET							1																			
		SS																										
102+10.00	28.60 RT.	END SECTION																										
		SS																										
102+10.00	20.00 RT.	INLET				1																						
		SS																										
102+25.00	20.00 RT.	INLET				1																						
PROLOGIS PARKWAY																												
1605+05.00	34.65 LT.	INLET				1																						
		SS																										
1605+05.00	20.36 RT.	INLET				1																						
		SS																										
1605+11.90	46.33 RT.	END SECTION																										
AIRPORT ROAD																												
305+30.00	34.10 LT.	INLET												1														
		SS																										
306+00.00	20.00 LT.	M.H.															1											
		SS																										
306+00.00	26.00 RT.	M.H.													1													
		SS																										
307+50.00	37.10 RT.	M.H.													1													
		SS																										
306+00.00	38.70 RT.	INLET							1																			
		SS																										
307+57.00	36.00 LT.	INLET							1																			
		SS																										
307+65.00	20.00 LT.	INLET					1																					
		SS																										
URBAN GRUNDY SUB-TOTAL			5	6	2	145	80	1	35	12	3	7	6	1	6	31	20	3	2	11	1	3	1	7	1	15	2	5

SEE NEXT SHEET