

EXISTING FIELD TILE SYSTEM REPAIR ITEMS					
ITEM	UNIT	GRUNDY URBAN	GRUNDY RURAL	KENDALL RURAL	TOTAL
PIPE DRAINS 6"	FOOT	600	300	100	1000
PIPE DRAINS 8"	FOOT	600	300	100	1000
PIPE DRAINS 10"	FOOT	600	300	100	1000
PIPE DRAINS 12"	FOOT	600	300	100	1000
PIPE DRAINS 15"	FOOT	600	300	100	1000
PIPE DRAINS 18"	FOOT	600	300	100	1000
MISCELLANEOUS CONCRETE	CU YD	3.0	2.0	1.0	6.0
STORM SEWERS PROTECTED, CLASS A, 6"	FOOT	600	300	100	1000
STORM SEWERS PROTECTED, CLASS A, 8"	FOOT	600	300	100	1000
STORM SEWERS PROTECTED, CLASS A, 10"	FOOT	600	300	100	1000
STORM SEWERS PROTECTED, CLASS A, 12"	FOOT	600	300	100	1000
STORM SEWERS PROTECTED, CLASS A, 15"	FOOT	600	300	100	1000
STORM SEWERS PROTECTED, CLASS A, 18"	FOOT	600	300	100	1000
FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	12	6	2	20
FIELD TILE JUNCTION VAULTS, 3' DIA.	EACH	12	6	2	20
STORM SEWERS (SPECIAL), 6"	FOOT	800	500	200	1500
STORM SEWERS (SPECIAL), 8"	FOOT	800	500	200	1500
STORM SEWERS (SPECIAL), 10"	FOOT	800	500	200	1500
STORM SEWERS (SPECIAL), 12"	FOOT	800	500	200	1500
STORM SEWERS (SPECIAL), 15"	FOOT	800	500	200	1500
STORM SEWERS (SPECIAL), 18"	FOOT	800	500	200	1500

SEE SPECIAL PROVISIONS FOR THESE ITEMS AND DETAILS IN THE PLANS.

DELINEATORS			
LOCATION			DELINEATORS
STATION	TO	STATION	EACH
URBAN GRUNDY			
IL 47			
6029+00.00	TO	6045+51.00	19
6045+51.00	TO	6061+51.00	10
6061+51.00	TO	6098+47.71	22
6098+47.71	TO	6117+59.58	8
6119+20.42	TO	6151+62.25	16
6151+62.25	TO	6185+17.44	16
6185+17.44	TO	6205+16.97	10
URBAN GRUNDY SUB-TOTAL			101
RURAL GRUNDY			
IL 47			
6205+16.97	TO	6257+48.41	28
RURAL GRUNDY SUB-TOTAL			28
RURAL KENDALL			
IL 47			
6257+48.41	TO	6277+00.00	8
RURAL KENDALL SUB-TOTAL			8
TOTAL			137

NOTE: DELINEATORS TO BE PLACED IN ACCORDANCE WITH HIGHWAY STANDARD 635001, AT SEGMENTAL CONCRETE BLOCK WALLS, AND AT ALL BOX CULVERT ALONG THE ROADWAY.

SLOTTED DRAIN 15" WITH 1 3/4" SLOT					
STATION	SIDE	TO	STATION	SIDE	LENGTH
					FOOT
RURAL KENDALL					
IL 47					
6260+80.96	RT	TO	6265+00	CL	419.0
TOTAL					419

FURNISHING AND ERECTING RIGHT OF WAY MARKERS				FURNISHING AND ERECTING RIGHT OF WAY MARKERS			
STATION	SIDE	OFFSET	EACH	STATION	SIDE	OFFSET	EACH
URBAN GRUNDY				NELSON RD.			
IL 47				200+00.00	RT	24.75'	1
6026+95.33	LT	85.00'	1	200+00.00	LT	37.25'	1
6029+00.00	RT	77.55'	1	200+50.00	RT	50.00'	1
6029+50.00	RT	100.00'	1	200+50.00	LT	50.00'	1
6039+49.04	LT	85.00'	1	204+50.00	RT	50.00'	1
6039+49.11	LT	80.00'	1	204+50.00	LT	50.00'	1
6040+00.00	RT	100.00'	1	205+00.00	RT	60.00'	1
6040+15.00	LT	80.00'	1	205+00.00	LT	60.00'	1
6040+15.00	LT	70.00'	1	207+95.00	LT	60.00'	1
6041+00.00	RT	105.00'	1	299+50.00	LT	30.79'	1
6044+60.00	RT	105.00'	1	300+00.00	LT	50.00'	1
6046+02.65	RT	100.00'	1	305+00.00	LT	50.00'	1
6046+50.00	LT	70.00'	1	306+00.00	LT	40.00'	1
6047+00.00	LT	80.00'	1	308+65.00	LT	40.00'	1
6049+50.00	RT	100.00'	1	AIRPORT RD.			
6050+00.00	RT	110.00'	1	299+50.00	RT	25.76'	1
6054+00.00	LT	80.00'	1	300+00.00	RT	50.00'	1
6055+00.00	LT	85.00'	1	300+50.00	RT	55.00'	1
6060+61.05	LT	85.00'	1	304+50.00	RT	50.00'	1
6062+24.12	LT	90.00'	1	308+00.00	RT	55.00'	1
6063+25.00	LT	75.00'	1	MINOOKA RD.			
6067+00.00	LT	75.00'	1	402+50.00	RT	32.85'	1
6070+00.00	LT	100.00'	1	402+50.00	LT	22.15'	1
6073+00.00	RT	110.00'	1	403+50.00	RT	50.00'	1
6073+50.00	RT	85.00'	1	403+50.00	LT	50.00'	1
6097+00.00	RT	85.00'	1	407+60.00	RT	50.00'	1
6097+50.00	RT	100.00'	1	407+65.00	LT	50.00'	1
6097+86.12	LT	100.00'	1	410+42.13	LT	50.00'	1
6098+41.53	RT	100.00'	1	410+62.59	RT	60.00'	1
6099+20.00	LT	90.00'	1	411+00.00	RT	50.00'	1
6099+00.00	RT	100.00'	1	415+00.00	RT	50.00'	1
6099+50.00	RT	85.00'	1	415+00.00	LT	50.00'	1
6102+29.89	RT	85.00'	1	415+50.00	RT	28.26'	1
6102+29.67	RT	75.00'	1	415+50.00	LT	32.74'	1
6103+72.09	LT	90.00'	1	URBAN GRUNDY SUB-TOTAL 103			
6104+27.17	RT	75.00'	1	RURAL GRUNDY			
6108+59.45	RT	75.00'	1	IL 47			
6105+59.45	RT	75.00'	1	6205+40.00	LT	105.00'	1
6109+45.29	LT	90.00'	1	6224+00.00	LT	105.00'	1
6115+19.45	LT	90.00'	1	6228+00.00	LT	85.00'	1
6117+00.00	LT	120.00'	1	6244+00.00	LT	85.00'	1
6126+00.00	LT	120.00'	1	6247+00.00	LT	115.00'	1
6141+00.00	LT	85.00'	1	6256+75.00	LT	115.00'	1
6141+50.00	LT	80.00'	1	SHERRILL RD.			
6150+65.00	LT	80.00'	1	507+60.00	RT	60.00'	1
6152+25.00	LT	60.00'	1	506+00.00	RT	60.00'	1
6153+00.00	LT	60.00'	1	505+00.00	RT	55.00'	1
6153+25.00	LT	75.00'	1	502+00.00	RT	55.00'	1
6154+67.46	LT	75.00'	1	501+50.00	RT	32.57'	1
6154+67.46	LT	90.00'	1	501+50.00	LT	27.43'	1
6162+00.00	LT	90.00'	1	502+00.00	LT	55.00'	1
6162+00.00	RT	69.42'	1	505+00.00	LT	55.00'	1
6162+00.00	RT	46.52'	1	506+00.00	LT	60.00'	1
6162+00.00	RT	75.00'	1	507+65.00	LT	60.00'	1
6162+73.91	LT	100.00'	1	510+51.41	RT	60.00'	1
6162+73.91	RT	95.00'	1	511+00.00	RT	50.00'	1
6168+86.89	RT	95.00'	1	515+25.00	RT	50.00'	1
6172+00.00	LT	100.00'	1	515+25.00	LT	55.00'	1
6173+00.00	LT	110.00'	1	515+75.00	RT	31.11'	1
6174+90.77	RT	110.97'	1	515+75.00	LT	28.89'	1
6177+52.79	LT	110.00'	1	RURAL GRUNDY SUB-TOTAL 22			
6178+13.76	LT	125.00'	1	RURAL KENDALL			
6185+00.00	LT	125.00'	1	IL 47			
6186+00.00	LT	100.00'	1	6258+25.00	LT	115.00'	1
6190+00.00	LT	100.00'	1	6258+05.77	RT	200.79'	1
6191+00.00	LT	105.00'	1	RURAL KENDALL SUB-TOTAL 2			
6203+90.00	LT	105.00'	1	TOTAL 127			
GRANVILLE RD.				RURAL KENDALL			
IL 47				IL 47			
102+00.00	RT	50.00'	1	TOTAL 127			
105+00.00	RT	50.00'	1	IL 47			
105+00.00	LT	50.00'	1	IL 47			
105+50.00	RT	27.46'	1	IL 47			
105+50.00	LT	31.54'	1	IL 47			

FILE NAME =	USER NAME = bdecreene	DESIGNED - LDZ	REVISED -
W:\3195\66883 (South Section)\CADD Sheets\0366883-sht-schedule-49.dgn		DRAWN - SRH/RMD	REVISED -
	PLOT SCALE = 2.000' / in.	CHECKED - DJD	REVISED -
SHT.PLAN	PLOT DATE = 8/6/2013	DATE - 7/15/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL. RTE. 47
SCHEDULES OF QUANTITIES

SCALE: N/A SHEET 49 OF 55 SHEETS STA. N/A TO STA. N/A

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(110)R, BR & BR-1	GRUNDY	644	88
CONTRACT NO. 66883			ILLINOIS FED. AID PROJECT	