

TRENCH BACKFILL		
LOCATION	STATE	CITY
	CU YD	CU YD
6029+05 LT	14.6	----
6029+94 LT	17.4	----
6032+60 LT	8.0	----
6033+95 LT	13.9	----
6035+20 LT	13.9	----
6036+60 LT	16.0	----
6036+43.86, 62.93' LT TO 6036+43.90, 55.95' LT	2.6	----
6038+00 LT	21.2	----
6040+95 LT	9.4	----
6044+92.82, 66.45' RT TO 6044+98.74, 66.43' RT	6.1	----
6045+20 LT	23.1	----
6050+65 RT	3.2	----
6052+00 RT	3.3	----
6053+35 RT	3.8	----
6054+70 RT	3.8	----
6055+90 RT	4.9	----
6056+90 RT	5.4	----
6058+00 RT	2.6	----
6059+00 RT	6.6	----
6060+40 RT	7.5	----
6061+80 RT	13.9	----
6062+45 RT	16.0	----
6064+75 RT	17.4	----
6065+90 RT	18.2	----
6072+48.08, 104.85' RT TO 6072+79.34, 104.85' RT	29.5	----
6075+36.26, 80.0' RT TO 6075+64.35, 80.0' RT	24.0	----
6082+42.93, 80.0' RT TO 6082+70.93, 80.0' RT	9.5	----
6178+76.40, 97.87' RT TO 6179+04.72, 97.15' RT	17.7	----
10+88.53 TO 11+88.53, TL	72.8	----
TOTAL	406	0

DOMESTIC WATER SERVICE BOXES		
LOCATION	STATE	CITY
	EACH	EACH
6034+57.98 (80.5 LT)	1	----
6036+41.74 (81.99 LT)	1	----
AIRPORT ROAD 308+20.87 (33.31 LT)	1	----
TOTAL	3	0

DOMESTIC METER VAULTS TO BE REMOVED		
LOCATION	STATE	CITY
	EACH	EACH
AIRPORT ROAD 308+98 LT	1	----
TOTAL	1	0

DOMESTIC WATER SERVICE BOXES TO BE REMOVED		
LOCATION	STATE	CITY
	EACH	EACH
6034+48 LT	1	----
6036+39 LT	1	----
AIRPORT ROAD 309+10 LT	1	----
TOTAL	3	0

WATER SERVICE LINE 1"		
LOCATION	STATE	CITY
	FOOT	FOOT
6034+48.56 (82.0 LT) to 6034+57.76 (57.03 LT)	35	----
6036+38.74 (81.97 LT) to 6036+43.90 (55.95 LT)	31	----
AIRPORT ROAD 308+20.62 (17.55 LT) to 308+20.87 (33.31 LT)	16	----
TOTAL	82	0

STEEL CASINGS 18"	
LOCATION	
STA 6204+22	90' LT TO 110' RT LENGTH 200'

PLUG ENDS FOR FUTURE CROSSING
NO CONNECTIONS TO MAIN
100% STATE - URBAN