

SI = SPECIALTY ITEM

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	FED 80% STATE 20%	FED 80% STATE 20%	FED 80% STATE 20%	FED 80% STATE 20%	FED 80% STATE 20%	CITY 100%	CITY 100%	FED 80% STATE 20%	CITY 100%
				ROADWAY	ROADWAY	ROADWAY	BRIDGE	BRIDGE	HIGHWAY LIGHTING	TRAFFIC SIGNALS	TRAFFIC SIGNALS	CITY
				0003	0003	0003	0010	0010	0021	0021	0021	0043
				URBAN GRUNDY	RURAL GRUNDY	RURAL KENDALL	SN 032-0122	SN 032-0123	URBAN	PROLOGIS	GRANVILLE	URBAN
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	2917	2812	105							
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1710	1492	218							
20101000	TEMPORARY FENCE	FOOT	3002	3002								
20200100	EARTH EXCAVATION	CU YD	157150	103490	34733	18927						
20200200	ROCK EXCAVATION	CU YD	570			570						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	86043	58718	18141	9184						
20300100	CHANNEL EXCAVATION	CU YD	2860	27	171		2074	588				
20400800	FURNISHED EXCAVATION	CU YD	279238	186953	68908	23377						
20700220	POROUS GRANULAR EMBANKMENT	CU YD	289	217	72							
20800150	TRENCH BACKFILL	CU YD	3352	2505	818	29						
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	40469	38415	2054							
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	30318	19354	7860	3104						
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	43821	32968	7449	3404						
25000210	SEEDING, CLASS 2A	ACRE	44.75	28.50	10.75	5.50						

14

FILE NAME = W:\3195\66883\South Section\CADD Sheets	USER NAME = bdegreene	DESIGNED - LDZ	REVISED -
	D366803-shr-500-1.dgn	DRAWN - SRH/RMD	REVISED -
	PLOT SCALE = 100.0000 1/ in.	CHECKED - DJD	REVISED -
SHT_PLAN	PLOT DATE = 8/6/2013	DATE - 7/15/2013	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL RTE. 47  
SUMMARY OF QUANTITIES

SCALE: N/A SHEET 1 OF 30 SHEETS STA. N/A TO STA. N/A

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(110)R. BR & BR-1	GRUNDY	644	4
CONTRACT NO. 66883			[ILLINOIS] FED. AID PROJECT	