



DIRKSEN PARKWAY & RIDGE AVENUE - TRAFFIC SIGNAL QUANTITIES

QUANTITY	UNIT	ITEM
465	METER	UNDERGROUND CONDUIT, PVC, 40MM DIA.
4	EACH	GULFBOX JUNCTION, COMPOSITE CONCRETE
1	EACH	TRANSCEIVER - FIBER OPTIC
506.2	METER	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F
167.1	METER	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14, 2C
202.4	METER	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14, 3C
25	METER	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14, 5C
600.4	FOOT	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 18 3C
132.6	METER	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6, 1C
1	EACH	DRILL EXISTING HANDHOLE
4	EACH	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER
1	EACH	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER
2	EACH	TRAFFIC SIGNAL BACKPLATE
6	EACH	PEDESTRIAN PUSH-BUTTON
2	EACH	REBUILD EXISTING SIGNAL HEAD
1	EACH	MODIFY EXISTING CONTROLLER
465.2	METER	REMOVE ELECTRIC CABLE FROM CONDUIT
1	EACH	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT
1	EACH	VIDEO VEHICLE DETECTION SYSTEM

USER NAME = sparksgw PLOT SCALE = 12.692 m / in. PLOT DATE = Jun-28-2013 10:52:32AM	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PROPOSED TRAFFIC SIGNAL PLAN DIRKSEN PKWY. & RIDGE AVE.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN -	REVISED -			668	28R-1	SANGAMON	354	157
	CHECKED -	REVISED -			CONTRACT NO. 72501				
	DATE -	REVISED -			ILLINOIS FED. AID PROJECT				
				SCALE:	SHEET	OF	SHEETS	STA.	TO STA.

FILE NAME = c:\pw_work\pwsdot\sparksgw\d0351999\0672501-sht-T55.dgn