

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
668	2BR-1	SANGAMON	354	8

CONTRACT NO. 72501

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				80% FEDERAL 20% STATE	80% FED 20% ST	80% FED 20% ST	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 15% STATE 5% CITY	80% FEDERAL 20% CITY	80% STATE 20% TOWNSHIP	
				ROADWAY/ STORM SEWER	SIDEWALK CITY	CAPITAL TOWNSHIP SIDEWALK	TRAFFIC SIGNALS ELM	TRAFFIC SIGNALS RIDGE	BIKE LANES CITY	BIKE LANES CAPITAL TOWNSHIP	
				0003 URBAN	0021			0028			
		URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN			
81500120	GULFBOX JUNCTION, COMPOSITE CONCRETE	EACH	15				11	4			
*85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1				1				
*86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	1				1				
*86400100	TRANSCEIVER - FIBER OPTIC	EACH	2				1	1			
*87301265	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 9C	FOOT	293.0				293.0				
*87301275	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 12C	FOOT	310.0				310.0				
*87301290	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 18 3C	FOOT	1301.5				701.0	600.5			
*87600100	PEDESTRIAN PUSH-BUTTON POST, TYPE I	EACH	4					4			
*87600200	PEDESTRIAN PUSH-BUTTON POST, TYPE II	EACH	5				4	1			
87900200	DRILL EXISTING HANDHOLE	EACH	2				1	1			
*88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4				4				
*88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4				4				
*88040120	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2				2				
*88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2				2				

14

*SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES F.A.P. ROUTE 668 (DIRKSEN PARKWAY) SECTION 2BR-1 SANGAMON COUNTY SCALE: NONE DATE: 06/2013

DRAWN BY: GE
CHECKED BY: FML