

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
668	28R-1	SANGAMON	354	16

CONTRACT NO. 72501

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				80% FEDERAL 20% STATE	80% FED 20% ST	80% FED 20% ST	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 15% STATE 5% CITY	80% FEDERAL 20% CITY	80% STATE 20% TOWNSHIP	
				ROADWAY/ STORM SEWER	SIDEWALK CITY	CAPITAL TOWNSHIP SIDEWALK	TRAFFIC SIGNALS ELM	TRAFFIC SIGNALS RIDGE	BIKE LANES CITY	BIKE LANES CAPITAL TOWNSHIP	
				0003 URBAN	0021 URBAN			0028 URBAN			
* M8101358	UNDERGROUND CONDUIT, PVC, 40MM DIA.	METER	1788.4				1323.4	465.0			
* M8101362	UNDERGROUND CONDUIT, PVC, 50MM DIA.	METER	13.4				13.4				
* M8101366	UNDERGROUND CONDUIT, PVC, 65MM DIA.	METER	6.5				6.5				
* M8101370	UNDERGROUND CONDUIT, PVC, 75MM DIA.	METER	48.0				48				
* M8101374	UNDERGROUND CONDUIT, PVC, 90MM DIA.	METER	34.3				34.3				
* M8731210	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	METER	167.1					167.1			
* M8731220	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	METER	338.9				136.5	202.4			
* M8731240	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	METER	617.7				592.7	25			
* M8731250	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	METER	119.3				119.3				
* M8731800	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	METER	8.3				8.3				
* M8731850	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR NO. 6 1C	METER	284.2				151.6	132.6			
M8750700	TRAFFIC SIGNAL POST, ALUMINUM 4.55 METER	EACH	2				2				
M8750710	TRAFFIC SIGNAL POST, ALUMINUM 4.85 METER	EACH	2				2				
M8770040	STEEL MAST ARM ASSEMBLY AND POLE, 8.53 METER	EACH	1				1				

*SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.P. ROUTE 668 (DIRKSEN PARKWAY)
SECTION 28R-1
SANGAMON COUNTY
SCALE: NONE
DATE: 06/2013
DRAWN BY: GE
CHECKED BY: FML