

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE BRIDGE
				0004	0004	0040
				ADAMS CO.	PIKE CO.	PIKE CO.
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	234		234	
44000100	PAVEMENT REMOVAL	SQ YD	626	140	486	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	126		126	
44004250	PAVED SHOULDER REMOVAL	SQ YD	1846		1846	
44200140	PAVEMENT PATCHING, TYPE I, 12 INCH	SQ YD	482	44	438	
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	219	16	203	
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	90	8	82	
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	366	15	351	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	23034	2254	20780	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	686	75	611	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1656	30	1626	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	120		120	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1	

FILE NAME *	USER NAME *	DESIGNED -	REVISED -
Z:\HA\2010\10-2013.12-16 Pike Co to IL	mike1	PSBA	
		DRAWN -	REVISED -
		NEL	
		CHECKED -	REVISED -
		DBS	
		DATE -	REVISED -
		08/15/2013	

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET 4 OF 10 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1597	14 (W, RS-7)	ADAMS/PIKE	152	6
ILLINOIS FED. AID PROJECT			CONTRACT NO. 72781	