

8187 018 2

SUMMARY OF QUANTITIES				CONSTRUCTION CODE				
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FEDERAL				
				20% STATE				
				SN 093-0024				
				0011				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12				
67100100	MOBILIZATION	L SUM	1	1				
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	100	100				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3,972	3,972				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	33	33				
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3,972	3,972				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	13	13				
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8				
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3				
* X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.5	0.5				
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1,176	1,176				
X5860110	GRANULAR BACKFILL FOR STRUCTURES	CU YD	85	85				
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	3	3				
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	129	129				

* SPECIALTY ITEM



JOB - 2223.5
 FILE NAME - 0774217-sh1-soq.dgn
 PLOT SCALE - 20.0000' / in.
 PLOT DATE - 7/25/2013

DESIGNED - NAK
 DRAWN - TJD
 CHECKED - NAK
 DATE - 4/8/2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

S&B	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
RTE.	(12A)B-1	WABASH	52	7
IB				CONTRACT NO. 74217
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		