

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
				80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE BRIDGE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0011
				ROADWAY	S. N. 076-0032
20200100	EARTH EXCAVATION	CU YD	101	101	
20400800	FURNISHED EXCAVATION	CU YD	107	107	
⊗ 25000210	SEEDING, CLASS 2A	ACRE	0.26	0.26	
⊗ 25000350	SEEDING, CLASS 7	ACRE	0.26	0.26	
⊗ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	24	24	
⊗ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	24	24	
⊗ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	24	24	
⊗ 25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.6	0.6	
⊗ 25100115	MULCH, METHOD 2	ACRE	0.26	0.26	
⊗ 25100630	EROSION CONTROL BLANKET	SO YD	1269	1269	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	60	60	
28000400	PERIMETER EROSION BARRIER	FOOT	1263	1263	
28100109	STONE RIPRAP, CLASS A5	SO YD	370		370
28200200	FILTER FABRIC	SO YD	370		370

⊗ SPECIALTY ITEM



USER NAME: HAS  
 ESCA PROJECT NO. 98812  
 PLOT SCALE: 0.3167" = 1' 0"  
 PLOT DATE: 8-2-2013

DESIGNED: JWS  
 DRAWN: HAS  
 CHECKED: RDP  
 DATE: 03/13

REVISED: -  
 REVISED: -  
 REVISED: -  
 REVISED: -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 6 SHEETS STA. TO STA.

F.A.P. RTE. 885	SECTION 112B-1	COUNTY POPE	TOTAL SHEETS 56	SHEET NO. 3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT AID			CONTRACT NO. 78230	