

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
				80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE BRIDGE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0011
				ROADWAY	S. N. 076-0032
50201102	COFFERDAM (TYPE 1) (LOCATION - 2)	EACH	1		1
50300225	CONCRETE STRUCTURES	CU YD	114.7		114.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	321.7		321.7
50300260	BRIDGE DECK GROOVING	SO YD	533		533
50300300	PROTECTIVE COAT	SO YD	728	46	682
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	84220		84220
50800515	BAR SPLICERS	EACH	459		459
51201900	FURNISHING STEEL PILES HP14x89	FOOT	1860		1860
51202305	DRIVING PILES	FOOT	1860		1860
51203900	TEST PILE STEEL HP14x89	EACH	2		2
51500100	NAME PLATES	EACH	1		1
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	44		44
⊕ 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	125	125	
⊕ 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	

⊕ SPECIALTY ITEM



GROUP TITLE - 885
 ESCA PROJECT NO. 988.12
 PLOT SCALE - 1/8" = 1' - 0"
 PLOT DATE - 05/20/13 10:02:05 AM

DESIGNED - JMS
 DRAWN - HAS
 CHECKED - RDP
 DATE - 05/13

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE SHEET NO. 3 OF 6 SHEETS STA. TO STA.

F.A. P. RTE. 885	SECTION 112B-1	COUNTY POPE	TOTAL SHEETS 56	SHEET NO. 5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT AID			CONTRACT NO. 78230	