WITH PRECAST END SECTION BOX CULVERT TABULATION CONCRETE REMOVAL INDICATES CONCRETE HEADWALL REMOVAL CU. YD. (m³) SPAN x RISE (25) (EST.) MIN. 2' × 2' (600 × 600) 0.26 (0.20) 2-#5E (#15M) $3' \times 2' (900 \times 600)$ 0.30 (0.23) S BARS 3' × 3' (900 × 900) 0.34 (0.26) 4' × 2' (1200 × 600) 0.36 (0.28) ¾" (20) Ø ANCHOR BOLTS 4' × 3' (1200 × 900) 0.39 (0.30) @ 18" (450) CENTERS

2" (50) CL

(TYP.)

THICKNESS (T) TO BE SAME AS

BOX CULVERT END SECTION OR

PROPOSED REINFORCED CONCRETE

CLASS SI CONC. EXPANSION BOLTS (EACH) 10 10 4' × 4' (1200 × 1200) 0.43 (0.33) 12 5' × 2' (1500 × 600) 0.41 (0.31) 12 12 5' x 3' (1500 x 900) 0.45 (0.34) 5' × 4' (1500 × 1200) 0.49 (0.37) 14 6' × 2' (1800 × 600) 0.47 (0.36) 14

0.51 (0.39)

0.54 (0.41)

14

16

BOX CULVERT EXTENSION

SHEET NO. OF SHEETS STA.

6' × 3' (1800 × 900)

2-#5E (#15M) S BARS

(TYPICAL)

6' × 4' (1800 × 1200)

SCALE:

GENERAL NOTES

- 1. ANCHOR BOLTS, MEETING THE REQUIREMENTS OF ARTICLE 1006.09 OF THE STANDARD SPECIFICATIONS, SHALL EXTEND A MINIMUM OF 9" (225 mm) INTO THE NEW CONCRETE.
- 2. REINFORCEMENT BARS SHALL MEET THE REQUIREMENTS OF ARTICLE 1006.10 OF THE STANDARD SPECIFICATIONS.
- 3. CLASS SI CONCRETE SHALL BE USED THROUGHOUT.
- 4. THE PRECAST END SECTION WILL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR BOX CULVERT END SECTIONS OF THE CULVERT NUMBER SPECIFIED WHICH PRICE SHALL INCLUDE THE CONCRETE COLLAR, ANCHOR BOLTS, REINFORCEMENT AND TOEWALL IF ANY.
- 5. ANY PRECAST BOX CULVERT BARREL SECTIONS PLACED AS PART OF THE EXTENSION WILL BE IN ACCORDANCE WITH APPLICABLE PORTIONS OF SECTION 540 OF THE SPECIFICATIONS EXCEPT THAT END SECTIONS WILL BE PAID FOR AS STATED ABOVE.

WITH PRECAST BOX CULVERT


¾" (20) Ø ANCHOR

BOLTS (TYPICAL)

2" (50) CL. 2

END VIEW

(TYP.)



DRAWN

DATE

CHECKED

BOTH FACES

TOP OF HEADWALL

EXISTING BOX CULVERT

(300)

TO BE REMOVED 12" (300)

EXTENSION.

REVISED

REVISED

REVISED

BELOW FINISHED SLOPE

(TYPICAL ALL FOUR SIDES)

PROPOSED

EXTENSION

PROPOSED

EXTENSION

TOEWALL

c:\pw_work\PWIDOT\CRAIGRE\dØ101509\540

PLOT DATE = 1/7/2010

PLAN VIEW

2-#5E (#15M) S BARS

SECTION A-A

GENERAL NOTES

- 1. THIS WORK SHALL BE IN ACCORDANCE WITH THE APPLICABLE PORTIONS OF SECTIONS 503 AND 540 OF THE STANDARD SPECIFICATIONS, EXCEPT THAT WHEN PRECAST END SECTIONS ARE USED, THE CONCRETE COLLAR, EXPANSION BOLTS, AND REINFORCEMENT BARS SHOWN ON THIS DETAIL SHALL BE INCLUDED IN THE PAY ITEM FOR BOX CULVERT END SECTIONS.
- 2. WHEN CAST-IN-PLACE END SECTIONS ARE USED, THE VARIOUS ITEMS FOR CONCRETE BOX CULVERTS, REINFORCEMENT BARS, AND EXPANSION BOLTS WILL BE COMPUTED AND INCLUDED IN THE PLAN QUANTITIES FOR THESE PAY ITEMS.

Note: All dimensions are in INCHES (millimeters) unless otherwise shown.

DISTRICT 5 DETAIL NO. 5400AAAA

	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			CONTRACT	NO.	
TO STA.	EED B	DAD DIST NO. THE INDIS FED. AT	D PROJECT		

STATE OF ILLINOIS					
DEPARTMENT OF	TRANSPORTATION				