

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

| F.A.I. RTE | SECTION                   | COUNTY    | TOTAL SHEETS       | SHEET NO. |
|------------|---------------------------|-----------|--------------------|-----------|
| 74         | D5 BRIDGE PAINTING 2020-1 | VERMILION | 52                 | 1         |
| ILLINOIS   |                           |           | CONTRACT NO. 70E06 |           |

FOR INDEX OF SHEETS, SEE SHEET NO. 2

FOR SUMMARY OF QUANTITIES, SEE SHEET NO. 7

PROPOSED  
HIGHWAY PLANS

F.A.I. ROUTE 74 (I-74)  
SECTION D5 BRIDGE PAINTING 2020-1  
PROJECT NHPP-3YFN(792)  
BRIDGE PAINTING  
VERMILION COUNTY


C-95-050-19

CURRENT ADT

| LOC. #1 & #2           | LOC. #3 & #4          | LOC. #5 & #6         |
|------------------------|-----------------------|----------------------|
| "L" STREET 1350 (2014) | LYNCH RD. 3550 (2018) | CR2100E 125 (2014)   |
| I-74(EB) 12300 (2019)  | I-74(WB) 9400 (2019)  | I-74(WB) 9400 (2019) |
| I-74(WB) 11800 (2019)  | I-74(EB) 9500 (2019)  | I-74(EB) 9500 (2019) |

TRAFFIC DATA LOCATIONS

- LOC. #1 = S.N. 092-0008 - FAI 74(EB) OVER "L" STREET IN TILTON  
LOC. #2 = S.N. 092-0009 - FAI 74(WB) OVER "L" STREET IN TILTON  
LOC. #3 = S.N. 092-0025 - FAI 74 (WB) OVER LYNCH ROAD IN DANVILLE  
LOC. #4 = S.N. 092-0026 - FAI 74 (EB) OVER LYNCH ROAD IN DANVILLE  
LOC. #5 = S.N. 092-0023 - FAI 74 (WB) OVER CR2100E AND CSX RR IN DANVILLE  
LOC. #6 = S.N. 092-0024 - FAI 74 (EB) OVER CR2100E AND CSX RR IN DANVILLE



FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD  
ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT  
CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS  
ON REDUCED PLANS THE ABOVE SCALES MAY BE USED.

J.U.L.I.E.  
JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS  
1-800-892-0123  
OR 811 TOWNSHIP: DANVILLE

PROJECT ENGINEER JASON STULTS  
SQUAD LEADER RYAN CARROLL  
PHONE NUMBER (217) 465-4181

CONTRACT NO. 70E06



FOR LOCATION MAP, SEE SHEET 3

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUBMITTED August 14, 2019  
[Signature]  
REGIONAL ENGINEER

OCT 4 2019  
[Signature]  
ENGINEER OF DESIGN AND ENVIRONMENT

OCT 4 2019  
[Signature]  
DIRECTOR OF HIGHWAYS PROJECT IMPLEMENTATION

PRINTED BY THE AUTHORITY  
OF THE STATE OF ILLINOIS

## INDEX OF SHEETS

| <u>SHEET NO.</u> | <u>DESCRIPTION</u>                                           |
|------------------|--------------------------------------------------------------|
| 1                | COVER SHEET                                                  |
| 2                | INDEX OF SHEETS, HIGHWAY STANDARDS, & GENERAL NOTES          |
| 3                | LOCATION MAP                                                 |
| 4                | DESCRIPTION OF WORK LOCATIONS #1 & #2                        |
| 5                | DESCRIPTION OF WORK LOCATIONS #3 & #4                        |
| 6                | DESCRIPTION OF WORK LOCATIONS #5 & #6                        |
| 6                | RAILROAD GENERAL NOTES                                       |
| 7-9              | SUMMARY OF QUANTITIES                                        |
| 10-11            | TRAFFIC CONTROL PLAN - LOCATIONS #1 & #2 - I-74 & "L" STREET |
| 12-15            | TRAFFIC CONTROL PLAN - LOCATIONS #3 & #4 - I-74 & LYNCH ROAD |
| 16               | CONCRETE MEDIAN REMOVAL/CONCRETE MEDIAN, TYPE SM (DOWELLED)  |
| 17-31            | STRUCTURE DETAILS FOR LOCATIONS #1 & #2                      |
| 32-41            | STRUCTURE DETAILS FOR LOCATIONS #3 & #4                      |
| 42-51            | STRUCTURE DETAILS FOR LOCATIONS #5 & #6                      |
| 52               | DETAILS FOR TEMPORARY RUMBLE STRIPS (SPECIAL)                |

## HIGHWAY STANDARDS

| <u>STANDARD NO.</u> | <u>DESCRIPTION</u>                                                             |
|---------------------|--------------------------------------------------------------------------------|
| 000001-07           | STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS                                   |
| 701001-02           | OFF-ROAD OPERATIONS, 2L, 2W, MORE THAN 15' (4.5 M) AWAY                        |
| 701006-05           | OFF-ROAD OPERATIONS, 2L, 2W, 15' (4.5 M) TO 24" (600 MM) FROM PAVEMENT EDGE    |
| 701101-05           | OFF-ROAD OPERATIONS, MULTILANE, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE |
| 701106-02           | OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 15' (4.5 M) AWAY                     |
| 701316-12           | LANE CLOSURE, 2L, 2W, BRIDGE REPAIR FOR SPEEDS > 45 MPH                        |
| 701400-09           | APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY                                   |
| 701402-12           | LANE CLOSURE, FREEWAY/EXPRESSWAY, WITH BARRIER                                 |
| 701601-09           | URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NON-TRAVERSABLE MEDIAN            |
| 701901-08           | TRAFFIC CONTROL DEVICES                                                        |

## GENERAL NOTES

G.N.-100  
ENGLISH UNITS OF MEASURE SHALL GOVERN OVER AND SUPERSEDE ANY METRIC  
UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR  
INFORMATION ONLY.

G.N.-100A  
ELECTRONIC FILES AND/OR ELECTRONIC SURVEY INFORMATION  
INCLUDING CADD FILES WILL NOT BE AVAILABLE TO THE CONTRACTOR.

GN 105.07C  
EXISTING STATE-OWNED AND MAINTAINED UNDERGROUND UTILITY FACILITIES EXIST WITHIN THE ROW. THE DEPARTMENT IS NOT A MEMBER OF JULIE AND DOES NOT LOCATE IT'S OWN FACILITIES. THE CONTRACTOR SHALL BE RESPONSIBLE AT THEIR OWN EXPENSE FOR SECURING AN APPROVED LOCATING FIRM TO LOCATE ALL EXISTING IDOT UNDERGROUND FACILITIES PRIOR TO COMMENCING ANY EXCAVATION, PER THE REQUIREMENTS OF ARTICLE 803 OF THE STANDARD SPECIFICATIONS. UTILITY LOCATES MAY ALSO BE REQUIRED OUTSIDE THE PROJECT LIMITS, SUCH AS FOR TRAFFIC CONTROL SIGNING AND OTHER ITEMS. THE CONTRACTOR MAY OBTAIN, ON REQUEST, PLANS OF EXISTING ELECTRICAL FACILITIES FROM THE DEPARTMENT. FOR FURTHER INFORMATION, THE CONTRACTOR MAY CONTACT THE DISTRICT TRAFFIC OPERATIONS ENGINEER, GARY SIMS, AT 217-251-4859.

THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR LOCATING AND PROVIDING PROTECTION FOR FACILITIES DURING ALL PHASES OF CONSTRUCTION. IF, AT ANY TIME, THE FACILITIES ARE DAMAGED, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE DEPARTMENT AND MAKE ALL NECESSARY ARRANGEMENTS FOR REPAIR TO THE SATISFACTION OF THE ENGINEER. THIS WORK SHALL BE INCLUDED IN THE CONTRACT BID PRICE AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

G.N.-107.12  
THE NAME, ADDRESS AND TELEPHONE NUMBER OF THE LOCAL RAILROAD  
CONTACT IS:

Ms. Amanda DeCesare  
CSX Transportation  
3131A Spring Grove Avenue  
Cincinnati, OH 45225  
(513) 853-1221

SPECIAL ATTENTION IS CALLED TO ARTICLE 107.12 REGARDING RAILROAD  
FLAGGERS. THE NAME, ADDRESS AND TELEPHONE NUMBER OF THE  
RAILROAD CONTACT PERSON FOR FLAGGERS IS:

Mr. Ben Ewing  
Roadmaster  
CSX Transportation  
564 CSX Lane  
Danville, IL 61834  
(217) 722-7993

G.N.-501A  
THE EXISTING STRUCTURAL STEEL COATING CONTAINS LEAD. THE CONTRACTOR SHALL FOLLOW THE GUIDE BRIDGE SPECIAL PROVISIONS FOR "CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES" TO DEAL WITH THE PRESENCE OF LEAD ON THIS PROJECT.

G.N.-506 (SPL.)  
ALL FINAL SURFACES OF THE BEAMS SHALL BE PAINTED GRAY (MUNSELL COLOR STANDARD - 5B 7/1) EXCEPT THE EXTERIOR SURFACES OF THE EXTERIOR BEAMS WHICH SHALL BE PAINTED WITH EITHER INTERSTATE GREEN (MUNSELL COLOR STANDARD 7.5G 4/8) OR REDDISH BROWN (MUNSELL COLOR STANDARD 2.5YR 3/4) AS SPECIFIED UNDER THE DESCRIPTION FOR EACH STRUCTURE.

ONLY STRUCTURAL STEEL AND OTHER DESIGNATED SURFACES SHALL BE PAINTED. ALL OTHER SURFACES SHALL BE PROTECTED FROM CONTRACTORS BLASTING AND PAINTING OPERATIONS. ANY AREAS DAMAGED BY BLASTING OR OVERSPRAY WILL BE REMOVED OR REPAIRED AT THE CONTRACTOR'S EXPENSE AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

CARE SHALL BE TAKEN NOT TO DAMAGE RUBBER BEARING OR JOINT COMPONENTS DURING BLASTING AND CLEANING OPERATIONS. ANY DAMAGE TO THESE COMPONENTS SHALL BE REPAIRED AT CONTRACTORS EXPENSE.

THE SSPC-QP1 AND QP2 PAINTING CONTRACTOR CERTIFICATIONS WILL BE REQUIRED FOR THIS CONTRACT.

ALL TRASH AND PAINTING DEBRIS, EXCLUDING WASTE BARRELS OR ROLL-OFF DUMPSTERS, SHALL BE REMOVED BEFORE BEGINNING WORK AT ANOTHER LOCATION.

2 YEAR PAINT WARRANTY REQUIRED FOR ALL STRUCTURES

NO COMMITMENTS


|             |                             |            |           |                                                   |                                                        |  |         |      |        |                    |         |           |              |           |  |
|-------------|-----------------------------|------------|-----------|---------------------------------------------------|--------------------------------------------------------|--|---------|------|--------|--------------------|---------|-----------|--------------|-----------|--|
| FILE NUMBER | USER NAME = dawnskb         | DESIGNED - | REVISED - | STATE OF ILLINOIS<br>DEPARTMENT OF TRANSPORTATION | INDEX OF SHEETS, HIGHWAY STANDARDS,<br>& GENERAL NOTES |  |         |      |        | F.A.I. RTE.        | SECTION | COUNTY    | TOTAL SHEETS | SHEET NO. |  |
|             |                             | DRAWN -    | REVISED - |                                                   |                                                        |  |         |      |        | 74                 | *       | VERMILION | 52           | 2         |  |
|             | PLOT SCALE = 40,0000' / in. | CHECKED -  | REVISED - |                                                   | * D5 BRIDGE PAINTING 2020-1                            |  |         |      |        | CONTRACT NO. 70E06 |         |           |              |           |  |
|             | PLOT DATE = 8/15/2019       | DATE -     | REVISED - |                                                   | SCALE:                                                 |  | SHEET 1 | OF 1 | SHEETS | STA.               |         | TO STA.   |              |           |  |
|             |                             |            |           |                                                   |                                                        |  |         |      |        |                    |         |           |              |           |  |
|             |                             |            |           |                                                   |                                                        |  |         |      |        |                    |         |           |              |           |  |



LOCATION #1, #2, #3, #4, #5, AND #6

- #1 – 092-0008 (EB)
- #2 – 092-0009 (WB)
- #3 – 092-0025 (WB)
- #4 – 092-0026 (EB)
- #5 – 092-0023 (WB)
- #6 – 092-0024 (EB)

LOCATION #3 & #4  
S.N. 092-0025 (WB)  
S.N. 092-0026 (EB)  
I-74 OVER LYNCH  
ST. IN DANVILLE  
I-74 M.P. 219.7



LOCATION #1 & #2  
S.N. 092-0008 (EB)  
S.N. 092-0009 (WB)  
I-74 OVER "L" ST.  
TILTON  
I-74 M.P. 213.4

LOCATION #5 & #6  
S.N. 092-0023 (WB)  
S.N. 092-0024 (EB)  
I-74 OVER CR 2100E  
AND CSX R.R. IN DANVILLE  
I-74 M.P. 219.5

MODEL: SHOTGUN.MXD  
FILE: 700606.dwg  
PROJECT: 700606  
CADD: 700606.dwg  
DESIGN: 700606.dwg  
OFFICE: 700606  
DATE: 8/15/2019

|            |                   |            |           |
|------------|-------------------|------------|-----------|
| USER NAME  | = dawsonkb        | DESIGNED - | REVISED - |
|            |                   | DRAWN -    | REVISED - |
| PLOT SCALE | = 40,0000 ' / in. | CHECKED -  | REVISED - |
| PLOT DATE  | = 8/15/2019       | DATE -     | REVISED - |

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

LOCATION MAP

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

| F.A.I. RTE.                 | SECTION | COUNTY             | TOTAL SHEETS     | SHEET NO. |
|-----------------------------|---------|--------------------|------------------|-----------|
| 74                          | *       | VERMILION          | 52               | 3         |
| * D5 BRIDGE PAINTING 2020-1 |         | CONTRACT NO. 70E06 |                  |           |
|                             |         | ILLINOIS           | FED. AID PROJECT |           |

# LOCATION #1

DESCRIPTION: I-74 EB over "L" STREET in TILTON - M.P. - 213.4  
COUNTY: VERMILION  
ROUTE: F.A.I. 74  
MARKED ROUTE: I-74  
SECTION: (92-11VB)BR  
STRUCTURE NO.: 092-0008 E.B.  
TYPE OF STRUCTURE CONTINUOUS STEEL  
7 BEAM LINES - BK-BK ABUTS = 277.4'

CLEANING AND PAINTING OF THE EXISTING STRUCTURAL STEEL SHALL BE AS SPECIFIED IN THE SPECIAL PROVISIONS FOR "CLEANING AND PAINTING EXISTING STEEL STRUCTURES." ALL BEAMS, BEARINGS AND OTHER STRUCTURAL STEEL SHALL BE CLEANED PER NEAR WHITE BLASTNG SSPC-SP10.

THE DESIGNATED AREAS CLEANED PER NEAR WHITE BLAST CLEANING SSPC-SP10 SHALL BE PAINTED ACCORDING TO THE REQUIREMENTS OF PAINT SYSTEM 1 OZ/E/U. THE COLOR OF THE FINAL FINISH COAT FOR ALL INTERIOR STEEL SURFACES SHALL BE GRAY, MUNSELL NO. 5B 7/1. THE COLOR OF THE FINAL FINISH COAT FOR ALL EXTERIOR AND BOTTOM FLANGE OF THE FASCIA BEAMS SHALL BE INTERSTATE GREEN (MUNSELL COLOR STANDARD 7.5G 4/8).

A MINIMUM OF TWO (2) HIGH VOLUME AIR MONITORS WILL BE REQUIRED TO MONITOR AIR QUALITY DURING DUST PRODUCING OPERATIONS AT THIS SITE. SEE SPECIAL PROVISIONS FOR "CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES".

THE EXISTING STRUCTURAL STEEL COATING CONTAINS LEAD. THE CONTRACTOR SHALL FOLLOW THE GUIDE BRIDGE SPECIAL PROVISIONS FOR "CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES" TO DEAL WITH THE PRESENCE OF LEAD ON THIS PROJECT.

NOTE: DECK DRAINS WITHIN THE PAINTING LIMITS DESCRIBED ABOVE ARE TO BE PAINTED AT NO ADDITIONAL COST.

NOTE: ELASTOMERIC BEARINGS

TWO (2) YEAR PAINT WARRANTY REQUIRED FOR THIS STRUCTURE

# LOCATION #2

DESCRIPTION: I-74 WB over "L" STREET in TILTON - M.P. - 213.4  
COUNTY: VERMILION  
ROUTE: F.A.I. 74  
MARKED ROUTE: I-74  
SECTION: (92-11VB)BR  
STRUCTURE NO.: 092-0009 W.B.  
TYPE OF STRUCTURE CONTINUOUS STEEL  
8 BEAM LINES - BK-BK ABUTS = 317.5'

CLEANING AND PAINTING OF THE EXISTING STRUCTURAL STEEL SHALL BE AS SPECIFIED IN THE SPECIAL PROVISIONS FOR "CLEANING AND PAINTING EXISTING STEEL STRUCTURES." ALL BEAMS, BEARINGS AND OTHER STRUCTURAL STEEL SHALL BE CLEANED PER NEAR WHITE BLASTNG SSPC-SP10.

THE DESIGNATED AREAS CLEANED PER NEAR WHITE BLAST CLEANING SSPC-SP10 SHALL BE PAINTED ACCORDING TO THE REQUIREMENTS OF PAINT SYSTEM 1 OZ/E/U. THE COLOR OF THE FINAL FINISH COAT FOR ALL INTERIOR STEEL SURFACES SHALL BE GRAY, MUNSELL NO. 5B 7/1. THE COLOR OF THE FINAL FINISH COAT FOR ALL EXTERIOR AND BOTTOM FLANGE OF THE FASCIA BEAMS SHALL BE INTERSTATE GREEN (MUNSELL COLOR STANDARD 7.5G 4/8).

A MINIMUM OF TWO (2) HIGH VOLUME AIR MONITORS WILL BE REQUIRED TO MONITOR AIR QUALITY DURING DUST PRODUCING OPERATIONS AT THIS SITE. SEE SPECIAL PROVISIONS FOR "CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES".

THE EXISTING STRUCTURAL STEEL COATING CONTAINS LEAD. THE CONTRACTOR SHALL FOLLOW THE GUIDE BRIDGE SPECIAL PROVISIONS FOR "CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES" TO DEAL WITH THE PRESENCE OF LEAD ON THIS PROJECT.

NOTE: DECK DRAINS WITHIN THE PAINTING LIMITS DESCRIBED ABOVE ARE TO BE PAINTED AT NO ADDITIONAL COST.

NOTE: ELASTOMERIC BEARINGS

TWO (2) YEAR PAINT WARRANTY REQUIRED FOR THIS STRUCTURE

MODEL: \\MODEL\\NAME'S  
FILE: \\NAME: \\paw\\dwmcom\\data\\ilind\\s\\gov\\PWIDOT\\Documents\\IDOT\_Offices\\ID\\d\\tct\_5\\projects\\0570E06\\CADD\\data\\Design\\0570E06-dht-Pr\\ilind.dgn

|  |                              |            |           |                                                   |                                          |  |                    |  |             |         |           |              |           |
|--|------------------------------|------------|-----------|---------------------------------------------------|------------------------------------------|--|--------------------|--|-------------|---------|-----------|--------------|-----------|
|  | USER NAME = dawsorkb         | DESIGNED - | REVISED - | STATE OF ILLINOIS<br>DEPARTMENT OF TRANSPORTATION | DESCRIPTION OF WORK<br>LOCATIONS #1 & #2 |  |                    |  | F.A.I. RTE. | SECTION | COUNTY    | TOTAL SHEETS | SHEET NO. |
|  |                              | DRAWN -    | REVISED - |                                                   |                                          |  |                    |  | 74          | *       | VERMILION | 52           | 4         |
|  | PLOT SCALE = 40,0000 ' / in. | CHECKED -  | REVISED - |                                                   | D5 BRIDGE PAINTING 2020-1                |  | CONTRACT NO. 70E06 |  |             |         |           |              |           |
|  | PLOT DATE = 8/15/2019        | DATE -     | REVISED - |                                                   | ILLINOIS FED. AID PROJECT                |  |                    |  |             |         |           |              |           |
|  | SCALE:                       |            | SHEET 1   |                                                   |                                          |  |                    |  |             | OF 1    | SHEETS    | STA.         | TO STA.   |

## LOCATION #4

# LOCATION #5

DESCRIPTION: I-74 WB over CSX RR & CR 2100E in DANVILLE - M.P. - 219.5  
COUNTY: VERMILION  
ROUTE: F.A.I. 74  
MARKED ROUTE: I-74  
SECTION: (92-12VB-1)BR  
STRUCTURE NO.: 092-0023 W.B.  
TYPE OF STRUCTURE CONTINUOUS STEEL  
11 BEAM LINES - BK-BK ABUTS = 271.0'

CLEANING AND PAINTING OF THE EXISTING STRUCTURAL STEEL SHALL BE AS SPECIFIED IN THE SPECIAL PROVISIONS FOR "CLEANING AND PAINTING EXISTING STEEL STRUCTURES." ALL BEAMS, BEARINGS AND OTHER STRUCTURAL STEEL SHALL BE CLEANED PER NEAR WHITE BLASTING SSPC-SP10.

THE DESIGNATED AREAS CLEANED PER NEAR WHITE BLAST CLEANING SSPC-SP10 SHALL BE PAINTED ACCORDING TO THE REQUIREMENTS OF PAINT SYSTEM 1 OZ/E.U. THE COLOR OF THE FINAL FINISH COAT FOR ALL INTERIOR STEEL SURFACES SHALL BE GRAY, MUNSELL NO. 5B 7/1. THE COLOR OF THE FINAL FINISH COAT FOR ALL EXTERIOR AND BOTTOM FLANGE OF THE FASCIA BEAMS SHALL BE INTERSTATE GREEN (MUNSELL COLOR STANDARD 7.5G 4/8).

A MINIMUM OF TWO (2) HIGH VOLUME AIR MONITORS WILL BE REQUIRED TO MONITOR AIR QUALITY DURING DUST PRODUCING OPERATIONS AT THIS SITE. SEE SPECIAL PROVISIONS FOR "CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES".

THE EXISTING STRUCTURAL STEEL COATING CONTAINS LEAD. THE CONTRACTOR SHALL FOLLOW THE GUIDE BRIDGE SPECIAL PROVISIONS FOR "CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES" TO DEAL WITH THE PRESENCE OF LEAD ON THIS PROJECT.

NOTE: DECK DRAINS WITHIN THE PAINTING LIMITS DESCRIBED ABOVE ARE TO BE PAINTED AT NO ADDITIONAL COST.

TWO (2) YEAR PAINT WARRANTY REQUIRED FOR THIS STRUCTURE

## LOCATION #6

|                   |                                                           |
|-------------------|-----------------------------------------------------------|
| DESCRIPTION:      | I-74 EB over CSX RR & CR 2100E in DANVILLE - M.P. - 219.5 |
| COUNTY:           | VERMILION                                                 |
| ROUTE:            | F.A.I. 74                                                 |
| MARKED ROUTE:     | I-74                                                      |
| SECTION:          | (92-12VB-1)BR                                             |
| STRUCTURE NO.:    | 092-0024 E.B.                                             |
| TYPE OF STRUCTURE | CONTINUOUS STEEL                                          |
|                   | 7 BEAM LINES - BK-BK ABUTS = 271.0'                       |

CLEANING AND PAINTING OF THE EXISTING STRUCTURAL STEEL SHALL BE AS SPECIFIED IN THE SPECIAL PROVISIONS FOR "CLEANING AND PAINTING EXISTING STEEL STRUCTURES." ALL BEAMS, BEARINGS AND OTHER STRUCTURAL STEEL SHALL BE CLEANED PER NEAR WHITE BLASTING SSPC-SP10.

THE DESIGNATED AREAS CLEANED PER NEAR WHITE BLAST CLEANING SSPC-SP10 SHALL BE PAINTED ACCORDING TO THE REQUIREMENTS OF PAINT SYSTEM 1 OZ/E.U. THE COLOR OF THE FINAL FINISH COAT FOR ALL INTERIOR STEEL SURFACES SHALL BE GRAY, MUNSELL NO. 5B 7/1. THE COLOR OF THE FINAL FINISH COAT FOR ALL EXTERIOR AND BOTTOM FLANGE OF THE FASCIA BEAMS SHALL BE INTERSTATE GREEN (MUNSELL COLOR STANDARD 7.5G 4/8).

A MINIMUM OF TWO (2) HIGH VOLUME AIR MONITORS WILL BE REQUIRED TO MONITOR AIR QUALITY DURING DUST PRODUCING OPERATIONS AT THIS SITE. SEE SPECIAL PROVISIONS FOR "CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES".

THE EXISTING STRUCTURAL STEEL COATING CONTAINS LEAD. THE CONTRACTOR SHALL FOLLOW THE GUIDE BRIDGE SPECIAL PROVISIONS FOR "CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES" TO DEAL WITH THE PRESENCE OF LEAD ON THIS PROJECT.

NOTE: DECK DRAINS WITHIN THE PAINTING LIMITS DESCRIBED ABOVE ARE TO BE PAINTED AT NO ADDITIONAL COST.

TWO (2) YEAR PAINT WARRANTY REQUIRED FOR THIS STRUCTURE

## RAILROAD GENERAL NOTES

Refer to the CSX Transportation Public Project Information Manual for additional requirements needed for working on/above/adjacent to CSXT. Specific sections that pertain to this project are: Special Provisions for Construction near CSXT Property, Overhead Bridge Criteria, Construction Submission Criteria, and Insurance Requirements for Public Projects.

CSXT may require the Contractor to install filter fabric over the track(s) and ballast to prevent any construction debris from fouling the ballast. This will be determined during actual construction activities by CSXT or its Representative. Fabric will remain in place until all construction activities are complete.

The Contractor may not use CSXT right-of-way for storage of materials or equipment during construction without prior CSXT approval. The CSXT right-of-way must remain clear for railroad use at all times. Equipment may not be positioned to block the railroad access road, track area or any part of the CSXT right-of-way without prior CSXT approval.

Temporary Construction Clearance - Ensure all falsework, bracing or forms have a minimum horizontal clearance of 12 feet measured perpendicular to the centerline of the nearest track, and a minimum vertical clearance of 22 feet or existing clearance, whichever is less, as measured from the top of rail profile.

Means and Methods – The Contractor shall develop a detailed submission indicating the progression of work with specific times when tasks will be performed for work activities that are on or in the vicinity of the CSXT property. This submission may require a walkthrough at which time CSXT and/or the CSXT Construction Representative will be present. Work will not be permitted to commence until the Contractor has provided CSXT with a satisfactory plan that the project will be undertaken without scheduling, performance or safety related issues. Provide a listing of the anticipated equipment to be used, the location of all equipment to be used and insure a contingency plan of action is in place should a primary piece of equipment malfunction. All work in the vicinity of CSXT property that has the potential of affecting CSXT train operations must be submitted and approved by CSXT prior to work being performed. This submission shall also include a detailed narrative discussing the coordination of project safety issues between Contractor, CSXT and the CSXT Construction Representative. The narrative shall address project level coordination and day to day, specific work operations including crane and equipment operations, erection plans and temporary works.

Construction Schedule – Submit a detailed construction schedule for the duration of the project clearly indicating the time periods while working on and around CSXT right-of-way. As the work progresses, this schedule shall be updated and resubmitted as necessary to reflect changes in work sequence, duration and method, etc.

Contractor access will be limited to the immediate project area only. The CSXT right-of-way outside the project area may not be used for contractor access to the project site and no temporary at-grade crossings will be allowed.

Contractor shall enter into Right-of-Entry Agreement with CSXT. Periodically, throughout the project duration, the Contractor will be required to meet, discuss and, if necessary, take immediate action at the discretion of CSXT personnel and/or their authorized Representative, to comply with provisions of that agreement and these specifications.

All waste materials generated by this project, including but not limited to washing with water, cleaning solvents, blasting, scraping, brushing and painting operations, shall be the responsibility of the Project Sponsor or its Contractor and shall be contained, collected and properly disposed of by the Project Sponsor or its Contractor. The Project Sponsor and its Contractor agree to fully comply with all federal, state, and local environmental laws, regulations, statutes and ordinances at all times.

Upon completion of the work on CSXT property, the Contractor shall request the Owner to arrange a final inspection of the project with the Railroad's Project Engineer or his authorized Representative.

|                                                       |                              |            |           |                                                   |                                          |                                              |         |             |              |           |  |  |
|-------------------------------------------------------|------------------------------|------------|-----------|---------------------------------------------------|------------------------------------------|----------------------------------------------|---------|-------------|--------------|-----------|--|--|
| FILE NAME: D:\PROJECTS\2019\11-15-2019\11-15-2019.DWG | USER NAME = dawsnkb          | DESIGNED - | REVISED - | STATE OF ILLINOIS<br>DEPARTMENT OF TRANSPORTATION | DESCRIPTION OF WORK<br>LOCATIONS #5 & #6 | F.A.I. RTE.                                  | SECTION | COUNTY      | TOTAL SHEETS | SHEET NO. |  |  |
|                                                       |                              | DRAWN -    | REVISED - |                                                   |                                          | 74                                           | *       | VERMILION   | 52           | 6         |  |  |
|                                                       | PLOT SCALE = 40,0000 ' / in. | CHECKED -  | REVISED - |                                                   |                                          | D5 BRIDGE PAINTING 2020-1 CONTRACT NO. 70E06 |         |             |              |           |  |  |
|                                                       | PLOT DATE = 8/15/2019        | DATE -     | REVISED - |                                                   |                                          |                                              |         |             |              |           |  |  |
|                                                       |                              |            |           |                                                   |                                          | SCALE:                                       | SHEET 1 | OF 1 SHEETS | STA.         | TO STA.   |  |  |

## SUMMARY OF QUANTITIES

| LOC. #1       | LOC. #2       | LOC. #3       | LOC. #4       | LOC. #5       | LOC. #6       |
|---------------|---------------|---------------|---------------|---------------|---------------|
| FAI 74        | FAI 74        | FAI 74        | FAI 74        | FAI 74        | FAI 74        |
| S.N. 092-0008 | S.N. 092-0009 | S.N. 092-0025 | S.N. 092-0026 | S.N. 092-0023 | S.N. 092-0024 |
| VERMILION CO. | VERMILION CO. | VERMILION CO. | VERMILION CO. | VERMILION CO. | VERMILION CO. |
| URBAN         | URBAN         | URBAN         | URBAN         | URBAN         | URBAN         |
| 80% FEDERAL   | 80% FEDERAL   | 80% FEDERAL   | 80% FEDERAL   | 80% FEDERAL   | 80% FEDERAL   |
| 20% STATE     | 20% STATE     | 20% STATE     | 20% STATE     | 20% STATE     | 20% STATE     |
| 0047          | 0047          | 0047          | 0047          | 0047          | 0047          |

CONSTRUCTION TYPE CODE:

[illegible]

SUMMARY OF QUANTITIES

|               |               |               |               |               |               |
|---------------|---------------|---------------|---------------|---------------|---------------|
| LOC. #1       | LOC. #2       | LOC. #3       | LOC. #4       | LOC. #5       | LOC. #6       |
| FAI 74        | FAI 74        | FAI 74        | FAI 74        | FAI 74        | FAI 74        |
| S.N. 092-0008 | S.N. 092-0009 | S.N. 092-0025 | S.N. 092-0026 | S.N. 092-0023 | S.N. 092-0024 |
| VERMILION CO. | VERMILION CO. | VERMILION CO. | VERMILION CO. | VERMILION CO. | VERMILION CO. |
| URBAN         | URBAN         | URBAN         | URBAN         | URBAN         | URBAN         |
| 80% FEDERAL   | 80% FEDERAL   | 80% FEDERAL   | 80% FEDERAL   | 80% FEDERAL   | 80% FEDERAL   |
| 20% STATE     | 20% STATE     | 20% STATE     | 20% STATE     | 20% STATE     | 20% STATE     |
| 0047          | 0047          | 0047          | 0047          | 0047          | 0047          |

CONSTRUCTION TYPE CODE :

| CODE NO. | ITEM                                                           | UNIT  | TOTAL QUANTITY | QUANTITY | QUANTITY | QUANTITY | QUANTITY | QUANTITY | QUANTITY |
|----------|----------------------------------------------------------------|-------|----------------|----------|----------|----------|----------|----------|----------|
| X5067503 | BRIDGE CLEANING AND PAINTING WARRANTY NUMBER 3                 | L SUM | 1.0            |          |          | 1.0      |          |          |          |
|          |                                                                |       |                |          |          |          |          |          |          |
| X5067504 | BRIDGE CLEANING AND PAINTING WARRANTY NUMBER 4                 | L SUM | 1.0            |          |          |          | 1.0      |          |          |
|          |                                                                |       |                |          |          |          |          |          |          |
| X5067505 | BRIDGE CLEANING AND PAINTING WARRANTY NUMBER 5                 | L SUM | 1.0            |          |          |          |          | 1.0      |          |
|          |                                                                |       |                |          |          |          |          |          |          |
| X5067506 | BRIDGE CLEANING AND PAINTING WARRANTY NUMBER 6                 | L SUM | 1.0            |          |          |          |          |          | 1.0      |
|          |                                                                |       |                |          |          |          |          |          |          |
| X6061702 | CONCRETE MEDIAN, TYPE SM (DOWELLED)                            | SQ FT | 4400.0         |          |          | 2200.0   | 2200.0   |          |          |
|          |                                                                |       |                |          |          |          |          |          |          |
| X7010216 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL)                      | L SUM | 1.0            | 0.5      | 0.5      |          |          |          |          |
|          |                                                                |       |                |          |          |          |          |          |          |
| Z0007101 | CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1 | L SUM | 1.0            | 1.0      |          |          |          |          |          |
|          |                                                                |       |                |          |          |          |          |          |          |
| Z0007102 | CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 2 | L SUM | 1.0            |          | 1.0      |          |          |          |          |
|          |                                                                |       |                |          |          |          |          |          |          |
| Z0007103 | CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 3 | L SUM | 1.0            |          |          | 1.0      |          |          |          |
|          |                                                                |       |                |          |          |          |          |          |          |
| Z0007104 | CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 4 | L SUM | 1.0            |          |          |          | 1.0      |          |          |
|          |                                                                |       |                |          |          |          |          |          |          |
| Z0007105 | CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 5 | L SUM | 1.0            |          |          |          |          | 1.0      |          |
|          |                                                                |       |                |          |          |          |          |          |          |
| Z0007106 | CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 6 | L SUM | 1.0            |          |          |          |          |          | 1.0      |
|          |                                                                |       |                |          |          |          |          |          |          |
| Z0010501 | CLEANING AND PAINTING STEEL BRIDGE NO. 1                       | L SUM | 1.0            | 1.0      |          |          |          |          |          |
|          |                                                                |       |                |          |          |          |          |          |          |
| Z0010502 | CLEANING AND PAINTING STEEL BRIDGE NO. 2                       | L SUM | 1.0            |          | 1.0      |          |          |          |          |
|          |                                                                |       |                |          |          |          |          |          |          |

MODEL: S:\MODEL\NAMES  
FILE: NAME: pva\vermilion\com\data\illinois\gov\pva\DOT\Documents\DOT\_Offices\Illnet\ct\_5\projects\0570E06\CADD\data\Design\0570E06-sh-500.dgn

















LEGEND

- CONSTRUCTION AREA
- CONSTRUCTION BARRELS
- CONCRETE MEDIAN REMOVAL
- STOP BAR

MODEL: ST0001\NAME'S  
FILE: NAME'S - 70E06.dwg  
PROJECT: 70E06  
SHEET: 13  
DATE: 8/15/2019  
DESIGNED: -  
DRAWN: -  
CHECKED: -  
DATE: -

|            |                  |          |   |          |   |
|------------|------------------|----------|---|----------|---|
| USER NAME  | = dawsomb        | DESIGNED | - | REVISED  | - |
| DRAWN      | -                | REVISION | - | REVISION | - |
| PLOT SCALE | = 40,000 ' / in. | CHECKED  | - | REVISION | - |
| PLOT DATE  | = 8/15/2019      | DATE     | - | REVISION | - |

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

LOCATIONS 3 & 4: TRAFFIC CONTROL PLAN – STAGE II  
I-74 & LYNCH ROAD

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

| F.A.I. RTE.               | SECTION | COUNTY                    | TOTAL SHEETS | SHEET NO. |
|---------------------------|---------|---------------------------|--------------|-----------|
| 74                        | *       | VERMILION                 | 52           | 13        |
| D5 BRIDGE PAINTING 2020-1 |         | CONTRACT NO. 70E06        |              |           |
|                           |         | ILLINOIS FED. AID PROJECT |              |           |



CONTRACTOR TO REMOVE A MINIMUM OF 145.0' OF CONCRETE MEDIAN. CONTRACTOR TO BEGIN AND TERMINATE REMOVAL AT EXISTING CONSTRUCTION JOINT. SEE MEDIAN DETAIL (SM-6) ON PAGE 16. CONTRACTOR TO REPLACE MEDIAN AT THE TERMINATION OF THE PROJECT ACCORDING TO MEDIAN DETAIL PROVIDED (SM-6) ON PAGE 16.

CONSTRUCTION AREA

## CONSTRUCTION BARRELS

CONTRACTOR TO REMOVE A MINIMUM OF 145.0' OF CONCRETE MEDIAN, CONTRACTOR TO BEGIN AND TERMINATE REMOVAL AT EXISTING CONSTRUCTION JOINT, SEE MEDIAN DETAIL (SM-6) ON PAGE 16. CONTRACTOR TO REPLACE MEDIAN AT THE TERMINATION OF THE PROJECT ACCORDING TO MEDIAN DETAIL PROVIDED (SM-6) ON PAGE 16.

### LEGEND



○

---

|                              |            |           |
|------------------------------|------------|-----------|
| USER NAME = dawsonkb         | DESIGNED - | REVISED - |
|                              | DRAWN -    | REVISED - |
| PLOT SCALE = 40,0000 ' / in. | CHECKED -  | REVISED - |
| PLOT DATE = 8/15/2019        | DATE -     | REVISED - |

**LOCATIONS 3 & 4: TRAFFIC CONTROL PLAN - STAGE II**  
**I-74 & LYNCH ROAD**

|        |                     |      |         |
|--------|---------------------|------|---------|
| SCALE: | SHEET 1 OF 1 SHEETS | STA. | TO STA. |
|--------|---------------------|------|---------|

| F.A.I.<br>RTE.            | SECTION  | COUNTY             | TOTAL<br>SHEETS | SHEET<br>NO. |
|---------------------------|----------|--------------------|-----------------|--------------|
| 74                        | *        | VERMILION          | 52              | 15           |
| D5 BRIDGE PAINTING 2020-1 |          | CONTRACT NO. 70E06 |                 |              |
|                           | ILLINOIS | FED. AID PROJECT   |                 |              |

MODEL: \$MODEL\NAMES  
FILE NAME: pw:\planroom.dot\IllIndoLgov.gov\WIDOT\Documents\IBOT\_Offices\District\_5\Projects\DS70E06\CADData\Design\DS70E06-shl-Plan.dgn



## GENERAL NOTES

1. DOWEL BARS @ 36" CTS. OR AS DIRECTED BY THE ENGINEER
2. THE EXISTING MEDIAN CONSISTS OF A 6" THICK CONCRETE MEDIAN DOWELED INTO FULL DEPTH ASPHALT PAVEMENT. THERE IS NO CURB AND GUTTER TO BE REMOVED ONLY THE 6" MEDIAN CAP SITTING ON THE FULL DEPTH ASPHALT PAVEMENT. THE EXISTING MEDIAN CONTAINS WELDED WIRE FABRIC.
3. CARE SHALL BE TAKEN NOT TO DAMAGE PORTIONS OF THE CONCRETE MEDIAN TO REMAIN IN PLACE. FULL DEPTH SAW CUTS SHALL BE USED AT THE REMOVAL LIMITS.
4. CARE SHALL BE TAKEN NOT TO DAMAGE THE FULL DEPTH ASPHALT PAVEMENT BELOW THE CONCRETE MEDIAN. THE UNDERLYING PAVEMENT WILL BE UTILIZED FOR CROSSOVER TRAFFIC. EXISTING DOWEL BARS SHALL BE CUT FLUSH WITH THE PAVEMENT OR REMOVED AND HOLES FILLED WITH MORTAR.
5. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQ FOOT FOR CONCRETE MEDIAN REMOVAL  
CONCRETE MEDIAN, TYPE SM (DOWELLED)  
THE COST OF FURNISHING AND INSTALLING THE DOWEL BARS, MORTAR FILLING, AND PAVEMENT FABRIC SHALL BE INCLUDED IN THE PAY ITEMS LISTED ABOVE WITH NO ADDITIONAL COMPENSATION ALLOWED.

LOCATION 3# & #4 - 092-0025 & 092-0026

```
MODEL: $MODELNAME$
FILE NAME: pw:\plannroom\dol\llnols.gov\PWIDOT\Documents\IDOT Offices\Distrtc 5\Projects\DS70E06\CADDData\Design\DS70E06-shit-X-S.dgn
```

|  |                             |            |           |                                                   |                                                                |                     |          |                  |                |                    |           |                 |              |
|--|-----------------------------|------------|-----------|---------------------------------------------------|----------------------------------------------------------------|---------------------|----------|------------------|----------------|--------------------|-----------|-----------------|--------------|
|  | USER NAME = dawsonkb        | DESIGNED - | REVISED - | STATE OF ILLINOIS<br>DEPARTMENT OF TRANSPORTATION | CONCRETE MEDIAN REMOVAL<br>CONCRETE MEDIAN, TYPE SM (DOWELLED) |                     |          |                  | F.A.I.<br>RTE. | SECTION            | COUNTY    | TOTAL<br>SHEETS | SHEET<br>NO. |
|  |                             | DRAWN -    | REVISED - |                                                   |                                                                |                     |          |                  | 74             | *                  | VERMILION | 52              | 16           |
|  | PLOT SCALE = 40,000 ' / in. | CHECKED -  | REVISED - |                                                   | D5 BRIDGE PAINTING 2020-1                                      |                     |          |                  |                | CONTRACT NO. 70E06 |           |                 |              |
|  | PLOT DATE = 8/15/2019       | DATE -     | REVISED - |                                                   | SCALE:                                                         | SHEET 1 OF 1 SHEETS | STA.     | TO STA.          |                |                    |           |                 |              |
|  |                             |            |           |                                                   |                                                                |                     | ILLINOIS | FED. AID PROJECT |                |                    |           |                 |              |

092-00008 E.B.

\*\*\* (92-11VB)BR

|                     |         |           |              |           |
|---------------------|---------|-----------|--------------|-----------|
| ROUTE NO.           | SECTION | COUNTY    | TOTAL SHEETS | SHEET NO. |
| FAI-74              | 00000   | Vermilion | 165          | 90        |
| STA.                |         | TO STA.   |              |           |
| FED. ROAD DIST. NO. | 3.18103 | PROJECT   |              |           |
| Dwg. No. 1 of 41    |         |           |              |           |

## LEGEND

F=Fixed Bearing  
E=Exp. Bearing  
PGL=Profile Grade Line

**ELEVATION**  
(Eastbound Bridge)

317'-6<sup>3</sup>/<sub>8</sub>" Bk. to Bk. Abutments

STATION 1877+01.73  
BUILT 199\_ BY  
STATE OF ILLINOIS  
E. 74 SECTION (92-11VB)BR  
LOADING HS20 & ALT.  
STR. NO. 092-0009

**WESTBOUND**

STATION 1877+01.73  
BUILT 199 BY  
STATE OF ILLINOIS  
FAL RTE. 74 SECTION (92-11VB)BR  
LOADING HS20 & ALT.  
STR. NO. 092-0008

**EASTBOUND**

**NEW NAME PLATES**  
**(1 EA. REQ'D)**

(SEE STD. 2113)

Note  
Salvage Existing Name Plates &  
Mount Adjacent to New Name  
Plates on New Parapet as shown  
on Sfd. 2113. The cost of Salvaging  
& Incorporating Exist. Name Plates  
into New Work is Incidental to Name Plates.

092-0009 W.B

BK. of E. Abut.  
Sta. 1879+02.33  
Elev. 667.53

A cross-sectional diagram of a parapet wall and its foundation. The diagram shows an existing sloped wall on the left, labeled "Exist. Slopedwall". A new parapet wall is shown extending from this, with its top surface labeled "Outside Face of New Parapet". The foundation consists of a concrete base, 1'-0" thick, labeled "Filter Fabric for use with Riprap". Above the concrete base is a layer of "Stone Riprap, Class A3", which is 5'-0" thick. The riprap layer is shown with a cross-hatched pattern.

092-0008 E.B.

**SECTION A-A**  
(Type & Location)

**SECTION C-C**

**SECTION B-B**  
*Similar @ 4 Locations*

\*\*\* REMOVE & REPLACE 4" SLOPEWALL  
WHERE REQUIRED FOR CONSTRUCTION  
OF PIER WIDENING. COST INCIDENTAL  
TO CLASS X CONCRETE.

**APPROVED**  
FOR STRUCTURAL ADEQUACY ONLY

Ralph E. Anderson

**ESCA**  
CONSULTANTS, INC.

|              |        |      |
|--------------|--------|------|
| DESIGNED BY: | RDP    | 8-89 |
| DRAWN BY:    | TP/WEM | 8-89 |
| CHECKED BY:  | JRF    | 8-89 |
| APPROVED BY: | RDP    | 8-89 |

FAI-74 PROFILE GRADE  
(Along E. Pavement)

"L" STREET PROFILE GRADE  
(Pavement Southbound Lanes)

R.R. SIDING PROFILE  
(Top of Rail)

### LOCATION SKETCH

**GENERAL PLAN & ELEVATION**  
**FAI 74 OVER "L" STREET & RR SIDING**  
**FAI RTE 74 SECTION(92-IIVB) BR**  
**VERMILION COUNTY**  
**STATION 1877+0.73**  
**STRUCTURE NO. 092-0008 (E.B.)**  
**STRUCTURE NO. 092-0009 (W.B.)**

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**FOR INFO ONLY – STRUCTURE DETAILS FOR  
LOCATIONS #1 & #2**

| F.A.I.<br>RTE.            | SECTION | COUNTY             | TOTAL<br>SHEETS | SHEET<br>NO. |
|---------------------------|---------|--------------------|-----------------|--------------|
| 74                        | *       | VERMILION          | 52              | 17           |
| D5 BRIDGE PAINTING 2020-1 |         | CONTRACT NO. 70E06 |                 |              |
| ILLINOIS                  |         | FED. AID PROJECT   |                 |              |


```
MODEL: $MODELNAME$
FILE NAME: newVlanRoom_dot_IIItools_conv.pwIDOTDocumentsIDOT_OfficesIDierIct_5ProjectsDS57OF06(CADDData\Deedom)DS7OF06-shr-Detalls.dgn
```



\* (9E-11VB) BR

|                  |          |            |              |          |
|------------------|----------|------------|--------------|----------|
| ROUTE NO         | SECTION  | COUNTY     | TOTAL SHEETS | SHEET NO |
| FAI-74           | ✻        | Kermillion | 145          | 91       |
| STA              |          | TO STA     |              |          |
| FED ROAD DIST NO | ILLINOIS | PROJECT    |              |          |
| Dwg No 2 of 41   |          |            |              |          |


1. SEE PROPOSAL FOR BORING DATA.
2. FASTENERS SHALL BE HIGH STRENGTH BOLTS. BOLTS 3/4" Ø, OPEN HOLES 13/16" Ø, UNLESS OTHERWISE NOTED.
3. CALCULATED WEIGHT OF STRUCTURAL STEEL = 74,000 LBS.



*Prior to pouring the new concrete for the deck, all loose rust, loose mill scale, and all other foreign material shall be removed from the embedded portions of flanges of stringers. The removal shall be accomplished in accordance with the requirements of the SSPC Surface Preparation Specifications SP-11 for Power tool cleaning or SP-2 for Hand tool cleaning. Cost shall be incidental to concrete removal.*

**ELEVATION**  
(Westbound Bridge)

3. ALL CONTACT SURFACES OF JOINTS FOR THE DIAPHRAGMS AND BOLTED SPLICES SHALL BE FREE OF PAINT OR LACQUER.
4. FIELD WELDING OF CONSTRUCTION ACCESSORIES WILL NOT BE PERMITTED TO THE BOTTOM FLANGE OF BEAMS OR GIRDERS NOR TO THE TOP FLANGE FOR A DISTANCE OF TWO HOLE-POUNCE THE SPAN LENGTH EACH WAY FROM THE PIER SUPPORTS. FIELD WELDING IN OTHER AREAS WILL BE PERMITTED ONLY WHEN APPROVED BY THE ENGINEER.
5. ANCHOR BOLTS SHALL BE SET BEFORE BOLTING DIAPHRAGMS OVER SUPPORTS.
6. THE NEW MAIN LOAD CARRYING MEMBER COMPONENTS SUBJECT TO TENSILE STRESS SHALL CONFORM TO THE SUPPLEMENTAL REQUIREMENTS FOR NOTCH TOUGHNESS, SECTION 2. THESE COMPONENTS ARE THE NEW FLANGE BEAMS AND ALL SPLICE PLATE MATERIAL FOR THESE NEW BEAMS.
7. REINFORCEMENT BARS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M-31, M-42 OR M-53 GRADE 60.
8. PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING STRUCTURE HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF THE WORK; HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.
9. EXPANSION BOLTS SHALL CONSIST OF APPROVED EXPANSION ANCHORS, PROVIDING MINIMUM CERTIFIED PROOF LOAD = 4,080 LBS., AND 3/4" Ø x 12" HOOKED BOLTS.
10. BEARING SEAT SURFACES SHALL BE CONSTRUCTED OR ADJUSTED TO THE DESIGNATED ELEVATIONS WITHIN A TOLERANCE OF 1/8 INCH. ADJUSTMENT SHALL BE MADE EITHER BY GRINDING THE SURFACE OR BY SHIMMING THE BEARING. THE 1/8" ADJUSTING SHIMS, OF THE DIMENSIONS OF THE BOTTOM BEARING PLATE, SHALL BE PROVIDED FOR EACH BEARING IN ADDITION TO ALL OTHER PLATES OR SHIMS.
11. THE CONTRACTOR SHALL DRIVE ONE CONCRETE TEST PILE IN A PERMANENT LOCATION AT EACH ABUTMENT ON THE EB BRIDGE AND ONE STEEL HP 10X12 PILE IN A PERMANENT LOCATION AT THE RETAINING WALL AND AT PIER 2 ON THE EB BRIDGE AS DIRECTED BY THE ENGINEER BEFORE ORDERING THE REMAINDER OF THE PILES.
12. THE CONTRACTOR WILL BE REQUIRED TO MARK ON TOP OF THE CONCRETE DECK THE LOCATIONS OF THE TOP FLANGE OF ALL THE STEEL BEAMS OR GIRDERS, PRIOR TO ANY REMOVAL OF THE BRIDGE CONCRETE DECK. SAW CUTTING DIRECTLY OVER THE TOP OF THE BEAM OR GIRDER FLANGES IS NOT PERMITTED.
13. SLOPES SHALL BE REINFORCED WITH WELDED WIRE FABRIC, 6"x6" - W4xM4.0, WEIGHING 58 LBS. PER SQ. FT.
14. BRIDGE SEAT SEALER SHALL BE APPLIED TO THE BEARING SEATS AT ALL ABUTMENTS AND AT PIERS 1 & 2 WB. ESTIMATED QUANTITY = 750 SQUARE FEET.
15. THE FIRST TWO COATS OF LEAD AND CHROMATE FREE ALKYLID PAINT SYSTEM SHALL BE USED FOR SHOP AND FIELD PAINTING OF NEW STRUCTURAL STEEL.
16. STRUCTURAL STEEL SHALL ONLY BE CLEANED AND PAINTED AS REQUIRED BY THE SPECIAL PROVISIONS FOR CLEANING AND PAINTING NEW STEEL AND ADJACENT AREAS OF EXISTING STEEL STRUCTURES.



**TYPICAL SECTION THRU ABUTMENTS**

| ITEM                                  | UNIT   | SUP-<br>STRUCTURE | SUB-<br>STRUCTURE | TOTAL  |
|---------------------------------------|--------|-------------------|-------------------|--------|
| Concrete Removal                      | Cu Yd  | -                 | 44.8              | 44.8   |
| Expansion Bolts, 4/4" x 9             | Ea     | -                 | 221               | 221    |
| Removal of Exist. Conc. DK. No. 3     | L.SUM  | 1                 | -                 | 1      |
| Removal of Exist. Conc. DK. No. 4     | L.SUM  | 1                 | -                 | 1      |
| Structure Excavation                  | Cu Yd  | -                 | 433.5             | 433.5  |
| Floor Drains                          | Ea     | 20                | -                 | 20     |
| Preformed Joint Seal, 4"              | Lin Ft | 145               | -                 | 145    |
| Aluminum Expansion Joint, 2"          | Lin Ft | 172               | -                 | 172    |
| Class X Concrete Superstructure       | Cu Yd  | 863.7             | -                 | 863.7  |
| Protective Coat                       | Sq Yd  | 485               | -                 | 485    |
| Class X Concrete                      | Cu Yd  | -                 | 190.5             | 190.5  |
| Furnt Erect. Struct. Steel            | L.SUM  | 1                 | -                 | 1      |
| Stud Shoar Connectors                 | Ea     | 5298              | -                 | 5298   |
| Jack Exist. Struct. No.3              | L.SUM  | 1                 | -                 | 1      |
| Jack Exist. Struct. NO.4              | L.SUM  | 1                 | -                 | 1      |
| Reinforcement Bars                    | Lbs    | -                 | 2420              | 2420   |
| Reinforcement Bars (Epoxy Coated)     | Lbs    | 188240            | 26310             | 214550 |
| Bridge Seat Sealer                    | L.SUM  | -                 | 1                 | 1      |
| Steel Piles HP10x42                   | Lin Ft | -                 | 544               | 544    |
| Concrete Piles                        | Lin Ft | -                 | 252               | 252    |
|                                       |        | -                 |                   |        |
| Filter Fabric For Use With Riprap     | Sq Yd  | -                 | 159               | 159    |
| Test Pile Steel HP10x42               | Ea     | -                 | 2                 | 2      |
| Test Pile Concrete                    | Ea     | -                 | 2                 | 2      |
| Temporary Sheet Piling                | Sq Ft  | -                 | 1336              | 1336   |
| Alumplates                            | Ea     | 2                 | -                 | 2      |
| Repair Concrete Structures            | Sq Ft  | -                 | 151               | 151    |
| Stone Riprap, Class R2                | Sq Yd  | -                 | 159               | 159    |
| Elastomeric Bearing Assembly, Type II | Ea     | -                 | 15                | 15     |
| Drainage Scupper                      | Ea     | 1                 | -                 | 1      |
| Elastomeric Brg. Assembly, Type I     | Ea     | -                 | 46                | 46     |
| Temporary Bridge Roll                 | Lin Ft | 350               | -                 | 350    |
| Drainage System                       | L.SUM  | 1                 | -                 | 1      |
| Elastomeric Brg. Assembly, Type III   | Ea     | -                 | 7                 | 7      |
| Bridge Deck Grooving                  | Sq Yd  | 2926              | -                 | 2926   |

\* INCLUDES TOP AND INSIDE FACE OF PARAPET ONLY.

GENERAL NOTES &  
BILL OF MATERIAL  
FAI 74 OVER L STREET  
FAI RTE. 74 SECTION (92-11VB)BR  
VERMILION COUNTY  
STATION 1877+01.73  
STRUCTURE NO. 092-0008(EB)  
STRUCTURE NO. 092-0009(WB)

|                          |     |       |
|--------------------------|-----|-------|
| <b>ESCA</b>              |     |       |
| <b>CONSULTANTS, INC.</b> |     |       |
| DESIGNED BY:             | RDP | 12-89 |
| DRAWN BY:                | WEM | 12-89 |
| CHECKED BY:              | JRF | 12-89 |
| APPROVED BY:             | RDP | 12-89 |

|                             |            |           |
|-----------------------------|------------|-----------|
| USER NAME = dawsomb         | DESIGNED - | REVISED - |
|                             | DRAWN -    | REVISED - |
| PLOT SCALE = 40,000 ' / in. | CHECKED -  | REVISED - |
| PLOT DATE = 8/15/2019       | DATE -     | REVISED - |

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**FOR INFO ONLY – STRUCTURE DETAILS FOR  
LOCATIONS #1 & #2**


|        |                     |      |         |
|--------|---------------------|------|---------|
| SCALE: | SHEET 1 OF 1 SHEETS | STA. | TO STA. |
|--------|---------------------|------|---------|

| F.A.I.<br>RTE.            | SECTION  | COUNTY             | TOTAL<br>SHEETS | SHEET<br>NO. |
|---------------------------|----------|--------------------|-----------------|--------------|
| 74                        | *        | VERMILION          | 52              | 18           |
| D5 BRIDGE PAINTING 2020-1 |          | CONTRACT NO. 70E06 |                 |              |
|                           | ILLINOIS | FED. AID PROJECT   |                 |              |

MODEL: \$MODELNAME\$  
FILE NAME: pw:\planroom\doi\lln\doi.qov\PWIDOT\Documents\IDOT\_Offices\District\_5\Projects\ID570E06\CADData\Design\ID570E06-shr-Detalls.dgn









PLAN

MIN BAR LAP  
#5 2'-2"

- ① @ 50' F.
- ② Order  $a_3(E)$  &  $a_4(E)$  bars full length. Field cut to fit skew & use remainder of bars in opposite end of span.
- ③ Order  $a_4(E)$  bars full length. Field cut to fit skew & use remainder of bars in West end of Span 2, North Side.



CROSS SECTION  
(LOOKING WEST)



REINFORCEMENT DETAIL  
AT SCUPPER

NOTES

- 1. SEE DWG. NO. 11 FOR SECTIONS A-A, C-C, & D-D.
- 2. BARS INDICATED THUS: 10x3-#5b, ETC., INDICATES 10 LINES OF BARS WITH 3 LENGTHS PER LINE.
- 3. BARS DESIGNATED (E) SHALL BE EPOXY COATED.
- 4. REINFORCEMENT BARS AND BAR SPLICERS AT STAGE LINE SHALL BE TIED WITH DOUBLE THE AMOUNT OF TIES NORMALLY USED.
- 5. CUT REINFORCEMENT BARS IN SLAB TO CLEAR DRAINAGE SCUPPERS.

**SUPERSTRUCTURE (WB)**  
**FAI 74 OVER L STREET**  
**FAI RTE. 74 SECTION (92-11VB)BR**  
**VERMILION COUNTY**  
**STATION 1877+01.73**  
**STRUCTURE NO. 092-0008(EB)**  
**STRUCTURE NO. 092-0009(WB)**

**ESCA**  
CONSULTANTS, INC.

|              |     |       |
|--------------|-----|-------|
| DESIGNED BY: | KMR | 12-89 |
| DRAWN BY:    | WEM | 1-90  |
| CHECKED BY:  | RDP | 1-90  |
| APPROVED BY: | RDP | 1-90  |

|            |                   |          |   |         |   |
|------------|-------------------|----------|---|---------|---|
| USER NAME  | = dawnskb         | DESIGNED | - | REVISED | - |
| PLOT SCALE | = 40,0000 ' / in. | DRAWN    | - | REVISED | - |
| PLOT DATE  | = 8/15/2019       | CHECKED  | - | REVISED | - |
|            |                   | DATE     | - | REVISED | - |

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION


FOR INFO ONLY - STRUCTURE DETAILS FOR  
LOCATIONS #1 & #2

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

|                           |         |                    |              |           |
|---------------------------|---------|--------------------|--------------|-----------|
| F.A.I. RTE.               | SECTION | COUNTY             | TOTAL SHEETS | SHEET NO. |
| 74                        | *       | VERMILION          | 52           | 20        |
| D5 BRIDGE PAINTING 2020-1 |         | CONTRACT NO. 70E06 |              |           |
| ILLINOIS                  |         | FED. AID PROJECT   |              |           |








### X DIMENSIONS



| LOCATION         | X         |
|------------------|-----------|
| EB Lanes, N Side | 3'-6 1/2" |
| EB Lanes, S Side | 3'-0"     |
| WB Lanes, N Side | 3'-5"     |
| WB Lanes, S Side | 3'-5"     |

## 7.2 DIMENSIONS



| LOCATION                     | Y      | $\bar{E}$  |
|------------------------------|--------|------------|
| EB Lanes, N4S Sides          | 3'     | 3'-8 1/2"  |
| WB Lanes, Span 1, N4S Sides  | 3 1/2" | 3'-8 1/2"  |
| WB Lanes, Span 2, N Side     | 4 3/4" | 3'-10 1/4" |
| WB Lanes, Span 2, S Side     | 1 3/4" | 3'-7 1/4"  |
| WB Lanes, Spans 3, 4, 5, N4S | 2 1/4" | 3'-7 1/4"  |



\*Dimension as required  
by Pipe Clamp.  
**SECTION A-A**




### FLOOR DRAIN DETAILS




**DETAILS OF PARAPET JOINT**

(See Dwg. Nos. 13 & 14 for locations of these joints.)




Note  
Grout Mixture shall consist of 1 part sand, 1 part cement, 1 part chips (pea gravel). The grout shall contain water for a 1" slump, cost incidental to Pole.




**SECTION B-B**

### DETAIL OF LIGHT STANDARD




S. Corner, W. Abut. EB Lanes Shown;  
S. Corner E. Abut. EB Lanes,  
N. Corner W. Abut. WB Lanes &  
N. Corner E. Abut. WB Lanes Similar



Note  
Cost of Plastic & Flexible Conduit, Junction Boxes, & Anchor Bolts is incidental to Class X Concrete Superstructure.

### BAR BENDING DETAILS



## NOTES

1. FIBERGLASS PIPE SHALL CONFORM TO ASTM D2996, WITH SHORT-TIME HUFFERS STRENGTH HOOF TENSILE STRESS OF 30,000 P.S.I. MINIMUM.
2. THE SURFACE OF THE FIBERGLASS PIPE SHALL BE FREE OF BOND INHIBITING AGENTS.
3. THE EXTERIOR SURFACES OF THE FLOOR DRAIN SHALL BE PAINTED WITH A PRIMA COAT OF THE LEADERS FREE MILKID PAINTING SPECIFIED FOR STRUCTURAL STEEL. THE EXTERIOR SURFACES OF THE ALUMINUM TUBES SHALL BE CLEANED WITH A WASHCOAT PRETREATMENT IN ACCORDANCE WITH STEEL STRUCTURES PAINTING COUNCIL'S SPEC. SSPC-SP 1 & SSPC-PAINT 7 PRIOR TO PAINTING. FIBERGLASS TO HAVE PRIMA AS PER MIL-P-15328.
4. THE CLAMPING DEVICE SHALL BE GALVANIZED IN ACCORDANCE WITH ASTM A-232.
5. SEE DWGS. 9 & 11 FOR LOCATION OF LIGHT STANDARDS.

## SUPERSTRUCTURE DETAILS

FAI 74 OVER L STREET  
FAI RTE. 74 SECTION (92-11VB)BR  
VERMILION COUNTY  
STATION 1877+01.73  
STRUCTURE NO. 092-0008(EB)  
STRUCTURE NO. 092-0009(WB)

**ESCA**  
CONSULTANTS, INC.

|              |     |       |
|--------------|-----|-------|
| DESIGNED BY: | KMR | 12-89 |
| DRAWN BY:    | WEM | 1-90  |
| CHECKED BY:  | RDP | 1-90  |
| APPROVED BY: | RDP | 1-90  |

|           |     |      |
|-----------|-----|------|
| DRAWN BY: | WEM | 1-90 |
|-----------|-----|------|

|             |     |      |
|-------------|-----|------|
| CHECKED BY: | RDP | 1-90 |
|-------------|-----|------|

APPROVED BY: RDP 1-90


STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

**FOR INFO ONLY – STRUCTURE DETAILS FOR  
LOCATIONS #1 & #2**

|        |         |      |        |      |        |
|--------|---------|------|--------|------|--------|
| SCALE: | SHEET 1 | OF 1 | SHEETS | STA. | TO STA |
|--------|---------|------|--------|------|--------|

|                           |         |                    |                 |              |
|---------------------------|---------|--------------------|-----------------|--------------|
| F.A.I.<br>RTE.            | SECTION | COUNTY             | TOTAL<br>SHEETS | SHEET<br>NO. |
| 74                        | *       | VERMILION          | 52              | 22           |
| D5 BRIDGE PAINTING 2020-1 |         | CONTRACT NO. 70E06 |                 |              |
| ILLINOIS                  |         | FED. AID PROJECT   |                 |              |








\*\*\*192-1118)BR

|                   |         |          |              |          |
|-------------------|---------|----------|--------------|----------|
| ROUTE NO          | SECTION | COUNTY   | TOTAL SHEETS | SHEET NO |
| 121-78            | 200 200 | Merriam  | 165          | 100      |
| STA               |         | TO STA   |              |          |
| FED ROAD DIST NO  |         | ILL NOIS | PROJECT      |          |
| Dwg. No. 19 of 41 |         |          |              |          |

1. SPLICE PLATES FOR FIELD SPLICES OF NEW BEAMS AND COVERPLATE RETROFITTING ARE SUBJECT TO NOTCH TOUGHNESS REQUIREMENTS.



| EXISTING BEAMS (W/COVER PLATES) | NEW BEAM (NO COVER PLATES) |
|---------------------------------|----------------------------|
| 1                               | 1                          |
| 2                               | 2                          |
| 3                               | 3                          |
| 4                               | 4                          |
| 5                               | 5                          |
| 6                               | 6                          |
| 7                               | 7                          |
| 8                               | 8                          |
| 9                               | 9                          |
| 10                              | 10                         |
| 11                              | 11                         |
| 12                              | 12                         |
| 13                              | 13                         |
| 14                              | 14                         |
| 15                              | 15                         |
| 16                              | 16                         |
| 17                              | 17                         |
| 18                              | 18                         |
| 19                              | 19                         |
| 20                              | 20                         |
| 21                              | 21                         |
| 22                              | 22                         |
| 23                              | 23                         |
| 24                              | 24                         |
| 25                              | 25                         |
| 26                              | 26                         |
| 27                              | 27                         |
| 28                              | 28                         |
| 29                              | 29                         |
| 30                              | 30                         |
| 31                              | 31                         |
| 32                              | 32                         |
| 33                              | 33                         |
| 34                              | 34                         |
| 35                              | 35                         |
| 36                              | 36                         |
| 37                              | 37                         |
| 38                              | 38                         |
| 39                              | 39                         |
| 40                              | 40                         |
| 41                              | 41                         |
| 42                              | 42                         |
| 43                              | 43                         |
| 44                              | 44                         |
| 45                              | 45                         |
| 46                              | 46                         |
| 47                              | 47                         |
| 48                              | 48                         |
| 49                              | 49                         |
| 50                              | 50                         |
| 51                              | 51                         |
| 52                              | 52                         |
| 53                              | 53                         |
| 54                              | 54                         |
| 55                              | 55                         |
| 56                              | 56                         |
| 57                              | 57                         |
| 58                              | 58                         |
| 59                              | 59                         |
| 60                              | 60                         |
| 61                              | 61                         |
| 62                              | 62                         |
| 63                              | 63                         |
| 64                              | 64                         |
| 65                              | 65                         |
| 66                              | 66                         |
| 67                              | 67                         |
| 68                              | 68                         |
| 69                              | 69                         |
| 70                              | 70                         |
| 71                              | 71                         |
| 72                              | 72                         |
| 73                              | 73                         |
| 74                              | 74                         |
| 75                              | 75                         |
| 76                              | 76                         |
| 77                              | 77                         |
| 78                              | 78                         |
| 79                              | 79                         |
| 80                              | 80                         |
| 81                              | 81                         |
| 82                              | 82                         |
| 83                              | 83                         |
| 84                              | 84                         |
| 85                              | 85                         |
| 86                              | 86                         |
| 87                              | 87                         |
| 88                              | 88                         |
| 89                              | 89                         |
| 90                              | 90                         |
| 91                              | 91                         |
| 92                              | 92                         |
| 93                              | 93                         |
| 94                              | 94                         |
| 95                              | 95                         |
| 96                              | 96                         |
| 97                              | 97                         |
| 98                              | 98                         |
| 99                              | 99                         |
| 100                             | 100                        |

### MOMENT TABLES (WB BRIDGE)

4'-6 1/4"

1 1/2" 8 Spd @ 3" x 2'-0" 8 Spd @ 3" x 2'-0" 1 1/2"

12"

2 1/4" 2 1/4" 2 1/4"

1/4" max. Opening

Flange Splice @ 12" x 4'-6 1/4" (Top & Bottom)

Web Splice @ 19" x 12" x 2'-8 1/4" (1 ea. side of web)

#36 x 135

1/4" x 12" x 2'-8 1/4" (1 ea. side of web)

1/4" x 135"

12"

1 1/2" 2'-8 1/4" 1 1/2"

1'-7"

|        |            |
|--------|------------|
| Pier 1 | Span 2, Pi |
|--------|------------|

FIELD SPLICE DETAIL  
(Req'd @ 3 Locations)

SUPERSTRUCTURE  
STEEL DETAILS

\_\_\_\_\_



| ITEM                           | UNIT   | QUANTITY |
|--------------------------------|--------|----------|
| Furnish & Erect Structural Stl | L. Sum | 1        |
| Stud Shear Connectors          | Each   | 5298     |
| Weld Peening                   | Each   | 24       |

**ESCA**  
CONSULTANTS, INC.

|              |     |      |
|--------------|-----|------|
| DESIGNED BY: | RDP | 1-90 |
| DRAWN BY:    | WEM | 1-90 |
| CHECKED BY:  | JRF | 2-90 |
| APPROVED BY: | RDP | 2-90 |

**FOR INFO ONLY – STRUCTURE DETAILS FOR  
LOCATIONS #1 & #2**




|        |         |      |        |      |         |
|--------|---------|------|--------|------|---------|
| SCALE: | SHEET 1 | OF 1 | SHEETS | STA. | TO STA. |
|--------|---------|------|--------|------|---------|

| F.A.I.<br>RTE.            | SECTION | COUNTY             | TOTAL<br>SHEETS | SHEET<br>NO. |
|---------------------------|---------|--------------------|-----------------|--------------|
| 74                        | *       | VERMILION          | 52              | 25           |
| D5 BRIDGE PAINTING 2020-1 |         | CONTRACT NO. 70E06 |                 |              |
| ILLINOIS FED. AID PROJECT |         |                    |                 |              |

```
MODEL: s.MODEL.NAMES
FILE NAME: pw:\planroom.dot\IllInols.gov:PWIDOT\Documents\IDOT_Offices\District_5\Projects\DS70E06\CADData\Design\DS70E06-shr-Details.dgn
```

092-0008 E.B.  
(1964 PLANS)

| F.A.I. RTE. NO.                           | SECTION  | COUNTY    | TOTAL SHEETS | SHEET NO. |
|-------------------------------------------|----------|-----------|--------------|-----------|
| 74                                        | 92-11 VB | VERMILION | 67           | 30        |
| FEDERAL ROAD DISTRICT NO. 7 ALABAMA PROJ. |          |           |              |           |



| TABLE OF SHEAR CONNECTOR SPACINGS |                               |      |                               |  |
|-----------------------------------|-------------------------------|------|-------------------------------|--|
| PART                              | SHEAR CONNECTOR 4"-7/8" STUDS | PART | SHEAR CONNECTOR 4"-7/8" STUDS |  |
| a                                 | 16 Spa. @ 0'-9"=12'-6"        | i    | 12 Spa. @ 1'-0"=12'-0"        |  |
| b                                 | 17 Spa. @ 1'-6"=25'-6"        | m    | 17 Spa. @ 1'-6"=25'-6"        |  |
| c                                 | 18 Spa. @ 1'-0"=18'-0"        | o    | 11 Spa. @ 1'-0"=11'-0"        |  |
| d                                 | 11'-8"                        | p    | 8'-3"                         |  |
| e                                 | 11'-5"                        | q    | 5'-3"                         |  |
| f                                 | 12 Spa. @ 0'-9"=9'-0"         | r    | 10 Spa. @ 1'-0"=10'-0"        |  |
| g                                 | 20 Spa. @ 0'-9"=15'-0"        | s    | 18 Spa. @ 1'-3"=22'-6"        |  |
| h                                 | 16 Spa. @ 1'-9"=28'-0"        | t    | 18 Spa. @ 0'-9"=13'-6"        |  |
| i                                 | 11 Spa. @ 1'-3"=13'-9"        |      |                               |  |
| j                                 | 11'-2"                        |      |                               |  |
| k                                 | 9'-9"                         |      |                               |  |

NOTES:

- Space 3 studs only at top of flange splice plates to avoid interference with flange bolts at field splices.
- Subject to adjustments due to
- For shear connector details see Sheets "Framing Plan No. 1 & No. 2 Left Bridge" & "Structural Steel Framing Plan".

| TABLE OF ELEVATIONS -- TOP OF STEEL BEAMS * |        |               |            |            |          |            |            |            |               |
|---------------------------------------------|--------|---------------|------------|------------|----------|------------|------------|------------|---------------|
| BRIDGE                                      | GIRDER | WEST ABUTMENT | PIER NO. 1 | SPAN NO. 2 |          | PIER NO. 2 | SPAN NO. 3 | PIER NO. 3 | EAST ABUTMENT |
|                                             |        |               |            | SPLICE     | SPLICE   |            | SPLICE     |            |               |
| RIGHT BRIDGE                                | A      | 669.3009      | 668.7236   | 668.5661   | 668.0117 | 667.8542   | 667.2468   | 667.1130   | 666.4911      |
|                                             | B      | 669.4079      | 668.8307   | 668.6732   | 668.1187 | 667.9512   | 667.3538   | 667.2201   | 666.5982      |
|                                             | C      | 669.4794      | 668.9022   | 668.7447   | 668.1902 | 668.0327   | 667.4253   | 667.2916   | 666.6696      |
|                                             | D      | 669.4794      | 668.9022   | 668.7447   | 668.1902 | 668.0327   | 667.4253   | 667.2916   | 666.6696      |
|                                             | E      | 669.4079      | 668.8307   | 668.6732   | 668.1187 | 667.9512   | 667.3538   | 667.2201   | 666.5982      |
|                                             | F      | 669.3009      | 668.7236   | 668.5661   | 668.0117 | 667.8542   | 667.2468   | 667.1130   | 666.4911      |

- NOTE: For fabrication use only, does not include deflections.
- \* Top of beam flanges without splice plates or coverplates elevations are at & of bearings, except as noted.

| COVERPLATE DIMENSIONS |           |       |        |        |        |           |           |
|-----------------------|-----------|-------|--------|--------|--------|-----------|-----------|
| NO.                   | THICKNESS | WIDTH | A      | B      | C      | WELD SIZE | NO. REQ'D |
| P1                    | 3/4"      | 10"   | 16'-6" | 8'-3"  | 6'-9"  | 1/4"      | 12        |
| P2                    | 5/8"      | 10"   | 14'-6" | 7'-3"  | 5'-9"  | 1/4"      | 12        |
| P3                    | 7/16"     | 10"   | 23'-0" | 11'-6" | 10'-0" | 3/16"     | 6         |

|                                         |       |        |                   |          |       |
|-----------------------------------------|-------|--------|-------------------|----------|-------|
| CONSOER, TOWNSEND & ASSOCIATES          |       |        |                   |          |       |
| CONSULTING ENGINEERS                    |       |        | CHICAGO, ILLINOIS |          |       |
| ILLINOIS DIVISION OF HIGHWAYS           |       |        |                   |          |       |
| FAI RT. 74 OVER GENERAL REFRATORIES CO. |       |        |                   |          |       |
| R.R. & "L" ST. SECTION 92-11VB          |       |        |                   |          |       |
| VERMILION COUNTY                        |       |        | STA. 1877+01.73   |          |       |
| FRAMING PLAN                            |       |        |                   |          |       |
| SPANS NO.1-NO.4 RIGHT BRIDGE            |       |        |                   |          |       |
| DESIGNED                                | DRAWN | TRACED | CHECKED           | REVIEWED | DATE  |
| LS                                      | LS    |        | LDB               | HSM      | Oct62 |

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION


FOR INFO ONLY - STRUCTURE DETAILS FOR  
LOCATIONS #1 & #2

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.


| F.A.I. RTE.                                  | SECTION | COUNTY    | TOTAL SHEETS | SHEET NO. |
|----------------------------------------------|---------|-----------|--------------|-----------|
| 74                                           |         | VERMILION | 52           | 26        |
| D5 BRIDGE PAINTING 2020-1 CONTRACT NO. 70E06 |         |           |              |           |
| ILLINOIS FED. AID PROJECT                    |         |           |              |           |

092-0009 W.B.  
(1964 PLANS)


| F.A.I. R.T.                 | SECTION  | COUNTY    | TOTAL SHEETS | SHEET NO. |
|-----------------------------|----------|-----------|--------------|-----------|
| 74                          | 92-11 VB | VERMILION | 67           | 26        |
| FEDERAL ROAD DISTRICT NO. 7 |          |           |              |           |
| ILLINOIS PROJ.              |          |           |              |           |



FRAMING PLAN LEFT BRIDGE  
SPAN #1 & #2




SHEAR CONNECTOR SPACING  
SHEAR CONNECTORS ARE INCLUDED IN QUANTITY OF STRUCTURAL STEEL  
EST. WT. = 7,537 LBS.



SHEAR CONNECTOR

| TABLE OF SHEAR CONNECTOR SPACINGS |        |             |           |                                           |           | ELEVATIONS TOP OF STEEL BEAM* |            |            |
|-----------------------------------|--------|-------------|-----------|-------------------------------------------|-----------|-------------------------------|------------|------------|
| SPAN                              | GIRDER | SPAN LENGTH | SPACING a | SHEAR CONNECTOR 4" x 7/8" STUDS SPACING b | SPACING c | WEST ABUTMENT                 | PIER NO. 1 | PIER NO. 2 |
| SPAN NO. 1                        | G      | 72'-6 1/4   | 0'-3 1/8  | 20 @ 1'-0                                 | 10 @ 1'-6 | 669.556                       | 669.965    |            |
|                                   | H      | do          | 0'-3 1/8  | 20 @ 1'-0                                 | 10 @ 1'-6 | 669.700                       | 669.115    |            |
|                                   | I      | do          | do        | do                                        | do        | 669.812                       | 669.234    |            |
|                                   | J      | do          | do        | do                                        | do        | 669.855                       | 669.283    |            |
|                                   | K      | do          | do        | do                                        | do        | 669.827                       | 669.262    |            |
|                                   | L      | do          | do        | do                                        | do        | 669.740                       | 669.181    |            |
|                                   | M      | do          | do        | do                                        | do        | 669.648                       | 669.093    |            |
|                                   | N      | 72'-6 1/4   | 0'-3 1/8  | 20 @ 1'-0                                 | 10 @ 1'-6 | 669.575                       | 669.029    |            |
| SPAN NO. 2                        | G      | 53'-2 7/16  | 0'-7 1/4  | 13 @ 1'-0                                 | 8 @ 1'-6  |                               | 668.952    | 668.464    |
|                                   | H      | 58'-6 1/4   | 0'-3 1/8  | 16 @ 1'-0                                 | 8 @ 1'-6  |                               | 669.102    | 668.567    |
|                                   | I      | 63'-10      | 0'-5      | 20 @ 1'-0                                 | 7 @ 1'-6  |                               | 669.222    | 668.641    |
|                                   | J      | 69'-1 3/4   | 0'-6 7/8  | 18 @ 1'-0                                 | 10 @ 1'-6 |                               | 669.271    | 668.644    |
|                                   | K      | 74'-5 9/16  | 0'-2 3/4  | 21 @ 1'-0                                 | 10 @ 1'-6 |                               | 669.250    | 668.578    |
|                                   | L      | 78'-9 5/16  | 0'-4 5/8  | 22 @ 1'-0                                 | 11 @ 1'-6 |                               | 669.169    | 668.453    |
|                                   | M      | 85'-1 1/8   | 0'-6 9/16 | 23 @ 1'-0                                 | 12 @ 1'-6 |                               | 669.062    | 668.321    |
|                                   | N      | 90'-4 7/8   | 0'-2 7/16 | 17 @ 1'-0                                 | 16 @ 1'-6 |                               | 669.018    | 668.214    |

NOTE: Elevations top of steel for fabrication use only, does not include deflections.  
\* Elevations are at & of bearings.



COVER PLATE DETAIL

| COVER PLATE DIMENSIONS |           |       |       |       |       |           |            |
|------------------------|-----------|-------|-------|-------|-------|-----------|------------|
| NR                     | THICKNESS | WIDTH | A     | B     | C     | WELD SIZE | NO. REQ'D. |
| P4                     | 5/8"      | 11"   | 40'-0 | 20'-0 | 18'-6 | 1/4"      | 2          |
| P5                     | 5/8"      | 11"   | 40'-0 | 20'-0 | 18'-6 | 1/4"      | 6          |
| P6                     | 5/8"      | 11"   | 35'-0 | 17'-6 | 16'-0 | 1/4"      | 1          |
| P7                     | 1/2"      | 11"   | 32'-0 | 11'-0 | 9'-6  | 1/4"      | 1          |
| P8                     | 1/2"      | 11"   | 20'-0 | 10'-0 | 8'-6  | 1/4"      | 1          |
| P9                     | 1/2"      | 10"   | 42'-6 | 21'-3 | 20'-9 | 1/4"      | 1          |
| P10                    | 7/16"     | 10"   | 33'-0 | 16'-6 | 15'-0 | 1/4"      | 1          |
| P11                    | 7/16"     | 10"   | 20'-0 | 10'-0 | 8'-6  | 1/4"      | 1          |

CONSOER, TOWNSEND & ASSOCIATES  
CONSULTING ENGINEERS CHICAGO, ILLINOIS  
ILLINOIS DIVISION OF HIGHWAYS  
FAI RT. 74 OVER GENERAL REFRACTORIES CO.  
R.R. B "L" ST. SECTION 92-11VB  
VERMILION COUNTY STA. 1877+01.73  
FRAMING PLAN  
SPANS NO.1 & NO.2 LEFT BRIDGE  
DESIGNED DRAWN CHECKED REVIEWED DATE  
ST ST TRACED LDB HSM Oct.62

|                              |            |           |
|------------------------------|------------|-----------|
| USER NAME = dawsonkb         | DESIGNED - | REVISED - |
| PLOT SCALE = 40,0000 ' / in. | DRAWN -    | REVISED - |
| PLOT DATE = 8/15/2019        | CHECKED -  | REVISED - |
|                              | DATE -     | REVISED - |

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION


FOR INFO ONLY - STRUCTURE DETAILS FOR  
LOCATIONS #1 & #2

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

| F.A.I. RTE.                                  | SECTION | COUNTY    | TOTAL SHEETS | SHEET NO. |
|----------------------------------------------|---------|-----------|--------------|-----------|
| 74                                           |         | VERMILION | 52           | 27        |
| D5 BRIDGE PAINTING 2020-1 CONTRACT NO. 70E06 |         |           |              |           |
| ILLINOIS FED. AID PROJECT                    |         |           |              |           |

092-0009 W.B.  
(1964 PLANS)

| F.A.I. RTE. NO.             | SECTION  | COUNTY    | TOTAL SHEETS | SHEET NO. |
|-----------------------------|----------|-----------|--------------|-----------|
| 74                          | 92-11 VB | VERMILION | 67           | 29        |
| FEDERAL ROAD DISTRICT NO. 7 |          |           |              |           |



FRAMING PLAN - LEFT BRIDGE  
SPANS NO. 3, NO. 4 & NO. 5

| TABLE OF ELEVATIONS - TOP OF STEEL BEAMS <sup>(1)</sup> |            |            |            |          |            |               |
|---------------------------------------------------------|------------|------------|------------|----------|------------|---------------|
| BRIDGE GIRDER                                           | PIER NO. 2 | PIER NO. 3 | SPAN NO. 4 |          | PIER NO. 4 | EAST ABUTMENT |
|                                                         |            |            | SPLICE     | SPLICE   |            |               |
| Q                                                       | 668.3815   | 667.8490   | 667.7152   | 667.2416 | 667.1078   | 666.4859      |
| R                                                       | 668.4951   | 667.9525   | 667.8188   | 667.3452 | 667.2114   | 666.5894      |
| I                                                       | 668.5584   | 668.0258   | 667.8921   | 667.4184 | 667.2847   | 666.6627      |
| J                                                       | 668.5621   | 668.0295   | 667.8957   | 667.4221 | 667.2883   | 666.6664      |
| K                                                       | 668.4951   | 667.9835   | 667.8298   | 667.3561 | 667.2224   | 666.6004      |
| L                                                       | 668.3711   | 667.8385   | 667.7048   | 667.2311 | 667.0974   | 666.4755      |
| M                                                       | 668.2392   | 667.7066   | 667.5728   | 667.0992 | 666.9654   | 666.3435      |
| N                                                       | 668.1315   | 667.5990   | 667.4652   | 666.9916 | 666.8578   | 666.2359      |

NOTES: For fabrication use only, does not include deflections.  
1. Top of beam flanges without splice plates elevations are at & of bearings, except as noted.

|                                                                                                             |             |        |                |                 |                 |
|-------------------------------------------------------------------------------------------------------------|-------------|--------|----------------|-----------------|-----------------|
| CONSOER, TOWNSEND & ASSOCIATES<br>CONSULTING ENGINEERS<br>CHICAGO, ILLINOIS                                 |             |        |                |                 |                 |
| ILLINOIS DIVISION OF HIGHWAYS<br>F&I RT. 74 OVER GENERAL REFRACTORIES CO.<br>R.R. & "L" ST. SECTION 92-11VB |             |        |                |                 |                 |
| VERMILION COUNTY STA. 1877+01.73                                                                            |             |        |                |                 |                 |
| FRAMING PLAN<br>SPANS NO.3 - NO.5 LEFT BRIDGE                                                               |             |        |                |                 |                 |
| DESIGNED<br>ST                                                                                              | DRAWN<br>ST | TRACED | CHECKED<br>LDB | REVIEWED<br>HSM | DATE<br>Oct. 62 |

|                              |            |           |
|------------------------------|------------|-----------|
| USER NAME = dawsonkb         | DESIGNED - | REVISED - |
| PLOT SCALE = 40,0000 ' / in. | DRAWN -    | REVISED - |
| PLOT DATE = 8/15/2019        | CHECKED -  | REVISED - |
|                              | DATE -     | REVISED - |

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION


FOR INFO ONLY - STRUCTURE DETAILS FOR  
LOCATIONS #1 & #2

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

| F.A.I. RTE.                                  | SECTION | COUNTY    | TOTAL SHEETS | SHEET NO. |
|----------------------------------------------|---------|-----------|--------------|-----------|
| 74                                           |         | VERMILION | 52           | 28        |
| D5 BRIDGE PAINTING 2020-1 CONTRACT NO. 70E06 |         |           |              |           |
| ILLINOIS FED. AID PROJECT                    |         |           |              |           |




092-0009 W.B.



LEFT BRIDGE

092-0009 W.B.



7/8"  $\phi$  x 4" Granular  
Flux-filled or  
Solid Studs

3"  
1 1/2"  
2 3/4"  
2 1/2"  
3 1/2"  
1'-0"

Flange Splice Pl.

4'-6 1/4"

1 1/2" 8 SP. # 3" x 2'-0" 31 1/4" 8 SP. # 3" x 2'-0" 1 1/2"

SP. PLATE

12" x 13 1/8" x 4'-5 1/4"

1/4" MAX. OPENING

7/8" # Rivet


1'-0"

2 3/4" 3 3/4" 2 3/4"


FIELD SPLICE DETAIL  
34 REQUIRED

[illegible]

45 - D2 DIAPHR.  
42 - D4 DIAPHR.  
2 - D9 DIAPHR.



15 - D3 DIAPHR.  
14 - D5 DIAPHR.



11'


5' 11 1/2"

36' 13 1/2"

D1 & D8 Diaphr.  
12' 40"

B

SECTION A-A  
D1 & D6 DIAPHR.



10 - D1 DIAPHR.

RIGHT BRIDGE  
092-0008 E.B.


|                                          |       |        |                   |                 |         |          |
|------------------------------------------|-------|--------|-------------------|-----------------|---------|----------|
| CONSOER, TOWNSEND & ASSOCIATES           |       |        |                   |                 |         |          |
| CONSULTING ENGINEERS                     |       |        | CHICAGO, ILLINOIS |                 |         |          |
| ILLINOIS DIVISION OF HIGHWAYS            |       |        |                   |                 |         |          |
| FAI RT. 74 OVER GENERAL REFRACTORIES CO. |       |        |                   |                 |         |          |
| R. R. B "L" ST. SECTION 92-11VB          |       |        |                   |                 |         |          |
| VERMION COUNTY                           |       |        |                   | STA. 1877+01.73 |         |          |
| STRUCTURAL STEEL FRAMING DETAILS         |       |        |                   |                 |         |          |
| DESIGNED                                 | DRAWN | TRACED | CHECKED           | REVIEWED        | DATE    | REVIEWED |
| LS                                       | EG    |        | LDB               | HSM             | Oct. 62 |          |

|                           |         |                    |                 |              |
|---------------------------|---------|--------------------|-----------------|--------------|
| F.A.I.<br>RTE.            | SECTION | COUNTY             | TOTAL<br>SHEETS | SHEET<br>NO. |
| 74                        | *       | VERMILION          | 52              | 29           |
| D5 BRIDGE PAINTING 2020-1 |         | CONTRACT NO. 70E06 |                 |              |
| ILLINOIS                  |         | FED. AID PROJECT   |                 |              |




Note: The 1/8" TFE sheet shall be bonded directly to the top steel plate with a two-component, medium viscosity epoxy resin, conforming to the requirements of the Federal Specification MM-A-134, Type I. The bond agent shall be applied on the full area of the contact surfaces.

Bonding of 1/8" TFE sheet during vulcanizing process will be permitted provided the process and method of adjusting assembly height is approved by the Engineer.




### SETTING ANCHOR BOLTS AT TYPES II & III EXP. BRG'S


D=1/4" per each 100' of expansion for every 15° temp. change from the normal temp. of 50°F.



PLAN - TOP PLATE





ELEVATION




PLAN - BOTTOM PLATE

### STEEL PEDESTALS AT TYPES II & III EXPANSION BEARINGS

(FOR USE AT EXP. BRGS. -  
SEE DWG. NO. 21)



PLAN-TFE SURFACE



SECTION THRU TFE

### FILL PLATE THICKNESS TABLE

| BEAM | W. ABUT. | PIER 1 | PIER 3  | M. ABUT. |
|------|----------|--------|---------|----------|
| 1    | 3/8"     | 5/16"  | 1 5/16" | 3/16"    |
| 2    | 3/8"     | 5/16"  | 1 5/16" | 3/16"    |
| 3    | 3/8"     | 5/16"  | 1 5/16" | 3/16"    |
| 4    | 3/8"     | 5/16"  | 1 5/16" | 3/16"    |
| 5    | 3/8"     | 5/16"  | 1 5/16" | 3/16"    |
| 6    | 3/8"     | 5/16"  | 1 5/16" | 3/16"    |
| 7    | 3/8"     | 3/16"  | 1/8"    | 1 5/16"  |

| BEAM | W. ABUT. | PIER 1  | PIER 2 | PIER 4 | E. ABUT. |
|------|----------|---------|--------|--------|----------|
| 8    | 3/16"    | 11/16"  | 2 1/8" | 1 3/8" | 3/16"    |
| 9    | 3/16"    | 1/2"    | 2 1/8" | 1 3/8" | 3/16"    |
| 10   | 3/16"    | 1/2"    | 2 1/8" | 1 3/8" | 3/16"    |
| 11   | 3/16"    | 13/16"  | 5/16"  | 1 3/8" | 3/16"    |
| 12   | 3/16"    | 1 1/16" | 5/16"  | 1 3/8" | 3/16"    |
| 13   | 3/16"    | 1/2"    | 5/16"  | 1 3/8" | 3/16"    |
| 14   | 3/16"    | 1/2"    | 5/16"  | 1 3/8" | 3/16"    |
| 15   | 3/16"    | 1/2"    | 5/16"  | 1 3/8" | 3/16"    |

NOTE: FILL PLATE THICKNESSES  
SHOWN MAY BE THE SUM  
OF TWO FILL PLATES.

### STEEL PEDESTAL DIMENSIONS

| LOCATION    | # REQ'D | a          | b      | c        | d    | e      | f        | g      | h        | i      | j  | k         |
|-------------|---------|------------|--------|----------|------|--------|----------|--------|----------|--------|----|-----------|
| E. ABUT. EB | 7       | 1'-10 1/2" | 8"     | 2"       | 5"   | 6 1/4" | 5 5/8"   | 1 3/8" | 8 1/2"   | 4"     | 4" | 1'-8 1/2" |
| E. ABUT. WB | 8       | 1'-10 1/2" | 8"     | 2"       | 5"   | 6 1/4" | 5 5/8"   | 1 3/8" | 8 1/2"   | 4"     | 4" | 1'-8 1/2" |
| PIER 2 WB   | 8       | 1'-2"      | 8"     | 3"       | 5/8" | 6 3/8" | 9 1/16"  | -      | 11 1/16" | 4"     | -  | 1'-2"     |
| W. ABUT. EB | 7       | 1'-10 1/2" | 8"     | 2"       | 5"   | 6 1/4" | 5 7/8"   | 1 3/8" | 8 3/4"   | 4"     | 4" | 1'-8 1/2" |
| W. ABUT. WB | 8       | 1'-2"      | 10"    | 3"       | 5/8" | 6 3/8" | 8 3/8"   | -      | 10 3/8"  | 5"     | -  | 1'-2"     |
| PIER 3 EB   | 7       | 1'-4"      | 11"    | 4"       | 5/8" | 7 3/8" | 6 11/16" | -      | 8 11/16" | 5 1/2" | -  | 1'-4"     |
| PIER 4 WB   | 8       | 1'-4"      | 11"    | 4"       | 5/8" | 7 3/8" | 6 11/16" | -      | 8 11/16" | 5 1/2" | -  | 1'-4"     |
| PIER 1 WB   | ① 5     | 1'-6"      | 11"    | 5"       | 5/8" | 8 3/8" | 6 1/16"  | -      | 8 1/16"  | 5 1/2" | -  | 1'-6"     |
| PIER 1 EB   | ② 3     | 1'-6"      | 11"    | 2 11/16" | 5/8" | 8 3/8" | 6 1/16"  | -      | 8 1/16"  | 5 1/2" | -  | 1'-6"     |
| PIER 1 WB   | 7       | 1'-8"      | 1'-11" | 6"       | 5/8" | 9 3/8" | 6 11/16" | -      | 8 11/16" | 6 1/2" | -  | 1'-8"     |

① Beams 11 Thru 15

② Beams 8 Thru 10






PLATE P1  
(1 Req'd)  
(Top Plate & New  
Beam - Pier 2 EB)



PINTLE  
(2 Req'd)



BOLSTER R1  
(1 Req'd) (New Beam  
- Pier 2 Eastbound)






PLATE P2  
(2 Req'd)

ELEVATION AT FIXED BEARING

### FIXED BEARINGS



PLAN - TOP PLATE



ELEVATION



PLAN - BOTTOM PLATE

### STEEL PEDESTALS AT TYPE I EXPANSION BEARINGS

(FOR USE AT EXP. BRGS. - SEE DWG. NO. 21)

### PROCEDURE

- THE CONTRACTOR SHALL SUBMIT FOR APPROVAL BY THE ENGINEER, PLANS FOR RAISING EXISTING BEAMS, PROVIDING NEW EXPANSION BEARINGS AND SHIMMING EXISTING FIXED BEARINGS PRIOR TO COMMENCING ANY RELATED WORK. THIS WORK SHALL BE DONE FOR EACH STAGE AFTER EXISTING CONCRETE DECK IS REMOVED AND PRIOR TO POURING OF NEW CONCRETE DECK. THE MAXIMUM DEAD LOAD REACTION PER BEAM (WEIGHT OF STEEL ONLY) AT ABUTMENTS IS 7 kips AND AT PIERS IS 16 kips.
- DIAPHRAGMS ALONG THE STAGE CONSTRUCTION LINE SHALL BE DISCONNECTED BEFORE RAISING OPERATIONS COMMENCE. ALL NUTS ON BEARING ANCHOR BOLTS ON BEAMS TO BE RAISED SHALL BE REMOVED AND REPLACED. (CUT OFF ANCHOR BOLTS FLUSH WITH BEG. SEAT AT ALL BEARINGS EXCEPT THE EB ABUTMENTS AND THE E. ABUT. WB. ANCHOR BOLTS AT THESE LOCATIONS ARE TO BE PRESERVED AND REUSED. SEE NOTE 6.)
- RAISING SHALL BE DONE BY JACKING. MEASURES SHALL BE TAKEN TO PREVENT LATERAL OR LONGITUDINAL DISPLACEMENT OF BEAMS DURING RAISING OPERATIONS. ALL BEAMS FOR EACH STAGE AT A GIVEN SUB-STRUCTURE ELEMENT SHALL BE SLOWLY AND CONTINUALLY RAISED THE SAME AMOUNT SIMULTANEOUSLY, WITH THE MAXIMUM AMOUNT OF RAISE LIMITED TO 1" GREATER THAN THAT REQUIRED TO INSTALL NEW BEARINGS OR SHIM PLATES. ANY SWAY OF THE STEEL DURING RAISING OPERATIONS SHALL BE IMMEDIATELY CORRECTED.
- DIAPHRAGMS MAY BE USED AS JACKING BEAMS. IF SO, JACKS SHALL BE PLACED AT THE MIDPOINT OF THE DIAPHRAGM, ON THE CENTERLINE OF BEARING. THE STEEL SHALL BE RAISED IN INCREMENTS OF 1/2" AND SHALL BE BLOCKED IN POSITION UPON COMPLETION OF A RAISING INTERVAL. TIMBER BLOCKING MAY BE USED TO HOLD THE STRUCTURE IN PLACE WHILE JACKS ARE REPOSITIONED FOR THE NEXT LIFT.
- PRIOR TO RAISING, ELEVATIONS OF EXISTING BEARING SEATS SHALL BE TAKEN AND THE ENGINEER SHALL VERIFY FILL PLATE AND SHIM PLATE THICKNESSES REQUIRED AT EACH BEARING. THIS SHALL BE ACCOMPLISHED BY USING FIELD MEASUREMENTS ALONG WITH THE "TABLE OF ELEVATIONS - TOP OF STEEL BEAMS" ON DWG. NOS. 17 AND 18.
- RAISE BEAMS, REMOVE EXISTING EXPANSION BEARINGS, INSTALL NEW SHIM PLATES AND PLATES P2 OR P3 UNDER EXISTING FIXED BEARINGS, AND INSTALL NEW ELASTOMERIC EXPANSION BEARINGS. INSTALL NEW ANCHOR BOLTS WHERE REQUIRED (SEE DWG. NO. 39), AND PLACE AND TIGHTEN NUTS ON NEW AND EXISTING ANCHOR BOLTS.
- AFTER WORK ON THE BEARINGS IS COMPLETE, REPAINT ANY AREAS DISTURBED BY WELDINGS, ETC. WITH THE SAME PAINT SYSTEM SPECIFIED FOR THE STRUCTURAL STEEL.

### NOTES

- PORTIONS OF EXISTING FIXED BEARINGS TO BE REUSED IN NEW CONSTRUCTION.
- SEE DWG. NO. 39 FOR ANCHOR BOLT DETAILS.
- ANCHOR BOLTS AT FIXED BEARINGS MAY BE BUILT INTO THE MASONRY.
- THE NEW STEEL PEDESTALS, FILL PLATES & SIDE RESTAINERS FOR EXP. BRGS. AS WELL AS THE NEW PLATES P2 & SHIM PLATES UNDER EXISTING FIXED BEARINGS AND NEW PLATES P1 & P2 AND BOLSTERS R1 FOR NEW FIXED BEARINGS ARE INCLUDED IN "FURNISHING & ERECTING STRUCTURAL STEEL."
- SEE DWG. NO. 21 FOR DETAILS OF ELASTOMERIC EXPANSION BEARINGS.

\* FIELD VERIFY; SEE NOTE 5 UNDER  
"PROCEDURE" THIS DWG.

### SHIM PLATE THICKNESS TABLE

| BEAM NO. | PIER 1   | PIER 2 | PIER 3 |
|----------|----------|--------|--------|
| 1        | -        | 13/16" | -      |
| 2        | -        | 13/16" | -      |
| 3        | -        | 13/16" | -      |
| 4        | -        | 13/16" | -      |
| 5        | -        | 13/16" | -      |
| 6        | -        | 13/16" | -      |
| 7        | -        | 5/16"  | -      |
| 8        | 1 11/16" | 11/16" | 13/16" |
| 9        | 1 1/2"   | 11/16" | 13/16" |
| 10       | 1 1/2"   | 11/16" | 13/16" |
| 11       | 1 1/4"   | 7/8"   | 13/16" |
| 12       | 1 1/2"   | 7/8"   | 13/16" |
| 13       | 15/16"   | 7/8"   | 13/16" |
| 14       | 15/16"   | 7/8"   | 13/16" |
| 15       | 15/16"   | 7/8"   | 13/16" |

### BEARINGS

FAI 74 OVER L STREET  
FAI RTE. 74 SECTION (92-11VB)BR  
VERMILION COUNTY  
STATION 1877+01.73  
STRUCTURE NO. 092-0008(EB)  
STRUCTURE NO. 092-0009(WB)









STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FOR INFO ONLY - STRUCTURE DETAILS FOR  
LOCATIONS #1 & #2

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

| F.A.I.<br>RTE.            | SECTION | COUNTY    | TOTAL<br>SHEETS    | SHEET<br>NO. |
|---------------------------|---------|-----------|--------------------|--------------|
| 74                        | *       | VERMILION | 52                 | 30           |
| D5 BRIDGE PAINTING 2020-1 |         |           | CONTRACT NO. 70E06 |              |
|                           |         | ILLINOIS  | FED. AID PROJECT   |              |

|                              |            |           |
|------------------------------|------------|-----------|
| USER NAME = dawsonkb         | DESIGNED - | REVISED - |
|                              | DRAWN -    | REVISED - |
| PLOT SCALE = 40,0000 ' / in. | CHECKED -  | REVISED - |
| PLOT DATE = 8/15/2019        | DATE -     | REVISED - |



| BILL OF MATERIAL                    |      |          |
|-------------------------------------|------|----------|
| ITEM                                | UNIT | QUANTITY |
| Elastomeric Brg. Assembly, Type I   | Each | 40       |
| Elastomeric Brg. Assembly, Type II  | Each | 15       |
| Elastomeric Brg. Assembly, Type III | Each | 7        |


NOTES

1. SEE DWG. NO. 20 FOR DETAILS OF STEEL PEDESTALS, TABLE OF FILL PLATE THICKNESSES, AND OTHER MISCELLANEOUS DETAILS.
2. SEE DWG. NO. 39 FOR DETAILS OF NEW ANCHOR BOLTS


| "X" DIMENSIONS |        |
|----------------|--------|
| BEARING        | "X"    |
| 7" x 12"       | 5 3/4" |
| 9" x 12"       | 6 1/2" |
| 10" x 14"      | 7 1/4" |
| 12" x 18"      | 7 1/2" |

**ELASTOMERIC BEARINGS**  
**FAI 74 OVER L STREET**  
**FAI RTE. 74 SECTION (92-11VB)BR**  
**VERMILION COUNTY**  
**STATION 1877+01.73**  
**STRUCTURE NO. 092-0008(EB)**  
**STRUCTURE NO. 092-0009(WB)**

BENCHMARK: PERMANENT SURVEY MARKER, LYNCH ROAD STATION  
349+00, ELEVATION 658.07  
EXISTING STRUCTURE: STRUCTURES NUMBERED 092-0025 AND  
092-0026 WERE BUILT IN 1962 AS FAI 74, SECTION 92-12HB-6.  
REPAIRS PERFORMED IN 1977 INCLUDED DECK PATCHING, EXP-  
ANSION DEVICE RECONSTRUCTION, INSTALLATION OF WATERPROOF-  
ING MEMBRANE SYSTEM, AND BITUMINOUS OVERLAY. EACH STRUCT-  
URE CONSISTS OF A THREE SPAN CONTINUOUS NON-COMPOSITE  
STEEL BEAM AND REINFORCED CONCRETE DECK SUPERSTRUCTURE  
WITH FILL BEAT ABUTMENTS AND FILL SUPPORTED MULTIPLE  
COLLIER PILES. OVERALL LENGTH IS 157'-6-3/4" AND CLEAR  
ROADWAY WIDTH IS 30'-0" FOR STRUCTURE NO. 092-0025 AND  
VARIES FROM 31'-4-3/8" TO 37'-3" FOR STRUCTURE NO. 092-  
0026. TRAFFIC TO BE MAINTAINED UTILIZING STAGE CONSTRUCTION.  
HANDRAIL TO BE SALVAGED. BRIDGE CONTRACTOR TO  
STOCKPILE HANDRAIL ON STATE ROW FOR REMOVAL BY DISTRICT  
MAINTENANCE FORCES.



ELEVATION  
(EB Shown, WB Similar)



PLAN

FAI 74 CURVE DATA

PC Sta 2213 + 25.95  
 $\Delta = 18^{\circ}-02'-45''$   
 $R = 5729.50$   
 $T = 807.57$   
 $L = 1604.58$   
 $D = 1^{\circ}-00'$   
 $SE = 0.01\%$

LYNCH ROAD CURVE DATA


P.I. Sta 350 + 51.85  
 $\Delta = 10^{\circ}-43'-47''$   
 $R = 1617.00'$   
 $T = 151.85'$   
 $L = 302.81'$   
 $D = 3^{\circ}-22'-36''$

LEGEND


F = Fixed Brg.  
E = Exp. Brg.  
PGL = Profile Grade Line  
B = Boring Location

**ESCA**  
CONSULTANTS, INC.

DESIGNED BY: RDP 9-89  
DRAWN BY: WEM 9-89  
CHECKED BY: LRF 10-89  
APPROVED BY: RDP 10-89



FAI 74 PROFILE GRADE  
(Exist TPO Conc. Along & Pavement Shown;  
For Proposed Bridge Elevation, add 0.25')



LYNCH ROAD PROFILE GRADE  
(Along Edge of Median)

DESIGN SPECIFICATIONS

AASHTO 1989 and applicable Interims (1990)  
and Seismic Retrofitting Guidelines for Highway Bridges.

LOADING

HS20-44 & ALTERNATE MILITARY,  
WITH ALLOWANCE FOR 25 psf  
FUTURE WEARING SURFACE

DESIGN STRESSES (NEW CONSTRUCTION)


$f'_c = 3,500$  psi  
 $f_y = 40,000$  psi (REINF. BARS)  
 $f_y = 36,000$  psi (A-183 STEEL, ETL.) (COMPOSITE)

DESIGN STRESSES (EXIST. CONST.)


$f'_c = 3,500$  psi  
 $f_y = 40,000$  psi (REINF. BARS)  
 $f_y = 20,000$  psi (REINF. BARS)  
 $f_y = 18,000$  psi (STEEL, ETL.) -  
NON-COMPOSITE

APPROVED  
FOR STRUCTURAL ANALYSIS

*Ralph E. Underwood*



LOCATION SKETCH



SECTION A-A

**GENERAL PLAN  
& ELEVATION**  
FAI 74 OVER LYNCH ROAD  
FAI RTE. 74 SECTION 92-12HB-6BR  
VERMILION COUNTY  
STATION 2213+83.36  
STRUCTURE NO. 092-0025(WB)  
STRUCTURE NO. 092-0026(EB)

| ROUTE NO.           | SECTION  | COUNTY           | TOTAL SHEETS | SHEET NO. |
|---------------------|----------|------------------|--------------|-----------|
| FAI 74              | 92       | Vermilion        | 118          | 63        |
| STA.                | TO STA.  | PROJECT          |              |           |
| PER. ROAD DIST. NO. | ILLINOIS | PROJECT          |              |           |
|                     |          | Dwg. No. 1 of 34 |              |           |

1 (32-12HB-6) BR

STATION 2213+83.36  
BUILT 1962 BY  
STATE OF ILLINOIS  
FAIRTE. 74 SECTION 92-12HB-6BR  
LOADING HS20 & ALT.  
STR. NO. 092-0025

WESTBOUND

STATION 2213+83.36  
BUILT 1962 BY  
STATE OF ILLINOIS  
FAI RTE. 74 SECTION 92-12HB-6BR  
LOADING HS20 & ALT.  
STR. NO. 092-0026

EASTBOUND

**NEW NAME PLATES  
(1 EA REQ'D)**  
(SEE STD. 2113)

*Notes*  
Salvage Existing Name Plates and  
Mount Adjacent to New Name  
Plates on New Parapet as shown  
on Std. 2113. The cost of salvaging  
& incorporating exist. Name Plates  
into new work is incidental to  
Name Plates.

092-0025 W.B.

092-0026 E.B.



STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FOR INFO ONLY - STRUCTURE DETAILS FOR  
LOCATIONS #3 & #4

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.


| F.A.I. RTE. | SECTION                   | COUNTY             | TOTAL SHEETS | SHEET NO. |
|-------------|---------------------------|--------------------|--------------|-----------|
| 74          |                           | VERMILION          | 52           | 32        |
|             | D5 BRIDGE PAINTING 2020-1 | CONTRACT NO. 70E06 |              |           |
|             | ILLINOIS                  | FED. AID PROJECT   |              |           |






|                  |       |            |           |                              |                                       |                           |                  |                    |              |           |
|------------------|-------|------------|-----------|------------------------------|---------------------------------------|---------------------------|------------------|--------------------|--------------|-----------|
| DESIGNED BY: RDP | 9-89  | DESIGNED - | REVISED - | STATE OF ILLINOIS            | FOR INFO ONLY - STRUCTURE DETAILS FOR | F.A.I. RTE.               | SECTION          | COUNTY             | TOTAL SHEETS | SHEET NO. |
| DRAWN BY: WEM    | 9-89  | DRAWN -    | REVISED - | DEPARTMENT OF TRANSPORTATION | LOCATIONS #3 & #4                     | 74                        | *                | VERMILION          | 52           | 33        |
| CHECKED BY: JRF  | 11-89 | CHECKED -  | REVISED - |                              |                                       | D5 BRIDGE PAINTING 2020-1 |                  | CONTRACT NO. 70E06 |              |           |
| APPROVED BY: RDP | 11-89 | DATE -     | REVISED - |                              |                                       | ILLINOIS                  | FED. AID PROJECT |                    |              |           |





**PLAN**  
 092-0025 W.B.



**CROSS SECTION**  
 (LOOKING WEST)

**NOTES**

- SEE DWG. NO. 11 FOR SECTION A-A AND PARAPET REINFORCEMENT.
- BARS INDICATED THUS: 47x5-85, ETC., INDICATES 47 LINES OF BARS WITH 5 LENGTHS PER LINE.
- REINFORCEMENT BARS DESIGNATED (N) SHALL BE EPOXY COATED.
- ONLY ALUMINUM SHEETED JOINTS IN PARAPETS ARE SHOWN ON THIS DWG. LOCATION OF ALL OTHER PARAPET JOINTS ARE SHOWN ON DWG. NO. 10.
- REINFORCEMENT BASE AND BAR COUPLERS AT STAGE LINE SHALL BE TIED WITH DOUBLE THE AMOUNT OF TIES NORMALLY USED.
- SEE DWG. NO. 6 FOR REINFORCEMENT DETAIL AT SCOFFERS.
- SEE DWG. NO. 11 OF 34 FOR SUPERSTRUCTURE BILL OF MATERIAL.

**SUPERSTRUCTURE (WB)**  
 FAI 74 OVER LYNCH ROAD  
 FAI RTE. 74 SECTION (92-12HB-6BR)  
 VERMILION COUNTY  
 STATION 2213+83.36  
 STRUCTURE NO. 092-0025(WB)  
 STRUCTURE NO. 092-0026(EB)


**ESCA**  
 CONSULTANTS, INC.  
 DESIGNED BY: RDP 7-89  
 DRAWN BY: WEM 9-89  
 CHECKED BY: JRF 11-89  
 APPROVED BY: RDP 11-89

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

FOR INFO ONLY - STRUCTURE DETAILS FOR  
 LOCATIONS #3 & #4

| F.A.I. RTE.               | SECTION | COUNTY    | TOTAL SHEETS       | SHEET NO. |
|---------------------------|---------|-----------|--------------------|-----------|
| 74                        |         | VERMILION | 52                 | 34        |
| D5 BRIDGE PAINTING 2020-1 |         |           | CONTRACT NO. 70E06 |           |
| ILLINOIS                  |         |           | FED. AID PROJECT   |           |

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.



**SECTION A-A**

\*\*\* PLACE a(S) AND b(S) THROUGH h<sub>2</sub>(S) BARS IN BACK OF ANCHOR BOLT AS SHOWN IF REQUIRED TO MAINTAIN 1" CL. (+0-1/8"). ANCHOR BOLTS SHOULD BE TIED TO a(S) AND b(S) THROUGH h<sub>3</sub>(S) BARS.



### X,Y&Z DIMENSIONS

|                   |           |
|-------------------|-----------|
| EB Lanes, N. Side | 3' 9 1/4" |
| EB Lanes, S. Side | 3' 1 3/8" |
| WB Lanes, N. Side | 3' 0"     |
| WB Lanes, S. Side | 3' 9 3/4" |
| Location          |           |
|                   |           |
| EB Lanes, N. Side | 3'        |
| EB Lanes, S. Side | 2' 2"     |
| WB Lanes, N. Side | 2' 8"     |
| WB Lanes, S. Side | 2' 8"     |

|                   |                 |
|-------------------|-----------------|
| <u>FIBERGLASS</u> | <u>ALUMINUM</u> |
| <u>PIPE</u>       | <u>TUBE</u>     |

## FLOOR DRAIN DETAILS



(See Dwg. No. 10 for locations of these joints)




**SECTION B-B**



TOP PLAN

1/2" x 8" Fiberglass  
Reinf. Plastic  
Rebar.



|                   |                 |
|-------------------|-----------------|
| <u>FIBERGLASS</u> | <u>ALUMINUM</u> |
| <u>PIPE</u>       | <u>TUBE</u>     |



BAR x(E)

### BAR BENDING DETAILS

**NOTES**

1. FIBERGLASS PIPE SHALL CONFORM TO ASTM D1996, WITH SHORT-TIME RUPTURE STRENGTH ROOF TENSILE STRESS OF 36,000 P.S.I. MINIMUM.
2. THE SURFACE OF THE FIBERGLASS PIPE SHALL BE FREE OF BOND INHIBITING AGENTS.
3. THE EXTERIOR SURFACES OF THE FLOOR DRAIN SHALL BE PAINTED WITH THE LEAD AND CHROMATE FREE PAINT SYSTEM PAINTING SPECIFIED FOR STRUCTURAL STEEL. THE EXTERIOR SURFACES OF THE ALUMINUM TUB SHALL BE CLEANED AND GIVEN A WASHCOAT PRETREATMENT IN ACCORDANCE WITH STEEL STRUCTURES PAINTING COUNCIL'S SPEC. SSPC-SP1 & SSPC-PAINT 27 PRIOR TO PAINTING. FIBERGLASS TO HAVE PRIMER AS PER MIL-P-15328.
4. THE CLAMPING DEVICE SHALL BE GALVANIZED IN ACCORDANCE WITH AASHTO M-232.


5. Reinforcement bars designated (E) shall be epoxy coated.

top and inside faces of

## SUPERSTRUCTURE DETAILS



FAI 74 OVER LYNCH ROAD  
FAI RTE. 74 SECTION (92-12HB-6)BR  
VERMILION COUNTY  
STATION 2213+83.36  
STRUCTURE NO.092-0025(WB)  
STRUCTURE NO.092-0026(EB)

REVISED 1-25-91




### FRAMING PLAN (EB BRIDGE)

092-0026 E.B.



### PEENING DETAILS (Exist. Beams) DETAIL 1



### NOTES

- EXISTING BEAMS 6 & 7 ARE TO BE REMOVED, REMOVED FOR REALIGNMENT, AND REUSED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL EXISTING DIAPHRAGMS SOUTH OF BEAM 5. BEAMS 6 & 7 SHALL BE SHORTENED (FIELD CUT 6 13/16" FROM EACH END OF BEAM 6; FIELD CUT 1'-2" FROM EACH END OF BEAM 7; CLIP CORNERS OF TOP FLANGE TO MATCH EXISTING BEAMS). BEARINGS SHALL BE RELOCATED ON THE BEAMS, AND NEW HOLES DRILLED FOR BEARING AND DIAPHRAGM CONNECTIONS AS REQUIRED. SHORTENING SHALL BE ACCOMPLISHED BY CUTTING LENGTH FROM THE BEAMS AT EACH END, SUCH THAT EXISTING SPLICES ARE LOCATED FROM PIERS AS SHOWN. EXISTING HOLES WHICH ARE NOT TO BE REUSED SHALL BE FILLED WITH E.S. BOLTS. COST INCIDENTAL TO FURNISHING & ERECTING STRUCTURAL STEEL. SEE SPECIAL PROVISIONS.
- D1 & D2 INDICATES NEW DIAPHRAGMS. SEE DWG. NO. 13 FOR DIAPHRAGM CONNECTION DETAILS.
- PROVIDE NEW E.S. BOLTS AT ALL CONNECTIONS WHICH MUST BE UNCONNECTED OR LOCKED IN ORDER TO REPOSITION BEAMS.
- PROVIDE SHEAR STUDS ON EXISTING AND NEW BEAMS AS SHOWN ON DETAILS THIS DWG.
- WELDS AT ENDS OF ALL EXISTING TOP COVER PLATES AT PIERS 1 & 2 ARE TO BE PEENED. PEENING IS TO BE PERFORMED UNDER FULL DEAD LOAD CONDITIONS, PRIOR TO REMOVAL OF EXISTING CONCRETE DECK. SEE DETAILS THIS DWG. & SPECIAL PROVISIONS.
- SEE DWG. NO. 13 FOR SECTION A-A.

### REACTION TABLES (EB BRIDGE)

| ALL BEAMS      |          |        |        |          |
|----------------|----------|--------|--------|----------|
|                | W. ABUT. | PIER 1 | PIER 2 | E. ABUT. |
| R <sub>1</sub> | 19.8     | 70.1   | 66.8   | 17.2     |
| R <sub>2</sub> | 32.7     | 38.4   | 38.7   | 26.4     |
| IMP            | 9.5      | 10.7   | 10.9   | 7.9      |
| R (TOTAL)      | 62.0     | 119.2  | 116.2  | 51.4     |

$I_x$  AND  $S_x$  ARE THE MOMENT OF INERTIA AND SECTION MODULUS OF THE STEEL SECTION USED IN COMPUTING  $I_x$  (TOTAL).

$I_y$  AND  $S_y$  ARE THE MOMENT OF INERTIA AND SECTION MODULUS OF THE COMPOSITE SECTION USED IN COMPUTING  $I_y$  (TOTAL).

VR IS THE MAXIMUM  $\frac{1}{2}$  + IMPACT SHEAR RANGE IN SPAN.

THE FULLY PLASTIC MOMENT CAPACITY ( $M_p$ ) IS COMPUTED ACCORDING TO AASHTO 10.50.1.1.

$M_a$  (APPLIED MOMENT) =  $1.3 (M_d + M_e + \frac{5}{3} (M_f + I))$ .

$S_x$  (TOTAL) IS THE SUM OF THE STRESSES DUE TO  $1.3 (M_d + M_e + \frac{5}{3} (M_f + I))$ .

$S_x$  (OVERLOAD) IS THE SUM OF THE STRESSES DUE TO  $M_d + M_e + \frac{5}{3} (M_f + I)$ .

$M_d$  W.D. = MOMENT DUE TO DEAD LOADS ON NON-COMPOSITE SECTION.

$M_e$  W.C. = MOMENT DUE TO DEAD LOADS ON COMPOSITE SECTION.

$M_f$  = MOMENT DUE TO LIVE LOAD ON NON-COMPOSITE OR COMPOSITE SECTION.

$M_{IMP}$  = MOMENT DUE TO LIVE LOAD IMPACT ON NON-COMPOSITE OR COMPOSITE SECTION.

### MOMENT TABLES (EB BRIDGE)

| EXIST. BEAMS (W/COVER PLATES) |            |        |            |        | NEW BEAMS (NO COVER PLATES) |            |        |            |        |
|-------------------------------|------------|--------|------------|--------|-----------------------------|------------|--------|------------|--------|
|                               | 0.4 SPAN 1 | PIER 1 | 0.5 SPAN 2 | PIER 2 | 0.6 SPAN 3                  | 0.4 SPAN 1 | PIER 1 | 0.5 SPAN 2 | PIER 2 |
| $I_x$                         | 4,918      | 6,488  | 4,918      | 6,488  | 4,930                       | 4,930      | 4,930  | 4,930      | 4,930  |
| $I_y$ (n=27)                  | 10,382     | 10,382 | 10,382     | 10,382 | 10,079                      | 10,079     | 10,079 | 10,079     | 10,079 |
| $I_y$ (n=9)                   | 14,137     | 14,137 | 14,137     | 14,137 | 13,820                      | 13,820     | 13,820 | 13,820     | 13,820 |
| $S_x$                         | 329        | 422    | 329        | 422    | 329                         | 329        | 329    | 329        | 329    |
| $S_y$ (n=27)                  | 453        | 453    | 453        | 453    | 448                         | 448        | 448    | 448        | 448    |
| $S_y$ (n=9)                   | 502        | 502    | 502        | 502    | 498                         | 498        | 498    | 498        | 498    |
| $M_d$ W.C.                    | 0.85       | 1.13   | 0.85       | 1.13   | 0.85                        | 0.82       | 1.08   | 0.82       | 1.08   |
| $M_e$ W.C.                    | 127.6      | 300.2  | 149.1      | 310.2  | 94.9                        | 121.3      | 323.6  | 144.6      | 295.1  |
| $M_f$ W.C.                    | 0.26       | 0.26   | 0.26       | 0.26   | 0.26                        | 0.26       | 0.26   | 0.26       | 0.26   |
| $M_a$ W.C.                    | 44.8       | 99.3   | 34.1       | 45.5   | 60.9                        | 60.9       | 60.9   | 60.9       | 60.9   |
| $M_{IMP}$                     | 292.2      | 174.1  | 368.8      | 166.5  | 265.0                       | 293.1      | 169.0  | 371.2      | 169.5  |
| $M_{IMP}$                     | 94.4       | 48.4   | 98.6       | 46.8   | 79.0                        | 84.7       | 45.7   | 99.3       | 45.2   |
| $S_x$ (n=27)                  | 627.7      | 370.8  | 779.1      | 355.6  | 572.7                       | 629.6      | 357.8  | 784.2      | 342.7  |
| $S_x$ (n=9)                   | 1040.1     | 937.5  | 1283.8     | 877.2  | 1035.3                      | 885.8      | 1286.6 | 829.2      | 989.5  |
| $S_y$ W.C.                    | 4.65       | 9.95   | 5.44       | 9.08   | 3.46                        | 4.42       | 11.80  | 5.27       | 10.76  |
| $S_y$ W.C.                    | 1.19       | 1.57   | 0.90       | 1.22   | 1.63                        | 1.63       | 1.63   | 1.63       | 1.63   |
| $S_x$ 5/3 (n+1)               | 15.00      | 10.54  | 18.62      | 10.11  | 13.69                       | 15.17      | 13.05  | 18.90      | 12.50  |
| $S_y$ (TOTAL)                 | 26.64      | 26.64  | 26.64      | 26.64  | 26.64                       | 26.64      | 26.64  | 26.64      | 26.64  |
| VR                            | 45.4       | 60.7   | 37.9       | 45.3   | 40.7                        | 40.7       | 40.7   | 40.7       | 40.7   |
| $S_x$ (TOTAL)                 | 2,135      | 2,135  | 2,135      | 2,135  | 2,135                       | 2,135      | 2,135  | 2,135      | 2,135  |
| $M_p$ (OVERLOAD)              | 20.84      | 20.45  | 25.63      | 19.19  | 18.05                       | 20.81      | 24.85  | 25.80      | 23.26  |

### TABLE OF ELEVATIONS (T/O STEEL BEAMS)

| BEAM | W. ABUT. | PIER 1 | PIER 2 | E. ABUT. |
|------|----------|--------|--------|----------|
| 1    | 677.63   | 676.42 | 674.80 | 673.65   |
| 2    | 677.52   | 676.29 | 674.67 | 673.52   |
| 3    | 677.40   | 676.17 | 674.55 | 673.39   |
| 4    | 677.28   | 676.05 | 674.42 | 673.26   |
| 5    | 677.17   | 675.93 | 674.29 | 673.13   |
| 6    | 677.05   | 675.80 | 674.16 | 672.99   |
| 7    | 676.93   | 675.68 | 674.02 | 672.85   |
| 8    | 676.81   | 675.55 | 673.89 | 672.70   |

### SUPERSTRUCTURE STEEL DETAILS (EB BRIDGE)

FAI 74 OVER LYNCH ROAD  
FAI RTE. 74 SECTION (92-12MB-6)BR  
VERMILION COUNTY  
STATION 2213+83.36  
STRUCTURE NO.092-0025(WB)  
STRUCTURE NO.092-0026(EB)

**ESCA**  
CONSULTANTS, INC.  
DESIGNED BY: ADP 9.09  
DRAWN BY: CJA 9.09  
CHECKED BY: AND 9.09  
APPROVED BY: ADP 9.09

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FOR INFO ONLY - STRUCTURE DETAILS FOR  
LOCATIONS #3 & #4

F.A.I. RTE. 74  
SECTION  
COUNTY VERMILION  
TOTAL SHEETS 52  
SHEET NO. 36  
D5 BRIDGE PAINTING 2020-1  
CONTRACT NO. 70E06  
ILLINOIS FED. AID PROJECT


USER NAME = dawsonkb  
DESIGNED -  
DRAWN -  
PLOT SCALE = 40,000' / in.  
PLOT DATE = 8/15/2019  
CHECKED -  
DATE -  
REVISED -  
REVISED -  
REVISED -  
REVISED -

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.





092-0025 W.B.  
(1960 PLANS)



Note: Pier Diaphragms shall be erected after anchor bolt holes have been field drilled.

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

|        |         |      |        |      |         |
|--------|---------|------|--------|------|---------|
| SCALE: | SHEET 1 | OF 1 | SHEETS | STA. | TO STA. |
|--------|---------|------|--------|------|---------|

| F.A.I.<br>RTE.            | SECTION  | COUNTY             | TOTAL<br>SHEETS | SHEET<br>NO. |
|---------------------------|----------|--------------------|-----------------|--------------|
| 74                        | *        | VERMILION          | 52              | 38           |
| D5 BRIDGE PAINTING 2020-1 |          | CONTRACT NO. 70E06 |                 |              |
|                           | ILLINOIS | FED. AID PROJECT   |                 |              |

|                              |            |           |
|------------------------------|------------|-----------|
| USER NAME = dawsonkb         | DESIGNED - | REVISED - |
|                              | DRAWN -    | REVISED - |
| PLOT SCALE = 40,0000 ' / in. | CHECKED -  | REVISED - |
| PLOT DATE = 8/15/2019        | DATE -     | REVISED - |

(1960 PLANS)

30W116

1.6 2.6 2.6 1.6 8.0

E Beam

1/8

1/4

Cover Pl 9 x 8 x 8-0

Top of Beam

E Bearing

COVER PLATE DETAIL  
52 Required 2 Bridges

Technical drawing of Section A-A of a structural joint. The drawing shows a vertical member with a horizontal flange at the top. A diagonal member, labeled "D1, D2 or D10", is shown in cross-section, passing through the flange. The flange is labeled "30W116". The diagonal member is labeled "12W40". The joint is shown in cross-section, with a 5/8 inch dimension indicated. A note points to the joint: "Cut Diaphragm on Skew on Flange top & bottom". Another note points to the diagonal member: "D1, D2 or D10". A dimension "E 849" is also shown.

SECTION A-A

SECTION B-B

Technical drawing of a double door assembly, showing side and end views.

**Side View (Left):**

- Two doors are shown, each labeled **16W36**.
- The top and bottom edges are labeled **D3 Thru D9**.
- The doors are mounted on a frame with **Level** lines indicating alignment.
- The doors are connected by **30W116** hinges.
- The doors are secured with **3/4"  $\phi$  Bolts, Hex. Nuts**.
- The doors are labeled **B** at the bottom.

**End View (Right):**

- The end view shows the door edge with a **6 Min.** gap.
- The door edge is labeled **D3 Thru D9**.
- The door edge is secured with **30W116** hinges.
- The door edge is labeled **16W36**.

DIAPHRAGM D1 D2 OR D10  
2 D1 & 2 D10 Required East Bound Bridge  
18 D2 Required 2 Bridges

DIAPHRAGM CONNECTION DETAILS  
2<sup>nd</sup> Rivets

All End Diaphragms 12 WF40  
All Interior Diaphragms 16 WF36

TOTAL COMPUTED WEIGHT OF FRAMING STEEL  
STRUCTURAL STEEL 273,850 LBS.  
(2 BRIDGES)

CONSOER, TOWNSEND & ASSOCIATES  
CONSULTING ENGINEERS CHICAGO, ILLINOIS  
ILLINOIS DIVISION OF HIGHWAYS  
F. A. I. RT. 74 BRIDGE  
OVER EAST DANVILLE SPUR SEC. 92-12HB-6  
VERMILION COUNTY STA. 2213+83.36


|                              |            |           |
|------------------------------|------------|-----------|
| USER NAME = dawsonkb         | DESIGNED - | REVISED - |
|                              | DRAWN -    | REVISED - |
| PLOT SCALE = 40,0000 ' / in. | CHECKED -  | REVISED - |
| PLOT DATE = 8/15/2019        | DATE -     | REVISED - |

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

**FOR INFO ONLY – STRUCTURE DETAILS FOR  
LOCATIONS #3 & #4**

|        |         |      |        |      |        |
|--------|---------|------|--------|------|--------|
| SCALE: | SHEET 1 | OF 1 | SHEETS | STA. | TO STA |
|--------|---------|------|--------|------|--------|

| F.A.I.<br>RTE.            | SECTION | COUNTY             | TOTAL<br>SHEETS | SHEET<br>NO. |
|---------------------------|---------|--------------------|-----------------|--------------|
| 74                        | *       | VERMILION          | 52              | 39           |
| D5 BRIDGE PAINTING 2020-1 |         | CONTRACT NO. 70E06 |                 |              |
| ILLINOIS                  |         | FED. AID PROJECT   |                 |              |



**ESCA**  
CONSULTANTS, INC.

|              |     |      |
|--------------|-----|------|
| DESIGNED BY: | ADP | 2/50 |
| DRAWN BY:    | GJB | 2/50 |
| CHECKED BY:  | JAF | 2/50 |
| APPROVED BY: | ADP | 2/50 |

**ELASTOMERIC BEARINGS**  
FAI 74 OVER LYNCH ROAD  
FAI RTE. 74 SECTION (92-12HB-6)BR  
VERMILION COUNTY  
STATION 2213+83.36  
STRUCTURE NO. 092-0025(WB)  
STRUCTURE NO. 092-0025(EB)

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FOR INFO ONLY - STRUCTURE DETAILS FOR  
LOCATIONS #3 & #4

| F.A.I. RTE.               | SECTION | COUNTY    | TOTAL SHEETS       | SHEET NO. |
|---------------------------|---------|-----------|--------------------|-----------|
| 74                        |         | VERMILION | 52                 | 40        |
| D5 BRIDGE PAINTING 2020-1 |         |           | CONTRACT NO. 70E06 |           |
| ILLINOIS                  |         |           | FED. AID PROJECT   |           |

|                             |            |           |
|-----------------------------|------------|-----------|
| USER NAME = dawsonkb        | DESIGNED - | REVISED - |
| PLOT SCALE = 40,0000' / in. | DRAWN -    | REVISED - |
| PLOT DATE = 8/15/2019       | CHECKED -  | REVISED - |
|                             | DATE -     | REVISED - |







※標準(92-12VA-1)A

EXISTING STRUCTURE: STRUCTURE NO. 092-0023 & 092-0024  
WAS BUILT IN 1962 AS PA 74 SECTION 12-12VB-1, VP-1.  
REPAIRS PERFORMED IN 1977 INCLUDED DECK PATCHING, EXPAN-  
SION DEVICE RECONSTRUCTION, INSTALLATION OF WATER PROOFING  
MEMBRANE SYSTEM, AND BITUMINOUS OVERLAY. EACH STRUCTURE  
CONSISTS OF A THREE SPAN CONTINUOUS NON-COMPRESSED STEEL  
BEAM AND RAILROAD TRACKS. THE TRACKS ARE SUPPORTED BY  
PILE BENT ABUTMENTS AND PILE SUPPORTED MULTIPLE COLUMN  
PIERS. OVERALL LENGTH IS 271'-0" AND CLEAR ROADWAY  
WIDTHS ARE 42'-0" FOR STRUCTURE NO. 092-0023 AND 30'-0"  
FOR STRUCTURE NO. 092-0024. TRAFFIC TO BE MAINTAINED  
UTILISING STAGE CONSTRUCTION. RAILROAD TO BE SALVAGED.  
CONFORMS TO REQUIREMENTS OF FEDERAL AID HIGHWAY ACT. SEE  
FOR REMOVAL BY DISTRICT MAINTENANCE FORCES.



LOADING HS20 & ALT.  
STR. NO. 092-0023

**WESTBOUND**

LOADING HS20 & ALT.  
STR. NO. 092-0024


EASTBOUND

**NEW NAME PLATES**  
**(1 EA. REQ'D)**  
**(SEE STD. 2113)**

092-0024 E.B

092-002

Note  
Salvage Existing Name Plates &  
Mount Adjacent to New Name  
Plates on New Parapet as shown  
on Srd. 2113. The cost of Salvaging  
& Incorporating Exist. Name Plates  
into New Work is Incidental to  
Nameplates.




**APPROVED**

FOR STRUCTURAL ADEQUACY

SECTION A-A

(See Dwg. No. 2 For Add'l  
Small Details)

James K. Quinn  
[Licensed Structural Engineer]



### LOCATION SKETCH


## GENERAL PLAN & ELEVATION

FAI 74 OVER SEABOARD SYSTEMS.R.R.  
FAI RTE. 74 SECTION (92-12VB-1)BR  
VERMILION COUNTY  
STATION 2203+43.26  
STRUCTURE NO. 092-0023(WB)  
STRUCTURE NO. 092-0024(EB)


F = Fixed Brg.  
E = Exp. Brg.  
POL = Profile Grade Line  
⊙ Boring Location

**ESCA**  
CONSULTANTS, INC.

|              |     |      |
|--------------|-----|------|
| DESIGNED BY: | RDP | 6-89 |
| DRAWN BY:    | WEM | 6-89 |
| CHECKED BY:  | JRF | 7-89 |
| APPROVED BY: | RDP | 7-89 |



## PLAN



**SEABOARD SYSTEMS R.R. PROFILE**  
(Top of Rail, East Track)

DESIGN SPECIFICATIONS  
AASHTO 1983 & GEORGIA  
DOTING (FDOT) 2012  
RETROFITTING GUIDELINES FOR HIGHWAY BRIDGES  
LOADING  
HS20-44 & ALTERNATE MILITARY,  
WITH ALLOWANCE FOR 25 psf  
FUTURE WEARING SURFACE

DESIGN STRESSES (New)  
f'c = 3,500 psi  
fy = 60,000 psi (REINF. BARS)  
fy = 36,000 psi (STRUCT. STL. M-183)  
(COMPOSITE)

DESIGN STRESSES (EXIST. CONST.)

|        |                             |
|--------|-----------------------------|
| $f'_c$ | = 3,500 psi                 |
| $f_y$  | = 40,000 psi (REINF. BARS)  |
| $f_s$  | = 20,000 psi (REINF. BARS)  |
| $f_e$  | = 18,000 psi (STRUCT. STL.) |

**FOR INFO ONLY – STRUCTURE DETAILS FOR  
LOCATIONS #5 & #6**

|        |         |      |        |      |         |
|--------|---------|------|--------|------|---------|
| SCALE: | SHEET 1 | OF 1 | SHEETS | STA. | TO STA. |
|--------|---------|------|--------|------|---------|


|                           |         |                           |                 |              |
|---------------------------|---------|---------------------------|-----------------|--------------|
| F.A.I.<br>RTE.            | SECTION | COUNTY                    | TOTAL<br>SHEETS | SHEET<br>NO. |
| 74                        | *       | VERMILION                 | 52              | 42           |
| D5 BRIDGE PAINTING 2020-1 |         | CONTRACT NO. 70E06        |                 |              |
|                           |         | ILLINOIS FED. AID PROJECT |                 |              |

[illegible][illegible]

1. SEE DWG. NO. 11 FOR SECTIONS A-A & B-B.
2. BARS INDICATED THUS: 4x10/10, ETC., INDICATES 4 LINES OF BARS WITH 10 LENGTHS PER LINE.
3. REINFORCEMENT BARS DESIGNATED (R) SHALL BE EPOXY COATED.
4. ONLY ALUMINUM GUESTED JOINTS IN PARAPETS SEE SHOWN ON THIS DWG. LOCATION OF ALL OTHER PARAPET JOINTS ARE SHOWN ON DWG. NO. 12.
5. REINFORCEMENT BARS AND SAS SPICERS AT STENCE LINE SHALL BE TIED WITH DOUBLE THE AMOUNT OF TIES NORMALLY USED.

SUPERSTRUCTURE (EB)  
FAI 74 OVER SEABOARD SYSTEMS RR  
FAI RTE 74 SECTION 192-12VB-1)BR  
VERMILION COUNTY  
STATION 2203+43.26  
STRUCTURE NO. 092-0023(WB)  
STRUCTURE NO. 092-0024(EB)

|                          |     |      |
|--------------------------|-----|------|
| <b>ESCA</b>              |     |      |
| <b>CONSULTANTS, INC.</b> |     |      |
| DESIGNED BY:             | RDP | 6-89 |
| DRAWN BY:                | NEM | 6-89 |
| CHECKED BY:              | JRF | 7-89 |
| APPROVED BY:             | RDP | 7-89 |



|                              |            |           |
|------------------------------|------------|-----------|
| USER NAME = dawsonkb         | DESIGNED - | REVISED - |
|                              | DRAWN -    | REVISED - |
| PLOT SCALE = 40,0000 ' / in. | CHECKED -  | REVISED - |
| PLOT DATE = 8/15/2019        | DATE -     | REVISED - |

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

|                                                            |         |      |         |
|------------------------------------------------------------|---------|------|---------|
| FOR INFO ONLY - STRUCTURE DETAILS FOR<br>LOCATIONS #5 & #6 |         |      |         |
| SCALE:                                                     | SHEET 1 | OF 1 | SHEETS  |
|                                                            | STA.    |      | TO STA. |


|                           |         |                    |                 |              |
|---------------------------|---------|--------------------|-----------------|--------------|
| F.A.I. RTE. 74            | SECTION | COUNTY VERMILION   | TOTAL SHEETS 52 | SHEET NO. 44 |
| D5 BRIDGE PAINTING 2020-1 |         | CONTRACT NO. 70E06 |                 |              |
| ILLINOIS                  |         | FED. AID PROJECT   |                 |              |

| ROUTE NO.           | SECTION          | COUNTY           | TOTAL SHEETS | SHEET NO. |
|---------------------|------------------|------------------|--------------|-----------|
| FAI 74              | 92-12VB-1        | Vermilion        | 118          | 43        |
| STA.                | TO STA.          | ILLINOIS PROJECT |              |           |
| FED. ROAD DIST. NO. | ILLINOIS PROJECT |                  |              |           |

Dwg. No. 11 of 30


## NOTES

- FIBERGLASS PIPE SHALL CONFORM TO ASTM D2996, WITH SHORT-TIME RUPTURE STRENGTH HOOP TENSILE STRESS OF 30,000 P.S.I. MINIMUM.
- THE SURFACE OF THE FIBERGLASS PIPE SHALL BE FREE OF BOND INHIBITING AGENTS.
- THE EXTERIOR SURFACES OF THE FLOOR DRAIN SHALL BE PAINTED WITH THE LEAD & CHROMATE FREE ALKYL PAINTING SPECIFIED FOR STRUCTURAL STEEL. THE EXTERIOR SURFACES OF THE ALUMINUM TUBE SHALL BE CLEANED AND GIVEN A WASHCOAT PRETREATMENT IN ACCORDANCE WITH STEEL STRUCTURES PAINTING COUNCIL'S SPEC. SSPC-SP1 & SSPC-PAINT 27 PRIOR TO PAINTING. FIBERGLASS TO HAVE PREPARE AS PER MIL-P-15328.
- THE CLAMPING DEVICE SHALL BE GALVANIZED IN ACCORDANCE WITH AASHTO M-232.
- Bars designated (E) shall be epoxy coated.




SECTION A-A

SECTION B-B




DETAILS OF PARAPET JOINT

(See Dwg. No. 12 for locations of these joints)




TYPICAL SECTION


- Furnish in segments of 20 ft. maximum length. Maximum space between installed segments shall be 3/16\".




4\"/>



TYPICAL END OF SEAL TREATMENT




SECTION C-C



SECTION THRU PARAPET

## "X" DIMENSIONS

|                   |           |
|-------------------|-----------|
| EB Lanes, N. Side | 3'-6 1/2" |
| EB Lanes, S. Side | 3'-0"     |
| WB Lanes, N. Side | 2'-11"    |
| WB Lanes, S. Side | 3'-5"     |



FLOOR DRAIN DETAILS

**SUPERSTRUCTURE DETAILS**  
**FAI 74 OVER SEABOARD SYSTEMS RR**  
**FAI RTE. 74 SECTION 92-12VB-11BR**  
**VERMILION COUNTY**  
**STATION 2203+43.26**  
**STRUCTURE NO. 092-0023(WB)**  
**STRUCTURE NO. 092-0024(EB)**

|                   |      |
|-------------------|------|
| <b>ESCA</b>       |      |
| CONSULTANTS, INC. |      |
| DESIGNED BY: RDP  | 6-89 |
| DRAWN BY: WEM     | 6-89 |
| CHECKED BY: JRF   | 7-89 |
| APPROVED BY: RDP  | 7-89 |

|                              |            |           |
|------------------------------|------------|-----------|
| USER NAME = dawsonkb         | DESIGNED - | REVISED - |
|                              | DRAWN -    | REVISED - |
| PLOT SCALE = 40,0000 ' / in. | CHECKED -  | REVISED - |
| PLOT DATE = 8/15/2019        | DATE -     | REVISED - |

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FOR INFO ONLY - STRUCTURE DETAILS FOR  
LOCATIONS #5 & #6

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

| F.A.I. RTE. | SECTION                   | COUNTY           | TOTAL SHEETS | SHEET NO. |
|-------------|---------------------------|------------------|--------------|-----------|
| 74          |                           | VERMILION        | 52           | 45        |
|             | D5 BRIDGE PAINTING 2020-1 | ILLINOIS         |              |           |
|             |                           | FED. AID PROJECT |              |           |



| ROUTE NO.          | SECTION   | COUNTY            | TOTAL SHEETS | SHEET NO. |
|--------------------|-----------|-------------------|--------------|-----------|
| FAI 74             | VERMILION | VERMILION         | 52           | 46        |
| STA.               | TO STA.   | PROJECT           |              |           |
| FED. ROAD DIST NO. | ILLINOIS  | PROJECT           |              |           |
|                    |           | Dwg. No. 14 of 30 |              |           |

NOTES

- REMOVE EXISTING STRUCTURAL STEEL BETWEEN THE W. ABUT. AND THE SPICE WEST OF PIER 1. PRESERVE EXISTING DIAPHRAGMS IN THIS AREA AND INCORPORATE INTO NEW WORK. PROVIDE NEW STEEL BEAMS. PROVIDE NEW H.S. BOLTS AT ALL CONNECTIONS & SPICES WHICH ARE UNCONNECTED OR LOOSEENED TO FACILITATE THE REQUIRED STRUCTURAL STEEL WORK.
- D1 AND D2 INDICATE NEW DIAPHRAGMS.
- PROVIDE SHEAR STUDS ON EXISTING STEEL BEAMS TO REMAIN AND ON NEW BEAMS AS SHOWN ON DETAILS THIS DWG.
- SEE SPECIAL PROVISIONS AND DWG. NO. 15 FOR ADDITIONAL DETAILS OF STRUCTURAL STEEL.

3/4" Granular or Solid Flux Filled Headed Studs Automatically End Welded (No Req'd = 645 per beam; 2675 Total for beams (1) thru (8))





TABLE OF ELEVATIONS- TOP OF STEEL BEAMS (EB)\*

| BEAM | SPAN 1  | PIER 1  | SPAN 2  | PIER 2  | SPAN 3  | E. ABUT. |
|------|---------|---------|---------|---------|---------|----------|
| 1    | 688.812 | 688.932 | 688.956 | 688.985 | 688.960 | 688.999  |
| 2    | 688.929 | 689.041 | 689.063 | 689.090 | 689.061 | 689.089  |
| 3    | 689.014 | 689.120 | 689.139 | 689.163 | 689.130 | 689.156  |
| 4    | 689.026 | 689.126 | 689.143 | 689.164 | 689.127 | 689.151  |
| 5    | 689.045 | 689.158 | 689.173 | 689.191 | 689.149 | 689.168  |
| 6    | 688.871 | 688.958 | 688.970 | 688.984 | 688.939 | 688.959  |
| 7    | 688.785 | 688.861 | 688.877 | 688.893 | 688.838 | 688.855  |

\* Elevations shown are Top of Flange (not Splice R or Cover R) after jacking; they do not include deflection, & are given for use in fabrication of New Steel Beams & to assist the contractor in determining req'd thickness of Shim R's under bearings.

FRAMING PLAN (EB BRIDGE)

REACTION TABLES (EB & WB)

| INTERIOR BEAMS (EXIST. w/ NEW SECTION @ W END) |          |        |        | NEW INTERIOR BEAM |          |        |        |          |
|------------------------------------------------|----------|--------|--------|-------------------|----------|--------|--------|----------|
|                                                | W. ABUT. | PIER 1 | PIER 2 | E. ABUT.          | W. ABUT. | PIER 1 | PIER 2 | E. ABUT. |
| R @                                            | 40.7     | 124.0  | 102.4  | 29.9              | 36.1     | 106.9  | 89.8   | 26.2     |
| R @                                            | 36.9     | 56.8   | 51.4   | 29.6              | 27.2     | 47.6   | 43.3   | 30.1     |
| IMP                                            | 8.4      | 12.9   | 13.0   | 7.5               | 6.2      | 10.8   | 11.0   | 7.6      |
| R (TOTAL)                                      | 86.0     | 193.7  | 166.8  | 67.0              | 69.5     | 165.3  | 144.1  | 63.9     |

$f_s$  (OVERLOAD) IS THE SUM OF THE STRESSES DUE TO  $M_R + M_D + 5/3 M_I + I$

$I_R$  AND  $I_D$  ARE THE MOMENT OF INERTIA AND SECTION MODULUS OF THE STEEL SECTION USED IN COMPUTING  $f_s$  (TOTAL)

$I_C$  AND  $S_C$  ARE THE MOMENT OF INERTIA AND SECTION MODULUS OF THE COMPOSITE SECTION USED IN COMPUTING  $f_s$  (TOTAL)

$V_R$  IS THE MAXIMUM  $V$  & IMPACT SHEAR RANGE IN SPAN

$M_R$  (APPLIED MOMENT) =  $1.3 (M_R + M_D + 5/3 M_I + I)$

$f_s$  (TOTAL) IS THE SUM OF THE STRESSES DUE TO

$1.3 (M_R + M_D + 5/3 M_I + I)$

$M_R$  H.C. = MOMENT DUE TO DEAD LOADS ON NONCOMPOSITE SECTION

$M_D$  H.C. = MOMENT DUE TO DEAD LOADS ON COMPOSITE SECTION




$M_I$  = MOMENT DUE TO LIVE LOAD ON NONCOMPOSITE OR COMPOSITE SECTION

$M_{IMP}$  = MOMENT DUE TO LIVE LOAD IMPACT ON NONCOMPOSITE OR COMPOSITE SECTION

THE FULLY PLASTIC MOMENT CAPACITY ( $M_u$ ) IS COMPUTED ACCORDING TO AASHTO 10.50.1.1.


MOMENT TABLES (EB & WB)

| INTERIOR BEAMS (Exist. w/ New Section @ W End) |                 |        |            | NEW INTERIOR BEAM |            |            |        |            |        |            |
|------------------------------------------------|-----------------|--------|------------|-------------------|------------|------------|--------|------------|--------|------------|
|                                                | 0.6 SPAN 1      | PIER 1 | 0.6 SPAN 2 | PIER 2            | 0.6 SPAN 3 | 0.6 SPAN 1 | PIER 1 | 0.6 SPAN 2 | PIER 2 | 0.6 SPAN 3 |
| I <sub>s</sub>                                 | in <sup>4</sup> | 15,000 | 24,543     | 15,000            | 21,254     | 15,000     | 15,000 | 15,000     | 15,000 | 15,000     |
| I <sub>c</sub> @ n=27                          |                 | 23,076 |            | 23,076            |            | 22,113     |        | 22,113     |        | 22,113     |
| I <sub>c</sub> @ n=9                           |                 | 31,460 |            | 31,460            |            | 30,062     |        | 30,062     |        | 30,062     |
| S <sub>s</sub>                                 | in <sup>3</sup> | 837    | 1299       | 837               | 1144       | 837        | 837    | 837        | 837    | 837        |
| S <sub>c</sub> @ n=27                          |                 | 991    |            | 991               |            | 976        |        | 976        |        | 976        |
| S <sub>c</sub> @ n=9                           |                 | 1094   |            | 1094              |            | 1079       |        | 1079       |        | 1079       |
| @ N.C.                                         | ft <sup>4</sup> | 0.84   | 1.21       | 0.84              | 1.18       | 0.84       | 0.75   | 0.98       | 0.75   | 0.98       |
| M @ N.C. ft-k                                  |                 | 554.5  | 1129.3     | 296.5             | 762.9      | 298.0      | 503.6  | 941.9      | 280.0  | 665.6      |
| @ C.                                           |                 | 0.27   |            | 0.27              |            | 0.23       |        | 0.23       |        | 0.23       |
| M <sub>s</sub> @ C.                            |                 | 190.2  |            | 118.1             |            | 102.1      | 146.6  |            | 106.9  | 87.4       |
| M @                                            |                 | 689.9  | 491.5      | 640.2             | 592.5      | 522.7      | 602.8  | 589.2      | 546.4  | 430.3      |
| M IMP                                          |                 | 157.0  | 111.8      | 142.9             | 99.2       | 132.2      | 157.2  | 88.6       | 122.0  | 108.8      |
| 45 (M <sub>s</sub> + IMP)                      |                 | 1411.5 | 1005.5     | 1305.2            | 819.5      | 1091.5     | 1233.3 | 796.3      | 1114.0 | 698.5      |
| M <sub>u</sub>                                 |                 | 2803.1 | 2775.2     | 2235.7            | 2057.1     | 2520.8     | 2474.6 | 2259.7     | 1742.1 | 1624.4     |
| f <sub>s</sub> @ N.C. ksi                      |                 | 7.95   | 10.44      | 4.25              | 8.00       | 4.27       | 7.22   | 15.50      | 4.02   | 9.54       |
| f <sub>s</sub> @ C.                            |                 | 2.30   |            | 1.43              |            | 1.24       |        | 2.05       |        | 1.07       |
| f <sub>s</sub> 45 (E + I)                      |                 | 15.68  | 9.29       | 14.32             | 8.60       | 11.98      | 13.72  | 11.42      | 12.39  | 9.67       |
| f <sub>s</sub> (TOTAL)                         |                 |        | 25.65      |                   | 21.58      |            | 29.60  | 32.39      |        | 24.97      |
| V <sub>R</sub>                                 | k               | 48.3   |            | 49.6              |            | 47.1       | 40.6   |            | 43.2   | 41.3       |
| M <sub>u</sub>                                 | ft-k            | 4325   |            | 4325              |            | 4325       | 4195   |            | 4195   | 4195       |
| f <sub>s</sub> (Over-Load) ksi                 |                 | 25.75  | 19.73      | 20.00             | 16.60      | 17.99      | 22.99  | 24.26      | 17.72  | 14.85      |



**ESCA**  
CONSULTANTS, INC.

DESIGNED BY: IRDP 1-89  
DRAWN BY: WEM 1-89  
CHECKED BY: JRF 1-89  
APPROVED BY: RDP 1-89



**SUPERSTRUCTURE STEEL DETAILS**  
FAI 74 OVER SEABOARD SYSTEMS R.R.  
FAI RTE. 74 SECTION (92-12VB-1)BR  
VERMILION COUNTY  
STATION 2203+43.26  
STRUCTURE NO. 092-0023(WB)  
STRUCTURE NO. 092-0024(EB)

MODEL: ST0001.DWG  
FILE: 092-0024-EB.DWG  
PROJECT: 092-0024-EB.DWG  
DATE: 8/15/2019

|            |                   |          |   |         |   |
|------------|-------------------|----------|---|---------|---|
| USER NAME  | = dawsonkb        | DESIGNED | - | REVISED | - |
| DRAWN      | -                 | REVISED  | - | REVISED | - |
| PLOT SCALE | = 40,0000 ' / in. | CHECKED  | - | REVISED | - |
| PLOT DATE  | = 8/15/2019       | DATE     | - | REVISED | - |

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION


FOR INFO ONLY - STRUCTURE DETAILS FOR  
LOCATIONS #5 & #6

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

| F.A.I. RTE. | SECTION                   | COUNTY             | TOTAL SHEETS | SHEET NO. |
|-------------|---------------------------|--------------------|--------------|-----------|
| 74          |                           | VERMILION          | 52           | 46        |
|             | D5 BRIDGE PAINTING 2020-1 | CONTRACT NO. 70E06 |              |           |
|             | ILLINOIS                  | FED. AID PROJECT   |              |           |

管帶裝(92-12VB-1)BR

1. PROVIDE SHEAR STUDS ON EXISTING STEEL BEAMS TO REMAIN AND ON NEW BEAMS AS SHOWN ON DETAILS ON THIS DWG. AND DWG. NO. 14 .
2. SEE DWG. NO. 14 FOR ADDITIONAL DETAILS OF STRUCTURAL STEEL.
3. AT EXISTING SPlice LOCATIONS WHERE NEW STEEL BEAMS ARE TO CONNECT TO EXISTING BEAMS, DRILL OUT EXISTING RIVETS IN EXISTING BEAMS TO REMAIN AND, IF REQUIRED, NEW BEAMS TO SIZE SHOWN ON SPlice DETAIL THIS DWG. PRESERVE AND REUSE SPlice PLATES.




### TABLE OF BEAM DIMENSIONS

| BEAM | a         | b       | c        | d        | e        | f        | g        | h       | i        | j        | k       | l        | m        | n        | o        | p       | q       | r        | s        | t        | u        | v       | w       |
|------|-----------|---------|----------|----------|----------|----------|----------|---------|----------|----------|---------|----------|----------|----------|----------|---------|---------|----------|----------|----------|----------|---------|---------|
| (8)  | 26.3°-6½° | 93°-8½° | 97°-10½° | 71°-11½° | 69°-11½° | 23°-8½°  | 29°-8°   | 47°-5½° | 20°-9½°  | 20°-9½°  | 51°-2½° | 18°-9½°  | 18°-10½° | 18°-10½° | 18°-10½° | 18°-4½° | 25°-3½° | 24°-9½°  | 23°-9½°  | 23°-11½° | 23°-8½°  | 22°-6½° | 23°-8°  |
| (9)  | 26.4°-5½° | 94°-0½° | 98°-3½°  | 72°-2½°  | 70°-2½°  | 23°-9½°  | 29°-9½°  | 47°-7½° | 20°-10½° | 20°-10½° | 51°-4½° | 18°-9½°  | 18°-11½° | 18°-11½° | 18°-11½° | 18°-5½° | 25°-4½° | 24°-10½° | 23°-10½° | 24°-0½°  | 25°-9½°  | 22°-8°  | 23°-9½° |
| (10) | 26.5°-5½° | 94°-4½° | 98°-7½°  | 72°-5½°  | 70°-5½°  | 23°-10½° | 29°-10½° | 47°-9½° | 20°-11½° | 20°-11½° | 51°-6½° | 18°-11½° | 19°-0°   | 19°-0°   | 19°-0°   | 18°-5½° | 25°-6½° | 25°-0°   | 24°-0°   | 24°-0½°  | 25°-11½° | 22°-9°  | 23°-9½° |

[illegible]

**\*\* Elevations Shown**  
are Top of Flange (not  
Top of Beam) or Cover (R)  
after jacking; they  
do not include deflec-  
tion, & are given for  
use in fabrication of  
new Stl. Beams & to  
assist the contractor  
in determining req'd  
thickness of Shim R's  
under bearings.




SECTION A A (A) *§ Brg. E. Abut.*

| ITEM                         | UNIT | QUANTITY |
|------------------------------|------|----------|
| Shear Studs                  | Each | 11,628   |
| Adjust & Reposition Bearings | Each | 36       |
| Structural Steel Removal     | Lbs. | 227600   |

Note  
32 New Flange P's & 32 New Web P's  
req'd. 4320  $\frac{7}{8}$ "  $\phi$  Flange Bolts and  
1980  $\frac{3}{4}$ "  $\phi$  Web Bolts req'd.

|              |     |   |
|--------------|-----|---|
| DESIGNED BY: | RDP | 6 |
| DRAWN BY:    | WEM | 6 |
| CHECKED BY:  | JRF | 7 |
| APPROVED BY: | RDP | 7 |


\* Includes Bolts for Connecting New Beams to Exist. Beams



Note  
Stud Spacing may be adjusted slightly  
at splice, to miss bolt locations.

REVISÉ 4-15-91

**SUPERSTRUCTURE**  
**STEEL DETAILS**  
**FAI 74 OVER SEABOARD SYSTEMSRR**  
**FAI RTE. 74 SECTION (92-12VB-1)BR**  
**VERMILION COUNTY**  
**STATION 2203+43.26**  
**STRUCTURE NO. 092-0023(WB)**  
**STRUCTURE NO. 092-0024(EB)**



|            |                   |          |   |         |   |
|------------|-------------------|----------|---|---------|---|
| USER NAME  | = dawsnkb         | DESIGNED | - | REVISED | - |
| DRAWN      | -                 | REVISOR  | - | REVISOR | - |
| PLOT SCALE | = 40,0000 ' / in. | CHECKED  | - | REVISOR | - |
| PLOT DATE  | = 8/15/2019       | DATE     | - | REVISOR | - |

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FOR INFO ONLY - STRUCTURE DETAILS FOR  
LOCATIONS #5 & #6

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

|                           |         |                    |              |           |
|---------------------------|---------|--------------------|--------------|-----------|
| F.A.I. RTE.               | SECTION | COUNTY             | TOTAL SHEETS | SHEET NO. |
| 74                        |         | VERMILION          | 52           | 48        |
| D5 BRIDGE PAINTING 2020-1 |         | CONTRACT NO. 70E06 |              |           |
| ILLINOIS                  |         | FED. AID PROJECT   |              |           |







44-38861-1000


1. THE CONTRACTOR SHALL SUBMIT FOR APPROVAL BY THE ENGINEER, PLANS FOR RAISING, SHIMMING, AND REPOSITIONING EXISTING BEAMS AND BEAMS PRIOR TO COMMENCING ANY RELATED WORK. THIS WORK SHALL BE DONE FOR EACH STAGE AFTER EXISTING CONCRETE DECK IS REMOVED AFTER NEW STEEL IS INSTALLED, AND PRIOR TO BUILDING OF NEW CONCRETE DECK. THE MAXIMUM DEAD LOAD REACTION PER BEAM (WEIGHT OF STEEL ONLY) AT ABUTMENTS IS 9 kips AND AT PIERS IS 27 kips.

- | EXISTING POSITION <sup>②</sup><br>(AT 50° F.)                                                                                        | ADJUSTED POSITION<br>(AT 50° F.)                                                  |
|--------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------|
| ① Horizontal Repositioning is req'd only if "d" is greater than or equal to 1/4" @ 50°F. as determined in the field by the Engineer. | ② D = 1/8" / 100 Ft. of expansion for every 15°F. above the normal temp. of 50°F. |
|                                                                                                                                      | ③ D = 1/8" / 100 Ft. of expansion for every 15°F. below the normal temp. of 50°F. |

NOTE: NEW PINTALS PLACED ON ROCKERS  
AT APTS DUE TO SEVERE  
DETERIORATION OF OLD PINTALS.

1. ALL EXISTING BEARINGS TO BE USED IN NEW CONSTRUCTION.
2. PROVIDE STEEL PLATES 1/2" UNDER ALL NEW AND EXISTING BEARINGS.
3. EXISTING BEAMS TO BE RAISED BY JACKING. SEE REPOSITIONING DETAIL THIS DRAWING.
4. SEE DWG. NO. 29 FOR ANCHOR BOLT DETAILS.
5. DETAILS ON THIS DRAWING DEPICT EXISTING BEARINGS AS WELL AS NEW BEARINGS.
6. PROVIDE ALL NEW LEAD PLATES AND PLATES P1, P2, & P3 (WITH NEW FIFTEEN OF P1 & P3), SUCH THAT NEW ANCHOR BOLT LOCATIONS WILL NOT CONFLICT WITH EXISTING. CUT ALL EXISTING ANCHOR BOLTS OFF FLOORS WITH TOP OF BEARING SEAT. REMOVE EXISTING BOTTOM PLATES AND LEAD PLATES.


FAI 74 OVER SEABOARD SYSTEMS RR  
FAI RTE. 74 SECTION (92-12VB-1)BR  
VERMILION COUNTY  
STATION 2203+43.26  
STRUCTURE NO. 092-0023(WB)  
STRUCTURE NO. 092-0024(EB)



STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

|        |         |      |        |      |         |
|--------|---------|------|--------|------|---------|
| SCALE: | SHEET 1 | OF 1 | SHEETS | STA. | TO STA. |
|--------|---------|------|--------|------|---------|

|                           |         |                    |                  |              |
|---------------------------|---------|--------------------|------------------|--------------|
| F.A.I.<br>RTE.            | SECTION | COUNTY             | TOTAL<br>SHEETS  | SHEET<br>NO. |
| 74                        | *       | VERMILION          | 52               | 50           |
| D5 BRIDGE PAINTING 2020-1 |         | CONTRACT NO. 70E06 |                  |              |
|                           |         | ILLINOIS           | FED. AID PROJECT |              |



| ROUTE No. | SECTION  | COUNTY    | TOTAL SHEETS | SHEET NO. |
|-----------|----------|-----------|--------------|-----------|
| 74        | 92-108-1 | VERMILION | 46           | 24        |

| ROUTE No. | SECTION  | COUNTY    | TOTAL SHEETS | SHEET NO. |
|-----------|----------|-----------|--------------|-----------|
| 74        | 92-108-1 | VERMILION | 46           | 24        |

| LOCATION | RIGHT BRIDGE | LEFT BRIDGE |
|----------|--------------|-------------|
| BEAM     | 12W40        | 12W40       |
| C        | 1/2          | 1/2         |
| D        | 1/2          | 1/2         |
| J        | 1/2          | 1/2         |

|                                                                                                                                            |
|--------------------------------------------------------------------------------------------------------------------------------------------|
| CONSOER, TOWNSEND & ASSOCIATES<br>CONSULTING ENGINEERS<br>CHICAGO, ILLINOIS                                                                |
| ILLINOIS DIVISION OF HIGHWAYS<br>FAI RT 74 OVER C. & N. E. I. R. R.<br>FAI - 74 SECTION 92-12VB-1, VF-1<br>VERMILION COUNTY STA 2203+43.26 |
| STRUCTURAL STEEL BEARING DEVICES                                                                                                           |
| DESIGNED: EER<br>DRAWN: EER<br>CHECKED: RBS<br>LOD<br>HSM 130-62                                                                           |



STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FOR INFO ONLY - STRUCTURE DETAILS FOR  
LOCATIONS #5 & #6

| F.A.I. RTE.               | SECTION | COUNTY    | TOTAL SHEETS | SHEET NO.          |
|---------------------------|---------|-----------|--------------|--------------------|
| 74                        |         | VERMILION | 52           | 51                 |
| D5 BRIDGE PAINTING 2020-1 |         |           |              | CONTRACT NO. 70E06 |
| ILLINOIS                  |         |           |              | FED. AID PROJECT   |

|                               |            |           |
|-------------------------------|------------|-----------|
| USER NAME = dawsonkb          | DESIGNED - | REVISED - |
| PLOT SCALE = 40,000' / 1" in. | DRAWN -    | REVISED - |
| PLOT DATE = 8/15/2019         | CHECKED -  | REVISED - |
|                               | DATE -     | REVISED - |

## DETAIL FOR TEMPORARY RUMBLE STRIPS (SPECIAL)



## SYMBOLS

- ▮ Sign
- || Temporary Rumble Strips (Special)
- ▮ Trailer Mounted Sign

## GENERAL NOTES

Remove the Temporary Rumble Strips (Special) prior to the removal of the advanced warning signs.

All dimensions are in inches (millimeters) unless otherwise shown.

|                              |            |           |
|------------------------------|------------|-----------|
| USER NAME = dawsonkb         | DESIGNED - | REVISED - |
|                              | DRAWN -    | REVISED - |
| PLOT SCALE = 40.0000 ' / in. | CHECKED -  | REVISED - |
| PLOT DATE = 8/15/2019        | DATE -     | REVISED - |

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

### DETAIL FOR TEMPORARY RUMBLE STRIPS (SPECIAL)

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

| F.A.I.<br>RTE.            | SECTION | COUNTY             | TOTAL<br>SHEETS | SHEET<br>NO. |
|---------------------------|---------|--------------------|-----------------|--------------|
| 74                        | *       | VERMILION          | 52              | 52           |
| D5 BRIDGE PAINTING 2020-1 |         | CONTRACT NO. 70E06 |                 |              |
| ILLINOIS                  |         | FED. AID PROJECT   |                 |              |

MODEL: \$MODELNAME\$  
FILE NAME: pw:\iplroom.dot.Illnols.gov:PW\IDOT\Documents\IDOT\_Offices\Disrlct\_5\Projects\DS70E06\CADData\Design\DS70E06-shr-Detalls.dgn