FOR INDEX OF SHEETS, SEE SHEET NO. 2

22,800

70.1%

5.3% 24.6%

9,150

95.0%

3.6%

1.4%

FAI 74 FARMER CITY RAMPS= WESTBOUND JUST OFF RAMP FAP 800 US 45 = SOUTHBOUND BY NCL of THOMASBORO

FAI 74 (FARMER CITY RAMPS)

TRAFFIC DATA LOCATIONS

2019 ADT =

FAP 800 (US 45)

2019 ADT

SU%

MU%

SU% MU%

0

0

0

FOR SUMMARY OF QUANTITIES, SEE SHEET NO. 4

**CURRENT TRAFFIC DATA** 

### STATE OF ILLINOIS

### **DEPARTMENT OF TRANSPORTATION**

#### D5 TREE REMOVAL 2020-1 \*FAI 74 & FAP BOO \*\*DEWITT & CHAMPAIGN AUNOIS CONTRACT NO. 70E35

#### P-95-009-20



# **PROPOSED** HIGHWAY PLANS

F.A.I. 74 (1-74) & F.A.P. 800 (U.S. 45) **SECTION D5 TREE REMOVAL 2020-1** TREE REMOVAL **DEWITT & CHAMPAIGN COUNTY** 

C-95-020-20

1-74; AT FARMER CITY EXIT;, US 45; AT NCL OF THOMASBORO

FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES, REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAIGNG MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS 1-800-892-0123 TOWNSHIPS: SANTA ANNA & RANTOUL

**PROJECT ENGINEER: JASON W. STULTS PROJECT MANAGER: AVOREE S. GORE** DESIGNERS: RAFAEL MONJARDIN, HANS KNOEPFEL

PHONE NUMBER: (217)-466-4181 CONTRACT NO. 70E35

SEE LOCATION MAP SHEET NO. 3

> STATE OF ELLINOIS DEPARTMENT OF TRANSPORTATION

> > PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

GROSS LENGTH = 1,830.00 FT = 0.347 MILE NET LENGTH = 1,830.00 FT = 0.347 MILE

#### **INDEX OF SHEETS**

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, HIGHWAY STANDARDS, AND GENERAL NOTES
3	LOCATION MAP
4	SUMMARY OF QUANTITIES
5	SCHEDULE OF QUANTITIES
6 TO 7	PLAN SHEETS

#### **HIGHWAY STANDARDS**

STANDARD	DESCRIPTION
000001-07	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001006	DECIMAL OF AN INCH AND OF A FOOT
701001-02	OFF-ROAD OPERATIONS, 2L, 2W, MORE THAN 15' (4.5 m) AWAY
701006-05	OFF-ROAD OPERATIONS, 2L, 2W, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
701101-05	OFF-RD OPERATIONS, MULTILANE, 15' (4.5m) TO 24" (600 mm) FROM PAVEMENT EDGE
701106-02	OFF-RD OPERATIONS, MULTILANE, MORE THAN 15' (4.5 m) AWAY
701901-08	TRAFFIC CONTROL DEVICES

#### **GENERAL NOTES**

G.N.-100A

ELECTRONIC FILES AND/OR ELECTRONIC SURVEY INFORMATION INCLUDING CADD FILES WILL NOT BE AVAILABLE TO THE CONTRACTOR.

G.N.-201

TREES THAT INTERFERE WITH THE CONSTRUCTION OPERATIONS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER. ANY TREE DUE TO ITS LOCATION AND DEEMED SUITABLE FOR SAVING BY THE ENGINEER SHALL BE PROTECTED DURING CLEARING AND SUBSEQUENT CONSTRUCTION OPERATIONS.

G.N.-250C-SPL

TEMPORARY EROSION CONTROL SEEDING IS INCLUDED IN THIS CONTRACT TO SEED DISTURBED EARTH DURING TIME PERIODS WHEN PERMANENT SEEDING IS NOT ALLOWED. SOME OR ALL OF THE TEMPORARY EROSION CONTROL SEEDING WILL BE DELETED IF IT IS POSSIBLE TO PLACE PERMANENT SEEDING ON EARTH AT THE TIME OF THEIR COMPLETION


#### NO COMMITMENTS

USER NAME = goreas	DESIGNED -	REVISED -	
	DRAWN -	REVISED -	
PLOT SCALE = 40.0000 ' / in.	CHECKED -	REVISED -	
PLOT DATE = 8/8/2019	DATE -	REVISED -	

## **LOCATION MAP**

LOCATION 1: I-74 WB (AT FARMER CITY EXIT) DEWITT CO.

LOCATION 2: U.S. 45 SOUTHBOUND (AT NCL OF THOMASBORO) CHAMPAIGN CO.



	SCALE	
0	1	2
0	5,000	10,000

USER NAME = monjardinrrt	DESIGNED -	REVISED -					LOCATION MAP		F.A. RTE	SECTION	COUNTY	TOTAL SHEET SHEETS NO.
	DRAWN -	REVISED -	STATE OF ILLINOIS						*	D5 TREE REMOVAL 2020-1	**	7 3
PLOT SCALE = 40.0048 / in	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION						**	DEWITT & CHAMPAIGN	CONTRAC	T NO. 70E35
PLOT DATE = 7/31/2019	DATE -	REVISED -		SCALE:	SHEET 1	OF 1	SHEETS STA.	TO STA.	*FAI 74	4 & FAP 800 ILLINOIS FED.	AID PROJECT	

## **SUMMARY OF QUANTITIES**

LOCATION OF WORK:

F.A.I 74 (I-74)

F.A.P. 800 (US 45)

RURAL

RURAL

STA. 822+00 TO STA. 832+00 DEWITT COUNTY STA. 470+80 to STA 479+10 CHAMPAIGN COUNTY

FUNDING BREAKOUT:

100% STATE

100% STATE

CONSTRUCTION TYPE CODE:

0031

0031

ITEM				
ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
TREE REMOVAL, ACRES	ACRE	2.25	1,00	1.25
SEEDING, CLASS 5	ACRE	2.25	1.00	1.25
NITROGEN FERTILIZER NUTRIENT	POLIND	203.00	90.00	113.00
THROUGH ENTERED TO THE ENTERED TO TH	T GOILE	200.00	00.00	110.00
PHOSPHORUS FERTILIZER NUTRIENT	POUND	203.00	90.00	113.00
POTASSIUM FERTILIZER NUTRIENT	POUND	203.00	90.00	113.00
MULCH, METHOD 2	ACRE	2.25	1.00	1.25
TEMPORARY EROSION CONTROL SEEDING	POUND	900.00	400.00	500.00
MOBILIZATION	L SUM	1.00	0.50	0.50
	TREE REMOVAL, ACRES  SEEDING, CLASS 5  NITROGEN FERTILIZER NUTRIENT  PHOSPHORUS FERTILIZER NUTRIENT  POTASSIUM FERTILIZER NUTRIENT  MULCH, METHOD 2  TEMPORARY EROSION CONTROL SEEDING	TREE REMOVAL, ACRES  ACRE  SEEDING, CLASS 5  ACRE  NITROGEN FERTILIZER NUTRIENT  POUND  PHOSPHORUS FERTILIZER NUTRIENT  POUND  POTASSIUM FERTILIZER NUTRIENT  POUND  MULCH, METHOD 2  ACRE  TEMPORARY EROSION CONTROL SEEDING  POUND	TREE REMOVAL, ACRES  ACRE  2.25  SEEDING, CLASS 5  ACRE  2.25  NITROGEN FERTILIZER NUTRIENT  POUND  PHOSPHORUS FERTILIZER NUTRIENT  POUND  POTASSIUM FERTILIZER NUTRIENT  POUND  203.00  MULCH, METHOD 2  ACRE  2.25  TEMPORARY EROSION CONTROL SEEDING  POUND  900.00	TREE REMOVAL, ACRES  ACRE  2.25  1.00  SEEDING, CLASS 5  ACRE  2.25  1.00  NITROGEN FERTILIZER NUTRIENT  POUND  PHOSPHORUS FERTILIZER NUTRIENT  POUND  POTASSIUM FERTILIZER NUTRIENT  POUND  POTASSIUM FERTILIZER NUTRIENT  POUND  ACRE  2.25  1.00  90.00  MULCH, METHOD 2  ACRE  2.25  1.00  TEMPORARY EROSION CONTROL SEEDING  POUND  900.00  400.00

USER NAME = goreas	DESIGNED -	REVISED -	
	DRAWN -	REVISED -	
PLOT SCALE = 40.0000 ' / in.	CHECKED -	REVISED -	
PLOT DATE = 8/8/2019	DATE -	REVISED -	
•			

## SCHEDULE OF QUANTITIES

TREE REMOVAL SCHEDULE

IREERE	INDVAL SCI		<u> </u>	
				20100501
				TREE REMOVAL
LOCATION	STATION	то	STATION	ACRE*
I-74 WB (FARMER CITY RAMPS)	822+00.00	ТО	832+00.00	1.00
US 45 SOUTHBOUND (THOMASBORO)	470+80.00	то	479+10.00	1.25
			TOTAL=	2.25
	2.25			

<sup>\*</sup>Note: Measured in CAD and Google Maps - rounded quantity

SEEDING SCHEDULE

		_	SELDI	NG SCHEDULE		
				25000320	28000250	25100115
				SEEDING, CLASS 5	TEMPORARY EROSION	MULCH
					CONTROL SEEDING**	METHOD 2
LOCATION	STATION	то	STATION	ACRE*	POUND	ACRE*
I-74 WB (FARMER CITY RAMPS)	822+00.00	то	832+00.00	1.00	400	1.00
US 45 SOUTHBOUND (THOMASBORO)	470+80.00	ТО	479+10.00	1.25	500	1.25
			TOTAL=	2.25	900	2.25
		ROUN	DED TOTAL =	2.25	900	2.25

#### FERTILIZER NUTRIENT SCHEDULE

TERRIEZER NOTHER TO OTHER DEE											
					25000400	25000500	25000600				
					NITROGEN FERTILIZER	PHOSPOROUS FERTILIZER	POTASSIUM FERTILIZER				
					NUTRIENT	NUTRIENT	NUTRIENT				
LOCATION	STATION	то	STATION	ACRE	POUND*	POUND*	POUND*				
I-74 WB (FARMER CITY RAMPS)	822+00.00	то	832+00.00	1.00	90.00	90.00	90.00				
US 45 SOUTHBOUND (THOMASBORO)	470+80.00	то	479+10.00	1.25	112.50	112.50	112.50				
			TOTAL=	2.25	202.50	202.50	202.50				
		ROUI	NDED TOTAL =	2.25	203.00	203.00	203.00				

\*Application Rate: 1 time--90 lb/acre


USER NAME = monjardinrrt	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 40.0003 / in.	CHECKED -	REVISED -
PLOT DATE = 8/1/2019	DATE -	REVISED -

SCALE:

SCHEDULE OF QUANTITIES						F.A. RTE	SEC.	TION	COUNTY	TOTAL SHEETS	SHEET NO.	
						*	D5 TREE REM	10VAL 2020-1	**	7	5	
SCHEDULE OF QUANTITIES					** DE'	WITT & CHAMPA	AIGN	CONTRACT	NO. 70	E35		
HEET	1	OF	1	SHEETS	STA.	TO STA.	*FAI 74	& FAP 800	ILLINOIS FED. A	ID PROJECT		

Notes: \*Area calculated in CAD and Google Earth - rounded quantity


\*\* Temporary Erosion Control Seeding application rate of 100 lbs/acre and 4 applications



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

\*\*DEWITT & CHAMPAIGN CONTRACT NO. 70E35 SHEET 1 OF 2 SHEETS STA.

## U.S. 45 SOUTHBOUND (AT NCL OF THOMASBORO) CHAMPAIGN CO.



\_\_\_\_

TREE REMOVAL, ACRES

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

MODEL: \$MODELNAME\$

FILE NAME: pw:\\planroom.dot.IIIInols.

pw:\\planroom.dot.lllInols.gov:PWIDOT\Do