



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 22, 2024

SUBJECT FAU Route 2503 (IL 25)
Section 2024-988-I
Kane County
Contract No. 62X13
Item No. 26, November 8, 2024 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised the Table of Contents to the Special Provisions
3. Added page 46 to the Special Provisions
4. Revised sheet 4 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF IMPROVEMENT	1
DESCRIPTION OF IMPROVEMENT	1
MAINTENANCE OF ROADWAYS (D1)	2
STATUS OF UTILITIES (D1).....	2
PUBLIC CONVENIENCE AND SAFETY (D1)	5
COMPLETION DATE PLUS WORKING DAYS (D1)	6
EMBANKMENT I (D1).....	6
ADJUSTMENTS AND RECONSTRUCTIONS (D1).....	8
ENGINEER'S FIELD OFFICE TYPE A (D1)	9
TRAFFIC CONTROL AND PROTECTION (ARTERIALS) (D1).....	9
TRAFFIC CONTROL PLAN (D1)	10
SELECTIVE CLEARING	11
TEMPORARY INFORMATION SIGNING	12
EARTH EXCAVATION (SPECIAL).....	13
WEEP HOLES CORED	14
TEMPORARY SOIL RETENTION SYSTEM (TO REMAIN IN PLACE).....	16
RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REPLACEMENT	17
CEMENT, TYPE IL (BDE)	17
COMPENSABLE DELAY COSTS (BDE)	18
CONCRETE SEALER (BDE)	21
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)	22
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE).....	24
ILLINOIS WORKS APPRENTICESHIP INITIATIVE – STATE FUNDED CONTRACTS (BDE).....	33
PORTLAND CEMENT CONCRETE (BDE)	33
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE).....	34
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....	35
STEEL COST ADJUSTMENT (BDE)	38
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	41
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	41
SUBMISSION OF PAYROLL RECORDS (BDE).....	42
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE).....	43
WEEKLY DBE TRUCKING REPORTS (BDE)	43
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	43
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)	46

Revised 10/22/2024

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)

Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites. The excavated soil and groundwater within the areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

Soil Disposal Analysis. When the waste material requires sampling for landfill disposal acceptance, the Contractor shall secure a written list of the specific analytical parameters and analytical methods required by the landfill. The Contractor shall collect and analyze the required number of samples for the parameters required by the landfill using the appropriate analytical procedures. A copy of the required parameters and analytical methods (from landfill email or on landfill letterhead) shall be provided as Attachment 4A of the BDE 2733 (Regulated Substances Final Construction Report). The price shall include all sampling materials and effort necessary for collection and management of the samples, including transportation of samples from the job site to the laboratory. The Contractor shall be responsible for determining the specific disposal facilities to be utilized; and collect and analyze any samples required for disposal facility acceptance using a NELAP certified analytical laboratory registered with the State of Illinois.

Site 25550A: 5th Avenue, St. Charles, Kane County

- Station 9+05 to Station 10+20 (CL 5th Avenue), 0 to 95 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Lead, and Manganese.
- Station 10+20 to Station 11+40 (CL 5th Avenue), 0 to 45 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminants of concern sampling parameters: Benzo(a)pyrene, and Manganese.

Work Zones

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites:
None

Added 10/22/24