

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION CODE
				URBAN
				100% STATE
				0044
20100110	TREE REMOVAL (6 TO 15 UNITS DIA)	EACH	7	7
20101200	TREE ROOT PRUNING	EACH	8	8
20100210	TREE REMOVAL (OVER 15 UNITS DIA)	EACH	1	1
21101600	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	CU YD	18	18
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	7	7
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	7	7
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	7	7
25200110	SODDING, SALT TOLERANT	SQ YD	340	340
28000400	PERIMETER EROSION BARRIER	FOOT	280	280
28000500	INLET AND PIPE PROTECTION	EACH	4	4
28001100	TEMPORARY EROSION CONTROL BLANKET	SQ YD	330	330
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	68	68
42001300	PROTECTIVE COAT	SQ YD	287	287
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1050	1050
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	214	214

* = SPECIALTY ITEM

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION CODE
				URBAN
				100% STATE
				0044
44000600	SIDEWALK REMOVAL	SQ FT	1050	1050
50102400	CONCRETE REMOVAL	CU YD	44	44
50200100	STRUCTURE EXCAVATION	CU YD	439	439
50800205	REINFORCEMENT BARS EPOXY COATED	POUND	4921	4921
50901760	PIPE HANDRAIL	FOOT	186	186
52200900	CONCRETE STRUCTURES (RETAINING WALL)	CU YD	46.7	46.7
58600101	GRANULAR BACKFILL FOR STRUCTURES	CU YD	260	260
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	150	150
66901001	REGULATED SUBSTANCES PRE- CONSTRUCTION PLAN	L SUM	1	1
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1
66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	1
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	214	214
66901006	REGULATED SUBSTANCES MONITORING	DAYS	4	4
67100100	MOBILIZATION	L SUM	1	1
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	360	360
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	634	634
70307120	TEMPORARY PAVEMENT MARKING - LINE 4"- TYPE IV TAPE	FOOT	1900	1900
70400100	TEMPORARY CONCRETE BARRIER	FOOT	335	335
70400125	PINNING TEMPORARY CONCRETE BARRIER	EACH	81	81

* = SPECIALTY ITEM

MODEL NUMBER
FILE NUMBER

DELTA ENGINEERING GROUP, LLC

111 W JACKSON BLVD, SUITE 910

CHICAGO, IL 60604

T 312.377.7700, F 312.427.6145

DESIGNED - NS

DRAWN - NS

CHECKED - MA

DATE - 8/8/2024

REVISED -

REVISED -

REVISED -

REVISED -

USER NAME = \$USERS	DESIGNED - NS	REVISED -
	DRAWN - NS	REVISED -
PLOT SCALE = \$SCALE\$	CHECKED - MA	REVISED -
PLOT DATE = \$DATES	DATE - 8/8/2024	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 25 (404 N 5TH AVENUE) - RETAINING WALL REPAIRS
SUMMARY OF QUANTITIES

SCALE:	SHEET	OF	SHEETS	STA.	TO STA.
--------	-------	----	--------	------	---------

1

REVISED SHEET 10/21/2024

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
106	2024-988-1	KANE	48	4
CONTRACT NO. 62X13				
ILLINOIS FED. AID PROJECT				