SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 0004 90% FED 10% STATE ROADWAY	0021 90% FED 5% STATE 5% ELGIN T. SIGNALS	0021 100% ELGIN EVP	0021 80% STATE 20% ELGIN SIDEWALK		
*	A2003220	TREE, CORYLUS COLURNA (TURKISH FILBERT),	EACH	2	2					
		2-1/2" CALIPER, BALLED AND BURLAPPED								
	X0322936	REMOVE EXISTING FLARED END SECTION	EACH	1	1					
	X2020110	GRADING AND SHAPING SHOULDERS	UNIT	4	4					
Δ	X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	44	44					
Δ	X5537900	STORM SEWERS TO BE CLEANED 15"	FOOT	80	80					
Δ	X5538000	STORM SEWERS TO BE CLEANED 18"	FOOT	120	120					
	X6020094	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1	EACH	1	1					
		FRAME, CLOSED LID, RESTRICTOR PLATE								
	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	3	3					
*	X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	1		1				
*	X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C,	FOOT	510			510			
		TWISTED, SHIELDED								
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
Δ	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5					
	Z0022800	FENCE REMOVAL	FOOT	70	70					
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	128.5	128.5					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 0004 90% FED 10% STATE ROADWAY	0021 90% FED 5% STATE 5% ELGIN T. SIGNALS	0021 100% ELGIN EVP	0021 80% STATE 20% ELGIN SIDEWALK		

* SPECIALTY ITEMS

Δ NON-PARTICIPATING ITEMS

FILE NAME = c:\pw_work\pwidot\paraynod\d0273204\P142209-Design.dgn	USER NAME = paraynod	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / In.	CHECKED -	REVISED -
	PLOT DATE = 8/23/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1320	581-N-1	COOK	50	8

CONTRACT NO. 60L43

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT