

CONDUIT ENTRANCE INTO MANHOLE/HANDHOLE APPLICABLE TO SWITCHGEAR AND TRANSFORMER VAULTS

GENERAL

CONDUIT ENTRANCES INTO MANHOLES/HANDHOLES SHALL NORMALLY BE MADE WITH PLASTIC ENTRANCE BELLS PER FIGURE 1 OR 2. THE ENTRANCE CONDUIT SHALL BE PLASTIC OR STEEL ENCASED IN CONCRETE AS PER FIGURE 1 AND 2 BELOW, SPECIFIED BY THE ENGINEER ON THE CONSTRUCTION DRAWINGS.

POCKETS

DUCT POCKETS SHALL BE PROVIDED IN WALLS WHERE SPECIFIED ON CONSTRUCTION DRAWINGS. POCKET NOT REQUIRED ON NEWER STYLE MANHOLE DESIGNS (FIGURE 2). TYPICAL POCKET DIMENSIONS ARE INDICATED BELOW ON FIGURE 1.

CONDUIT SPACING

CONDUIT SHALL NORMALLY BE SUPPORTED BY VERTICAL AND HORIZONTALLY INTERLOCKED PLASTIC SPACERS TO PROVIDE ALIGNMENT WITH PLASTIC ENTRANCE BELL UNITS AT 8 1/4 IN. SPACING.

ENTRANCE BELL UNITS

PLASTIC 6 INCH ENTRANCE BELLS, DPU-E# 285-103-00100 SHALL BE USED ON CONDUIT ENTRANCES TO MANHOLES.

ENTRANCE PIPES

GALVANIZED STEEL CONDUIT, M30-1550, SHALL BE USED FOR ALL BENDS. PIPES INTENDED FOR CABLES ON INITIAL INSTALLATION SHALL BE CAPPED WITH PLUGS (DPU-E# 285-103-00090) TO PREVENT CONTAMINATION FROM ENTERING THE PIPES.

INSTALLATION METHODS

EVERY EFFORT SHALL BE MADE TO INSURE A WATERTIGHT INSTALLATION OF ENTRANCE PIPES. WHERE PIPES ARE INSTALLED THROUGH AN OPENING LEFT IN A MANHOLE, OR BROKEN OUT OF AN EXISTING MANHOLE WALL, SURFACES SHALL BE CLEANED, WETTED AND COVERED WITH A COATING OF 3 TO 1 SAND AND CEMENT MORTAR. IF BRICKWORK IS EXISTING ON THE INNER FACE OF WALL, IT SHALL ALSO BE COATED WITH A SAND AND CEMENT MORTAR. AN ALTERNATE PROCEDURE IS TO DRILL HOLES IN THE WALL AND GROUT THE PIPES IN PLACE WITH A SAND AND CEMENT MORTAR. THE INSIDE SURFACE OF THE HOLES SHALL BE ROUGHENED TO OBTAIN A STRONG AND WATERTIGHT BOND.




FIG. 1 MANHOLE ENTRANCE WITH PLASTIC TERMINATORS (OLDER STYLE)
FOR PLASTIC OR STEEL CONDUIT (POCKET TYPE)




FIG. 2 ENTRANCE IN MANHOLE/HANDHOLE (NEWER STYLE)



NAPERVILLE PUBLIC UTILITIES DEPARTMENT ELECTRIC STANDARDS	DUCTBANK CONSTRUCTION SPECIFICATION	DATE: 04-24-07 Page 8 of 12 C30-1900
--	-------------------------------------	--

CONDUIT TO RISER AT POLE

CONDUIT TO RISER AT POLE
FOR PLASTIC OR STEEL CONDUIT

APPLICATION

- THIS STANDARD SHALL BE USED WHEN A TRANSITION FROM A SINGLE DUCT TO SINGLE RISER PIPE IS REQUIRED.



SUPPLEMENTARY MATERIAL


- IF BELLED END OF PLASTIC CONDUIT CAN BE CONNECTED TO STEEL BEND OMIT COUPLING.

NOTES:

- FIRST SECTION ABOVE ELBOW MUST BE SCHEDULE 80.
- FOR LARGER POLES (>50'), ADDITIONAL CONDUIT AND HARDWARE MAY BE REQUIRED.
- STEEL BEND AND POLE BRACKET EXISTING FROM PREVIOUS DUCT BANK INSTALLATION.
- INSTALL STEEL BEND AND POLE BRACKET AND CHANNEL.
- INSTALL SPARE OF CONDUIT UP POLE WITH BEND, ATTACH TO BRACKET AND PLUG.

NAPERVILLE PUBLIC UTILITIES DEPARTMENT ELECTRIC STANDARDS	DUCTBANK CONSTRUCTION SPECIFICATION	DATE: 04-24-07 Page 9 of 12 C30-1900
--	-------------------------------------	--

RISER CONSTRUCTION FOLLOW CONSTRUCTION STANDARD C20-5220




INFORMATION

- FIELD CUT SO THAT A GOOD CONNECTING FIT CAN BE MADE BETWEEN THE CONDUITS AND BENDS.
- LOCATE THE BEND ON A QUADRANT OF THE POLE WHERE IT IS THE LEAST SUSCEPTIBLE TO DAMAGE BY VEHICLES.
- IF SPARE DUCT IS INSTALLED, PLUG AT BOTH ENDS AND ENCASE IN CONCRETE WHEN NECESSARY.
- SCHEDULE 80 PVC DOES NOT REQUIRE CONCRETE ENCASEMENT.
- CONDUIT TO A U-GUARD* RISER FOLLOWS C20-5222, FOR USE AS MAINTENANCE ONLY.


PLASTIC CONDUIT COUPLINGS

SUBTITLE LINE TWO



PLASTIC TO PLASTIC OR PLASTIC TO STEEL COUPLING

SIZE	DPU-E #	MATERIAL / USE
3"	285-102-00040	PLASTIC TO PLASTIC
5"	285-102-00110	PLASTIC TO PLASTIC
6"	285-102-00140	PLASTIC TO PLASTIC
5"	285-102-00110	PLASTIC TO STEEL
6"	285-102-00140	PLASTIC TO STEEL



PLASTIC TO PLASTIC 5" COUPLING

SIZE	DPU-E #	MATERIAL / USE
3"	285-102-00050	PLASTIC TO PLASTIC
5"	285-102-00120	PLASTIC TO PLASTIC
6"	285-102-00150	PLASTIC TO PLASTIC


PLUG W/PULL TAB

SIZE	DPU-E #
3"	285-103-00030
5"	285-103-00070
6"	285-103-00090

APPLICATION


THIS STANDARD SHALL BE USED FOR THE INSTALLATION OF CONDUIT CONNECTIONS ON CONCRETE ENCASED PLASTIC CONDUIT DUCTBANK.

NAPERVILLE PUBLIC UTILITIES DEPARTMENT ELECTRIC STANDARDS	DUCTBANK CONSTRUCTION SPECIFICATION	DATE: 04-24-07 Page 10 of 12 C30-1900
--	-------------------------------------	---




PLASTIC TO PLASTIC OR PLASTIC TO STEEL SLEEVE

SIZE	DPU-E #	MATERIAL / USE
3"	285-102-00060	PLASTIC TO PLASTIC
5"	285-102-00100	PLASTIC OR STEEL
6"	285-102-00130	PLASTIC OR STEEL



PLASTIC BELL END FITTINGS

SIZE	DPU-E #	MATERIAL
3"	285-103-00040	PLASTIC
5"	285-103-00080	PLASTIC
6"	285-103-00100	PLASTIC



THE 6" EXPANDING PLUG W/EYE NUT DPU-E# 285-103-00150

ROUTE 59 ROAD IMPROVEMENTS

PROJECT TITLE				ROUTE 59 ROAD IMPROVEMENTS			
PROJECT DESCRIPTION							
ENGINEER	DRAFTING DATE	MAP #	SCALE				
BCC	5-11-12	4211,4212,4223	N.T.S.				
GIS DESIGN BY	DRAFTED BY	AT&T JOINT AGREEMENT #	PROJECT #				
DL	PSM	N/A	EU-12				
CHECKED BY	APPROVED BY	CAD FILE	SHEET #				
		0060648001D130.DWG	30 OF 63				

Naperville	Department of Public Utilities Electric Division	WORK REQUEST # 60468
------------	---	-------------------------