



RESTORATION OF WORK AREA, RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEMS SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

GEVALT HAMILTON PLIANS CIATES, INC.

USER NAME = ZACH WALLSTEN	DESIGNED	-	JRD	REVISED	-
	DRAWN	-	ZCW	REVISED	-
PLOT SCALE = 1" = .0833"	CHECKED	-	KLB	REVISED	-
PLOT DATE = 8/15/2012	DATE	-	8/15/2012	REVISED	-

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

TRAFFIC SIGNAL MODERNIZATION PLAN

IL 62 (ALGONQUIN RD) AT DEMPSTER STREET

SCALE 1"=20" SHEET NO. OF SHEETS STA TO STA

| COUNTY | COUNTRACT # 60 T82 | COUNTRACT #