SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE: SIDEWALK/LIGHTS 0031 QUANTITY	CONSTRUCTION TYPE CODE: LANDSCAPING 0031 QUANTITY
X6026052	SANITARY MANHOLES FRAME AND ADJUSTMENT SEALING	EACH	4	4	
* X8140115	HANDHOLE TO BE ADJUSTED	EACH	9	9	
* X8360215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	18	18	
* X8360315	LIGHT POLE FOUNDATION, 30" DIAMETER, OFFSET	FOOT	105	105	
XX000959	TRASH RECEPTACLES	EACH	10		10
XX001186	PLANTER REMOVAL	EACH	1	1	
XX001621	BRICK PAVER REMOVAL	SQ FT	123	123	
XX003689	BUS SHELTER	EACH	2		2
XX004688	BRICK PAVER SIDEWALK	SQ FT	7,966		7,966
XX008277	PORTLAND CEMENT CONCRETE UNDERLAYMENT, 5"	SQ YD	885		885
* XX008280	ORNAMENTAL STREET LIGHTING UNIT - SINGLE TEARDROP FIXTURE	EACH	41	41	
* XX008281	ORNAMENTAL STREET LIGHTING UNIT - SINGLE ACORN FIXTURE	EACH	16	16	
* XX008730	DOUBLE HANDHOLE TO BE ADJUSTED	EACH	1	1	
* X8163585	UNIT DUCT, 600V, 7-1/C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 2" DIA. POLYETHYLENE	FOOT	3,051	3,051	
* X8163575	UNIT DUCT, 600V, 5-1/C NO.6, 3-1/C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 2" DIA. POLYETHYLENE	FOOT	3,288	3,288	

* INDICATES SPECIALTY ITEM

COPYRIGHT © 2012 BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
LICENSE NO. 184-000512 EXPIRES 4/30/2013
5/14/2012 2:27:25 AM