SUMMARY OF QUANTITIES

GENERAL NOTES

			URBAN 100 % STATE 0014
Pay Item Number	Description	Units	Total Quantily
52000320	NEOPRENE EXPANSION JOINT 2"	FOOT	66
52000340	NEOPRENE EXPANSION JOINT 4"	F00T	66
67/00/00	MOBILIZATION	L SUM	1
70100420	TRAFFIC CONTROL AND PROTECTION STANDARD 701411	EACH	2
70100700	TRAFFIC CONTROL AND PROTECTION STANDARD 701406	L SUM	1
20001905	STRUCTURAL STEEL REPAIR	POUND	800
X0327286	SUBSTRUCTURE REPAIRS (GROUT BAGS)	L SUM	1

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123.

All Borrow/Waste/Use sites must be approved by the Department prior to removing any material from the project or initiating any earth moving activities, including temporary stockpiling outside the limits of construction.

The cost of the removal of existing expansion joints is included in the pay item Neophrene Expansion Joint 2" and Neophrene Expansion Joint 4".

FILE NAME .	USER NAME : bortage	DESIGNED -	REVISED -			F.A. SECTION	COUNTY TOTAL SHEET
\\CENTRAL\Shorad\D2\B8\CONSTANTIN\64E	3 88 Repairs\64E33 SQD.dgn	DRAWN -	REVISEO -	STATE OF ILLINOIS	Summary of Quantities	A I I I I I I I I I I I I I I I I I I I	COUNTY SHEETS NO.
	PLOT SCALE + 189,0000 '/ In.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION		I-80 (81-18)M-4	CONTRACT NO. 64F33
	FLOT DATE : Hon Aug 06 87:33:48 28:2	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FEO. ROAD DIST. NO. HELINOIS FED. AL	10 PROJECT