

INTERSTATE PAVEMENT

LOCATION			AGGREGATE SUBGRADE IMPROVEMENT 12"	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	WHITEWASHING FOR CONCRETE PAVEMENT	BITUMINOUS MATERIALS (PRIME COAT)	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	PROTECTIVE COAT	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 11"	PAVEMENT REINFORCEMENT
ROAD	STATION FROM	STATION TO	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)
I-74	464+54.59	471+00.00	5,071	5,071	5,071	5,071	10			5,493		2,582	2,582
I-74	471+00.00	486+00.00	19,527	19,527	19,527	19,527	39			20,534		11,200	11,200
I-74	486+00.00	501+00.00	21,459	21,459	21,459	21,459	43			22,184		14,021	14,021
I-74	501+00.00	516+00.00	23,024	23,024	23,024	23,024	46			24,020		15,932	15,932
I-74	516+00.00	531+00.00	21,940	21,940	21,940	21,940	44			22,826		14,087	14,087
I-74	531+00.00	546+00.00	20,377	20,377	20,377	20,377	41			21,141		12,518	12,518
I-74	546+00.00	561+00.00	18,051	18,051	18,051	18,051	36			16,753	1,994	9,667	9,667
I-74	561+00.00	576+00.00	14,203	14,203	14,203	14,203	28			13,020	2,257	6,824	6,824
I-74	576+00.00	591+00.00	18,633	18,633	18,633	18,633	37			19,400		11,333	11,333
I-74	591+00.00	606+00.00	8,119	8,119	8,119	8,119	16			7,952		4,619	4,619
I-74	606+00.00	621+00.00	1,816	1,816	1,816	1,816	4			1,791		967	967
I-155	00+00.00	13+00.00	9,461	9,461	9,461	9,461	19			8,950	736	2,954	8,950
I-155	13+00.00	28+00.00	17,539	17,539	17,539	17,539	35			17,603		9,449	17,603
I-155	28+00.00	35+90.00	8,290	8,290	8,290	8,290	17			8,114		4,601	8,114
Ramp E (I-155)	200+00.00	214+00.00	2,911	2,911	2,911	2,911	6			1,762		2,816	2,816
Ramp E (I-155)	214+00.00	229+00.00	1,649	1,649	1,649	1,649	3			1,598		1,051	1,598
Ramp F (I-155)	311+00.00	326+00.00	6,988	6,988	6,988	6,988	14			6,840		3,819	6,840
Ramp F (I-155)	326+00.00	341+00.00	6,058	6,058	6,058	6,058	12			5,936		3,428	5,936
Ramp G (I-155)	10+00.00	25+00.00	3,209	3,209	3,209	3,209	6			3,102		1,952	3,102
Ramp G (I-155)	25+00.00	39+33.16	4,332	4,332	4,332	4,332	9			4,860		2,205	4,860
Ramp H (I-155)	100+00.00	115+00.00	3,489	3,489	3,489	3,489	7			3,360		2,065	3,360
Ramp H (I-155)	115+00.00	130+00.00	4,279	4,279	4,279	4,279	9			4,132		2,617	4,132
Ramp B (Mort. Ave.)	04+01.99	10+00.00	764	764	764	764	2	426		1,224			1,224
Ramp D (Mort. Ave.)	1000+00.00	1112+00.00	3,182	3,182	3,182	3,182	6	1,856		2,532			2,532
Ramp D (Mort. Ave.)	1112+00.00	1124+03.28	2,420	2,420	2,420	2,420	5	1,526		2,801			2,801
Ramp E (Mort. Ave.)	10+00.00	20+00.00	1,887	1,887	1,887	1,887	4	1,145		1,462			1,462
Ramp E (Mort. Ave.)	20+00.00	32+41.53	2,415	2,415	2,415	2,415	5	1,506		1,817			1,817
Ramp F (Mort. Ave.)	1000+00.00	1011+00.00	1,988	1,988	1,988	1,988	4	1,222		2,438			2,438
Ramp F (Mort. Ave.)	1011+00.00	1021+10.65	5,163	5,163	5,163	5,163	10	4,085		4,912			4,912
TOTAL			258,244	258,244	258,244	258,244	517	11,766	35,903	259,611	4,987	103,750	103,750

NON-INTERSTATE PAVEMENT

LOCATION			SUBBASE GRANULAR MATERIAL, TYPE A 4"	SUBBASE GRANULAR MATERIAL, TYPE A 12"	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	BITUMINOUS MATERIALS (PRIME COAT)	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	PROTECTIVE COAT	CLASS D PATCHES, TYPE III, 6 INCH	CLASS D PATCHES, TYPE IV, 16 INCH
ROAD	STATION FROM	STATION TO	(SQ YD)	(SQ YD)	(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)
Morton Ave.	26+94.00	33+00.00	6,309	6,309			4,870	7,261			
Morton Ave.	33+00.00	39+00.00	4,624	4,624			3,554	5,163			
Morton Ave.	39+00.00	45+00.00	5,915	5,915			4,029	7,464			
Morton Ave.	45+00.00	49+30.67	4,240	4,240			3,025	3,577			
Jefferson St.	18+71.86	20+50.00		836	342	83	2	433			
Jefferson St.	20+50.00	26+50.00		2,565	1,031	250	5	1,627			
Jefferson St.	26+50.00	28+50.00		850	341	83	2	964	22		
Jackson St.	38+00.00	44+00.00		80				679			80
TOTAL			21,088	25,419	1,714	416	9	15,478	27,168	22	80

MEDIAN, CURB & GUTTER

LOCATION			COMBINATION CURB AND GUTTER, TYPE B-6.06	COMBINATION CURB AND GUTTER, TYPE B-6.12	COMBINATION CURB AND GUTTER, TYPE B-6.18	COMBINATION CURB AND GUTTER, TYPE B-6.24	CONCRETE MEDIAN SURFACE, 4 INCH	CONCRETE MEDIAN, TYPE SB-6.24	CORRUGATED MEDIAN	PRISMATIC CURB REFLECTOR
ROAD	STATION FROM	STATION TO	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(SQ FT)	(SQ FT)	(EACH)
Morton Ave.	26+94.00	33+00.00				1,587	8,943	497		35
Morton Ave.	33+00.00	39+00.00	18	22	39	444	3,389	3,466		65
Morton Ave.	39+00.00	45+00.00	58			1,251	9,190		6,299	59
Morton Ave.	45+00.00	49+30.67				519	519			14
Jefferson St.	18+71.86	20+50.00				356				
Jefferson St.	20+50.00	26+50.00				1,200				
Jefferson St.	26+50.00	28+50.00				400				
Jackson St.	38+00.00	44+00.00								
TOTAL			76	22	39	5,757	22,041	3,963	6,299	173

SHOULDERS

LOCATION			AGGREGATE SHOULDERS, TYPE B 6"	PORTLAND CEMENT CONCRETE SHOULDERS 10"	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/4"	PORTLAND CEMENT CONCRETE SHOULDERS 11"	SHOULDER RUMBLE STRIPS, 16 INCH
ROAD	STATION FROM	STATION TO	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(FOOT)
I-74	464+54.59	471+00.00	110			2,525	1,291
I-74	471+00.00	486+00.00	501			7,919	5,600
I-74	486+00.00	501+00.00	416			6,771	6,000
I-74	501+00.00	516+00.00	362			6,596	5,070
I-74	516+00.00	531+00.00	615			7,202	4,864
I-74	531+00.00	546+00.00	550			7,208	5,338
I-74	546+00.00	561+00.00	331			5,761	4,118
I-74	561+00.00	576+00.00	41			5,053	4,390
I-74	576+00.00	591+00.00	533			6,732	4,404
I-74	591+00.00	606+00.00	667			3,333	3,000
I-74	606+00.00	621+00.00	110			824	458
I-155	00+00.00	13+00.00	372		5,312		4,056
I-155	13+00.00	28+00.00	900		7,679		5,141
I-155	28+00.00	35+90.00	703		3,513		3,161
Ramp E (I-155)	200+00.00	214+00.00	380		1,054		
Ramp E (I-155)	214+00.00	229+00.00	196		547		
Ramp F (I-155)	311+00.00	326+00.00	589		3,021		
Ramp F (I-155)	326+00.00	341+00.00	481		2,508		
Ramp G (I-155)	10+00.00	25+00.00	429		1,150		
Ramp G (I-155)	25+00.00	39+33.16	339		1,695		
Ramp H (I-155)	100+00.00	115+00.00	517		1,295		
Ramp H (I-155)	115+00.00	130+00.00	581		1,515		
Morton Ave.	26+94.00	33+00.00	148	798			
Morton Ave.	33+00.00	39+00.00	126	676			
Morton Ave.	39+00.00	45+00.00	195	1,275			
Morton Ave.	45+00.00	49+30.67	54	317			
Ramp B (Mort. Ave.)	04+01.99	10+00.00	104	311			
Ramp D (Mort. Ave.)	1000+00.00	1112+00.00	431	1,216			
Ramp D (Mort. Ave.)	1112+00.00	1124+03.28	267	827			
Ramp E (Mort. Ave.)	10+00.00	20+00.00	251	679			
Ramp E (Mort. Ave.)	20+00.00	32+41.53	304	831			
Ramp F (Mort. Ave.)	1000+00.00	1011+00.00	157	703			
Ramp F (Mort. Ave.)	1011+00.00	1021+10.65	338	980			
Jefferson St.	18+71.86	20+50.00					
Jefferson St.	20+50.00	26+50.00					
Jefferson St.	26+50.00	28+50.00					
Jackson St.	38+00.00	44+00.00	44				
TOTAL			12,142	8,613	29,289	59,924	56,891

FILE NAME =	DESIGNED - EJA	REVISED -		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...D468620-sh-t-schedule_01.dgn	DRAWN - TMB	REVISED -				90-[14R]14HB-4,14,14HB[B]R	TAZEWELL	2433	71	
USER NAME = jreambillo	CHECKED - JNR	REVISED -				CONTRACT NO. 68620				
PLOT DATE = 7/20/2012	DATE - JULY 20, 2012	REVISED -				ILLINOIS	FED. AID PROJECT			
SCALE: NTS		SHEET NO. 1 OF 6 SHEETS		STA. TO STA.						