

FUNDING:	80% FEDERAL/ 20% STATE		
LOCATION:	URBAN		
COUNTY:	WILLIAMSON		
ROUTE:	FAP 331 (IL 13)	FAP 331 (IL13/IL37 INTERSECTION)	FAP 331 (IL 13)
CONST TYPE CODE:	0003	0003	0021

CODE NUMBER	PAY ITEM DESCRIPTION	UNIT	PROJECT TOTAL QUANTITY	ROADWAY	ROADWAY	SIGNALS & LIGHTING
X 88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2			2
X 88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	2			2
X 88102830	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED	EACH	1			1
X 88200100	TRAFFIC SIGNAL BACKPLATE	EACH	12			12
X 88500100	INDUCTIVE LOOP DETECTOR	EACH	17			17
X 88600100	DETECTOR LOOP, TYPE I	FOOT	2,710			2,710
X 88800100	PEDESTRIAN PUSH-BUTTON	EACH	4			4
X 89501250	RELOCATE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1			1
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2			2
X4402805	ISLAND REMOVAL	SQ FT	109	109		
X4403800	MEDIAN SURFACE REMOVAL	SQ FT	4,941	4,941		
X5010522	REMOVE CONCRETE END SECTION	EACH	1	1		
X6024242	INLETS, SPECIAL, NO. 1	EACH	49	43	6	

X SPECIALTY ITEM

FILE NAME = c:\pwwork\pvidot\kellykd\0184451\78203	USER NAME = *USER* shl-sched.dgn	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES SHEET 11 OF 13			F.A.P. RTE. 331	SECTION 11X-11R-5,RS-3,N-5,TS-4	COUNTY WILLIAMSON	TOTAL SHEETS 288	SHEET NO. 15
PLOT SCALE = 1/8"=1'-0"		CHECKED -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT NO. 78203				
PLOT DATE = 5/10/2012		DATE -	REVISED -		ILLINOIS FED. AID PROJECT							