

## HMA PAVEMENT SCHEDULE

LOCATION STA TO STA	HMA PAVEMENT (FULL-DEPTH), 14 3/4"					SUBBASE GRANULAR MATERIAL TYPE A, 8"	HMA SURFACE REMOVAL, 3 1/4"	POLYMERIZED HMA BINDER COURSE, IL-19.0 N105	POLYMERIZED HMA SURFACE COURSE, MIX "E", N105	TEMPORARY RAMP	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	
	FOR INFORMATION ONLY												
	POLY HMA SURFACE COURSE, MIX "E", N105	POLY HMA BINDER COURSE, IL-19.0, N105	HMA BINDER COURSE, IL-19.0, N90	UNDER CC&G HMA BINDER COURSE, IL-19.0, N90	SQ YD								SQ YD
IL 13													
EBL													
STA 861+86.82													
STA 861+86.82 TO STA 867+17.18									16.8				
STA 861+86.82 TO STA 871+11.22	127.1	235.8	933.5		1,506.3	1,506.3		1,143.1	112.4	96.5	102.9	1.7	
STA 867+17.18 TO STA 871+83.54								1,633.2	160.1	137.2	147.0	2.4	
STA 871+11.22 TO STA 872+49.71	15.4	28.2	107.7		183.1	183.1		1,703.1	166.9	143.1	153.3	2.6	
STA 871+83.54 TO STA 876+84.57													
STA 872+49.71 TO STA 876+20.32	41.8	77.7	310.2		495.0	495.0							
STA 876+20.32 TO STA 880+16.17 BK	44.3	81.2	309.9	75.6	527.0	527.0							
STA 876+84.57 TO STA 881+22.40								911.7	89.3	76.6	82.1	1.4	
STA 880+15.69 AH TO STA 883+25.00	34.7	63.6	243	59.1	413.3	413.3							
STA 881+22.40 TO STA 883+25.00								984.6	96.5	82.7	88.6	1.5	
STA 883+25.00										42.0			
WBL													
STA 862+76.01													
STA 862+76.01 TO STA 871+83.87										42.7			
STA 862+76.01 TO STA 864+51.33	29.4	53.9	205.9	11.9	350.2	350.2		2,596.7	254.9	218.5	233.7	3.9	
STA 864+51.33 TO STA 880+15.53 BK	175.2	321.2	1226.6	258.3	2,086.0	2,086.0							
STA 871+83.87 TO STA 876+84.36								1,691.1	165.7	142.1	152.2	2.5	
STA 876+84.36 TO STA 883+25.00								2,420.5	237.2	203.3	218.2	4.0	
STA 880+15.69 AH TO STA 883+25.00	34.7	63.6	242.9	21.2	413.1	413.1							
STA 883+25.00										29.5			
<b>SCHEDULE TOTAL</b>					<b>5,974.0</b>	<b>5,974.0</b>		<b>13,084.0</b>	<b>1,283.0</b>	<b>1,100.0</b>	<b>131.0</b>	<b>1,178.0</b>	<b>20.0</b>
FROM SHOULDER SCHEDULE						1214						385	
FROM PCC PAVEMENT SCHEDULE						9154							
FROM CURB & GUTTER SCHEDULE						2781							
<b>PROJECT TOTAL</b>					<b>5,974</b>	<b>19,123</b>		<b>13,084</b>	<b>1,283</b>	<b>1,100</b>	<b>131</b>	<b>1,563</b>	<b>20</b>