

## SIDEWALK SCHEDULE

LOCATION STA TO STA	PCC SIDEWALK 5"	DETECTABLE WARNINGS	PROTECTIVE COAT
	SQ FT	SQ FT	SQ YD
<b>IL 13</b>			
<b>EBL</b>			
STA 857+75.00 TO STA 8+40.24 (RUSSELL)	1,340.2		148.9
STA 859+72.80		10.0	
STA 877+22.30		10.0	
STA 877+09.33 TO STA 8+75.46 (HIGHLAND)	1,690.7		187.9
STA 879+80.50		10.0	
STA 880+43.13 TO STA 883+47.94	1,654.9		183.9
STA 880+57.30		10.0	
<b>WBL</b>			
STA 859+12.43 TO STA 11+67.33 (RUSSELL)	963.4		107.0
859+74.25		20.0	
860+81.50		10.0	
STA 860+75.39 TO STA 871+43.01	5,474.3		608.3
871+35.50		10.0	
872+30.25		10.0	
STA 872+18.24 TO STA 876+48.19	2,130.0		236.7
876+36.67		10.0	
STA 877+25.69 TO STA 880+15.53 BK	1,432.7		159.2
877+40.50		10.0	
STA 880+15.69 AH TO STA 883+45.87	1,631.6		181.3
883+37.75		10.0	
STA 883+81.62 TO STA 886+51.99	2,093.3		232.6
883+90.75		10.0	
886+47.10		10.0	
<b>RUSSELL ST.</b>			
STA 8+48.00		10.0	
STA 11+58.50		10.0	
<b>HIGHLAND ST.</b>			
RT STA 9+01.84 TO STA 9+22.86	112.9		13.2
<b>SCHEDULE TOTAL</b>			
	18,524.0	160.0	2,059.0
FROM PCC PAVEMENT SCHEDULE			
			9,154.0
FROM CURB & GUTTER SCHEDULE			
			3,485.0
<b>PROJECT TOTAL</b>			
	18,524	160	14,698

FILE NAME *	USER NAME = lavenderba	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE - SIDEWALK</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr:\pwork\pvidat\lavenderba\d018451\7203-shl-sched.dgn		DRAWN -	REVISED -			331	(1X-1)R-5,RS-3,N-5,TS-4	WILLIAMSON	288	32	
PLOT SCALE = 1/8"=880' / 1"		CHECKED -	REVISED -			CONTRACT NO. 78203					
PLOT DATE = 9/12/2012		DATE -	REVISED -			[ILLINOIS] FED. AID PROJECT					