STORM SEWER SCHEDULE

LOCATION STA TO STA	STORM SEWERS, CLASS A, TYPE 1 12" FOOT	15" FOOT	18" FOOT	24" FOOT	30" FOOT	42" FOOT	54" FOOT	66" FOOT	EQUIV. ROUND - SIZE 24" FOOT	EQUIV. ROUND - SIZE 30" FOOT	EQUIV. ROUND - SIZE 42" FOOT	STORM SEWERS JACKED IN PLACE, 24" FOOT	INSERTION CULVERT LINER 63" FOOT	PIPE CLUVERTS, CLASS C, TYPE 1 15" FOOT	TRENCH BACKFILL CU YD	CONCRETE COLLAR CU YD
LT STA 875+02.57 TO STA 875+95.93	89.0														55.7	
LT STA 875+95.93 TO STA 876+48.62	49.0														9.8	
LT STA 877+24.48 TO STA 878+41.16	113.0														34.3	
LT STA 878+41.16 TO STA 879+17.66	72.0														15.7	
LT STA 879+17.66 TO STA 879+61.66	39.0														4.3	
LT STA 879+61.66 TO STA 880+22.32	56.0														11.8	
LT STA 880+22.32 TO STA 880+68.32	41.0														9.3	
LT STA 880+68.32 TO STA 881+11.27		38.0													9.1	
LT STA 881+11.27 TO STA 881+63.77		48.0													33.2	
LT STA 881+63.77 TO STA 881+81.76	13.0														9.0	
LT STA 881+81.76 TO STA 882+63.61	77.0														13.7	
LT STA 883+43.58 TO STA 883+45. CONNECT TO EXIST INLET	23.0														0.8	
LT STA 883+84.22 TO STA 884+05.11	20.0														1.9	
LT STA 883+83. TO STA 884+05.11 CONNECT TO EXIST INLET	26.0														0.9	
LT STA 884+05.11 TO STA 884+79.65	70.0														4.9	
LT STA 884+79.65 TO STA 885+60.86	77.0														6.8	
LT STA 886+41.22 TO STA 886+76. CONNECT TO EXIST INLET	96.0														7.7	
LT STA 886+41.22 TO STA 886+50. CONNECT TO EXIST SS	11.0														1.0	
LT STA 886+50.																0.24
RUSSELL ST.																
LT STA 7+25. TO STA 8+61.49 CONNECT TO EXIST INLET										137.0					49.1	
LT STA 8+61.49 TO STA 9+07.35					51.0										19.1	
LT STA 9+07.35 TO STA 10+57.1				17.0								130.0			39.7	
LT STA 10+44.8 TO STA 10+57.1		70.0													6.8	
LT STA 10+57.1 TO STA 11+30.28				70.0											27.2	
LT STA 11+30.28 TO STA 12+09.32				75.0											20.0	
LT STA 12+09.32 TO STA 12+13.9														8.0	2.7	
RT STA 9+11.17 TO STA 9+14.4										33.0						
RT STA 9+14.4 TO STA 10+71.85									41.0			115.0			12.4	
RT STA 10+71.85 TO STA 10+94.76									22.0						2.0	
RT STA 10+94.76 TO STA 11+32.93									36.0						2.9	
RT STA 11+32.93 TO STA 12+07.35				70.0											19.4	
RT STA 12+07.35 TO STA 12+14.37														14.0	7.1	
PROJECT TOTAL	2,204	359	279	232	51	26	26	20	99	170	117	245	115	22	927	0.24