

TEMPORARY PAVEMENT MARKING SCHEDULE

3 OF 3

LOCATION STA TO STA	TEMPORARY PAVEMENT MARKING,					
	LETTERS & SYMBOLS	- LINE 4"			- LINE 12"	- LINE 24"
		WHITE		YELLOW		
		SOLID	SKIP DASH	SOLID		
SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	
BENTLEY ST.						
RT STA	9+40.76					29.0
LT STA	10+58.93					33.0
VICKSBURG ST.						
RT STA	9+27.81					18.0
LT STA	10+55.44					29.0
HIGHLAND ST.						
RT STA	9+34.38					23.0
JOHNSON ST.						
RT STA	9+02.48	"ONLY"	20.8			
RT STA	9+28.06	RT ARROW	15.6			
RT STA	9+46.00					19.0
LT STA	10+58.43					14.0
LT STA	10+70.14	RT ARROW	15.6			
LT STA	10+95.78	"ONLY"	20.8			
RUSSEL ST.						
STA	8+00.00	TO	STA	9+19.93		
	STA 8+07.82		"ONLY"	20.8	120.0	240.0
RT STA	8+61.60		"ONLY"	20.8		
	STA 8+65.00		LT ARROW	15.6		
RT STA	8+87.28		RT ARROW	15.6		
LT STA	9+07.28	TO	STA	10+57.45	306.0	
RT STA	9+13.56					18.0
RT STA	9+20.06					24.0
LT STA	10+70.02					44.0
	STA 10+70.02	TO	STA	11+80.98	333.0	222.0
RT STA	11+02.34		"ONLY"	21.6		
	STA 11+09.25		LT & RT ARROWS	31.2		
RT STA	11+59.50		RT ARROW	15.6		
	STA 11+66.16		2 "ONLY"	41.6		
SHEET 3 SUB TOTALS			255.6	759.0	0.0	462.0
SHEET 3 TOTALS			255.6		1,221.0	0.0
SHEET 2 TOTALS			182.0		4,036.0	167.7
SHEET 1 TOTALS			218.4		4,888.0	141.3
PROJECT TOTAL			656.0		10,145	309