

LOCATION OF PROJECT: FAP 0559 IL RTE 58 (GOLF ROAD) AT NEW WILKE ROAD, COOK COUNTY  
 FUNDS: NEW WILKE RD - 75%FED(STP/STU) 25%LOCAL(ERP), GOLF RD - STP/STU 75%FED 25%LOCAL, URBAN  
 CONSTRUCTION TYPE CODE 0003

\* SPECIALTY ITEM

CODE NO	DESCRIPTION	UNIT	TOTAL QUANTITY
44003100	MEDIAN REMOVAL	SQFT	2078
44200982	CLASS B PATCHES, TYPE II, 11 INCH	SQYD	175
44200986	CLASS B PATCHES, TYPE III, 11 INCH	SQYD	265
44200988	CLASS B PATCHES, TYPE IV, 11 INCH	SQYD	445
50300300	PROTECTIVE COAT	SQYD	185
54213857	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	295
550A0330	STORM SEWERS, CLASS A, TYPE 2 10"	FOOT	16
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	648
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	1250
55100300	STORM SEWER REMOVAL 8"	FOOT	53
55100400	STORM SEWER REMOVAL 10"	FOOT	13
55100500	STORM SEWER REMOVAL 12"	FOOT	809
55100700	STORM SEWER REMOVAL 15"	FOOT	75
55101400	STORM SEWER REMOVAL 30"	FOOT	1417
* 58105000	DUCTILE IRON WATER MAIN 8"	FOOT	8
* 58103300	DUCTILE IRON WATER MAIN 12"	FOOT	140
* 56105200	WATER VALVES 12"	EACH	2
* 58108800	ADJUSTING WATER MAIN 12"	FOOT	40
* 58109100	TAPPING VALVES AND SLEEVES 12"	EACH	2
* 56201400	CORPORATION STOPS 1"	EACH	2
* 56300300	ADJUSTING WATER SERVICE LINES	FOOT	60

CODE NO	DESCRIPTION	UNIT	TOTAL QUANTITY
* 58400500	FIRE HYDRANTS TO BE REMOVED	EACH	4
* 58400920	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	1
80107800	PIPE UNDERDRAINS 4"	FOOT	6766
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	3
60201110	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	11
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	18
60207805	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	4
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	4
80221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	10
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1
60238825	INLETS, TYPE A, TYPE 11V FRAME AND GRATE	EACH	4
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	1
60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2
60250200	CATCH BASINS TO BE ADJUSTED	EACH	5
60255500	MANHOLES TO BE ADJUSTED	EACH	2
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	4
60260100	INLETS TO BE ADJUSTED	EACH	6
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1
60266100	VALVE VAULTS TO BE RECONSTRUCTED	EACH	1
60500040	REMOVING MANHOLES	EACH	8
60500050	REMOVING CATCH BASINS	EACH	28

FILE NAME: I:\PROJECTS\0559 IL RTE 58 (GOLF ROAD) AT NEW WILKE ROAD, COOK COUNTY\0559 IL RTE 58 (GOLF ROAD) AT NEW WILKE ROAD, COOK COUNTY.dwg

USER NAME: mwordener

DESIGNED - BLL  
 DRAWN - PMM

REVISED

PLOT SCALE = 20'

CHECKED - JGS  
 DATE - 8/06/12

REVISED

PLOT DATE = 8/31/2012

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

IL RTE 58 (GOLF ROAD) AND NEW WILKE ROAD IMPROVEMENTS  
 SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0559	00-00078-00-CH	COOK	116	4
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 83735	

SCALE: N.T.S. SHEET NO. 2 OF 5 SHEETS STA. TO STA.