

REMOVAL SCHEDULE													
LOCATION		44000100	44000157	44000163	44000200	44000300	44000500	44000600	X4401198	Z0042199	Z0007125	Z0022800	Z0075496
		PAVEMENT REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL 2"	HOT-MIX ASPHALT SURFACE REMOVAL - 3.5"	DRIVEWAY PAVEMENT REMOVAL	CURB REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	SIDEWALK REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	PORTLAND CEMENT CONCRETE PAVEMENT SURFACE REMOVAL	HANDRAIL REMOVAL	FENCE REMOVAL	CONCRETE RETAINING WALL REMOVAL
BEGIN STATION	END STATION	SQ YD	SQ YD	SQ YD	SQ FT	FOOT	FOOT	SQ FT	SQ YD	SQ YD	EACH	FOOT	FOOT
<b>ADAMS STREET</b>													
PERSIMMON TO MAPLE													
140+10.00	145+93.90	1525	0	0	1097	0	1222	10873	2717	0	0	0	0
<b>MAPLE TO ELM</b>													
145+93.90	150+13.90	1569	0	0	2367	0	892	10065	1022	0	0	0	0
<b>ELM TO OAK</b>													
150+13.90	154+41.40	1589	0	0	1825	47	864	7427	1246	0	0	0	0
<b>OAK TO STATE</b>													
154+41.40	158+74.80	1425	0	0	1645	0	948	12180	1369	0	0	0	0
<b>STATE TO WALNUT</b>													
158+74.80	165+30.00	2182	0	0	482	0	1300	12396	1993	0	0	0	0
<b>JEFFERSON AVENUE</b>													
PERSIMMON TO MAPLE													
240+25.00	245+60.80	1530	0	0	1432	0	1164	6579	2740	0	0	0	0
<b>MAPLE TO ELM</b>													
245+60.80	250+10.80	1156	0	0	325	0	890	4390	1835	0	0	0	0
<b>ELM TO OAK</b>													
250+10.80	255+55.00	1457	0	0	794	0	816	8098	2010	430	0	0	0
<b>PERSIMMON STREET</b>													
JEFFERSON TO ADAMS													
593+60.00	596+70.00	656	0	0	102	0	609	3456	0	0	0	0	0
<b>ADAMS TO WASHINGTON</b>													
598+25.00	599+74.71	250	0	0	0	0	282	2888	0	0	1	0	0
<b>MAPLE STREET</b>													
JEFFERSON TO ADAMS													
246+60.00	249+55.00	167	0	0	63	292	0	3331	0	0	0	0	0
<b>ADAMS TO WASHINGTON</b>													
698+10.00	701+54.14	443	0	0	25	601	0	4151	0	0	4	90	0
<b>OAK STREET</b>													
JEFFERSON TO ADAMS													
793+65.00	796+60.00	224	832	0	55	0	592	9029	0	0	0	0	0
<b>ADAMS TO WASHINGTON</b>													
796+15.00	799+90.53	819	0	0	139	304	0	127	0	0	0	0	0
<b>STATE STREET</b>													
ADAMS TO WASHINGTON													
898+45.00	901+00.45	494	949	0	399	0	5899	0	0	0	0	0	0
<b>WASHINGTON TO COMMERCIAL</b>													
903+15.00	907+05.86	1992	0	0	145	674	0	7161	0	0	0	0	0
<b>ELM STREET</b>													
746+15.00	747+08.00	439	0	97	245	0	410	2239	0	0	0	0	0
<b>WALNUT STREET</b>													
950+34.30	952+00.00	871	0	176	0	0	302	3868	0	0	0	0	0
<b>COMMERCIAL STREET</b>													
1711+50.00	1716+60.00	3116	0	0	0	0	559	2610	0	0	115	0	0
<b>TOTAL</b>		21904	1781	273	10441	2317	10850	116767	14932	430	1	119	90

REMOVAL SCHEDULE 2							
LOCATION		20100110	60500040	60500060	X0323569	XX008662	Z0036900
		TREE REMOVAL (6 TO 15 UNITS DIAMETER)	REMOVING MANHOLES	REMOVING INLETS	STEEL POST REMOVAL	REMOVE EXISTING LIGHT POLE	PARKING METERS TO BE REMOVED
BEGIN STATION	END STATION	UNIT	EACH	EACH	EACH	EACH	EACH
<b>*FROM ADAMS STREET</b>							
		14	6	17	0	18	26
<b>*FROM JEFFERSON AVENUE</b>							
		102	4	20	0	2	0
<b>PERSIMMON STREET</b>							
593+60.00	596+70.00	0	0	3	0	0	0
598+25.00	599+74.71	0	0	1	0	0	0
<b>MAPLE STREET</b>							
246+60.00	249+55.00	0	0	0	0	0	0
698+10.00	701+54.14	0	0	2	0	0	0
<b>OAK STREET</b>							
793+65.00	796+60.00	0	0	2	0	5	0
796+15.00	799+90.53	0	0	1	8	0	0
<b>STATE STREET</b>							
898+45.00	901+00.45	0	0	2	0	3	5
903+15.00	907+05.86	0	0	4	0	6	0
<b>ELM STREET</b>							
746+15.00	749+15.00	12	0	0	0	1	0
<b>WALNUT STREET</b>							
950+11.00	953+57.00	12	0	1	0	1	0
<b>COMMERCIAL STREET</b>							
1711+10.00	1716+70.00	18	0	3	5	4	0
<b>TOTAL</b>		158	10	56	13	40	31

• SEE REMOVAL SHEETS FOR SCHEDULE INFORMATION

REMOVAL SCHEDULE 3								
LOCATION		55100400	55100500	55100700	55100900	55101200	55101400	55101900
		STORM SEWER REMOVAL 10"	STORM SEWER REMOVAL 12"	STORM SEWER REMOVAL 15"	STORM SEWER REMOVAL 18"	STORM SEWER REMOVAL 24"	STORM SEWER REMOVAL 30"	STORM SEWER REMOVAL 48"
BEGIN STATION	END STATION	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH
<b>*FROM ADAMS STREET</b>								
		20	219	16	4	51	43	0
<b>*FROM JEFFERSON AVENUE</b>								
		30	283	0	0	0	0	0
<b>PERSIMMON STREET</b>								
593+60.00	596+70.00	0	12	0	0	0	0	0
598+25.00	599+74.71	0	9	0	0	0	0	0
<b>MAPLE STREET</b>								
246+60.00	249+55.00	0	0	0	0	0	0	0
698+10.00	701+54.14	0	0	0	0	0	0	0
<b>OAK STREET</b>								
793+65.00	796+60.00	0	0	0	0	0	0	0
796+15.00	799+90.53	0	18	0	0	0	0	0
<b>STATE STREET</b>								
898+45.00	901+00.45	0	47	0	0	0	0	0
903+15.00	907+05.86	0	72	0	0	0	0	0
<b>ELM STREET</b>								
746+15.00	749+15.00	0	0	0	0	0	0	0
<b>WALNUT STREET</b>								
950+11.00	953+57.00	0	45	0	0	0	0	0
<b>COMMERCIAL STREET</b>								
1711+10.00	1716+70.00	0	233	0	0	0	0	21
<b>TOTAL</b>		50	938	16	4	51	43	21

• SEE REMOVAL SHEETS FOR SCHEDULE INFORMATION