



NOTE 1:  
 CROSSWALK PAVEMENT MARKINGS SHALL BE PLACED IN THE CENTER OF THE CONCRETE BANDING ON EITHER SIDE OF THE BRICK PAVEMENT SIDEWALK ON RIGID BASE. PRIMER SHALL BE APPLIED AS INDICATED IN THE STANDARD SPECIFICATIONS.

- ① DOUBLE YELLOW THERMOPLASTIC PAVEMENT MARKING LINE - 4" SOLID, 4" GAP
- ② WHITE THERMOPLASTIC PAVEMENT MARKING LINE - 8" SOLID
- ③ WHITE THERMOPLASTIC PAVEMENT MARKING LINE - 12" (ON 45° ANGLE, 20' CTC)
- ④ WHITE THERMOPLASTIC PAVEMENT MARKING LINE - 8" (2' LONG, 6' GAP)
- ⑤ WHITE THERMOPLASTIC PAVEMENT MARKING LINE - 10' LONG, 30' GAP - 4"
- ⑥ WHITE PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - 10' LONG, 30' GAP - 4"
- ⑦ WHITE PREFORMED THERMOPLASTIC STOP BAR PAVEMENT MARKING LINE - 24" SOLID
- ⑧ WHITE PREFORMED THERMOPLASTIC PAVEMENT MARKING LINE - 8" SOLID
- ⑨ PREFORMED THERMOPLASTIC PAVEMENT MARKING, LETTERS (6' HEIGHT) AND SYMBOLS (FOR LEFT AND RIGHT TURN LANE ONE ARROW 20' FROM FRONT OF STORAGE AND ONE ARROW 20' AT BACK OF STORAGE)



FILE NAME *	USER NAME * dawa09070	DESIGNED - MCD	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>ADAMS STREET PAVEMENT MARKING PLANS</b>		F.A.U. RTE. 228	SECTION 12-00356-01-PV	COUNTY PEORIA	TOTAL SHEETS 519	SHEET NO. 88
al\pwise\work\do_not_delete\des73308\041\1155-sh1-pmk003.dgn		DRAWN - RLA	REVISED -		SCALE: 1"=20'	SHEET NO. OF SHEETS	STA. 150+50 TO STA. 156+50	CONTRACT NO. 89626		ILLINOIS FED. AID PROJECT TIG-509305B1	
		CHECKED - KNB	REVISED -								
		DATE - 7/18/12	REVISED -								