




REPAIR DESCRIPTIONS

REPAIR 3558 - REMOVE THE EXISTING CASTING AND LID OF MANHOLE ESAN-14 AND REPLACE IT WITH NEW, WATERPROOF-TYPE CASTING AND LID. CAREFULLY REMOVE ANY LOOSE BRICKS BELOW THE EXISTING CASTING AND LID AND REPLACE THEM WITH ADJUSTING RINGS IN ACCORDANCE WITH GPSD SPECIFICATIONS. ADDITIONALLY, REMOVE AND REPLACE BENCH AND TROUGH OF THE SAME.

REPAIR 3576 - REMOVE AND REPLACE WITH NEW THE EXISTING BENCH AND TROUGH OF MANHOLE E-SAN12.

SANITARY SCHEDULE

LOCATION	X8026802	X8028000
	MANHOLES TO BE ADJUSTED WITH FRAME AND GRATE (SPECIAL)	MANHOLES TO BE RECONSTRUCTED (SPECIAL)
	EACH	EACH
REPAIR 3558	1	1
REPAIR 3576	0	1
TOTAL	1	2



FILE NAME =
 USER NAME = kovan01511
 DESIGNED - PWM
 DRAWN - RLA
 CHECKED - CAL
 PLOT DATE = 07/23/2012

DESIGNED - PWM
 DRAWN - RLA
 CHECKED - CAL
 DATE - 7/18/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**ADAMS STREET AND JEFFERSON AVENUE
 SANITARY SEWER PLANS**

SCALE: 1"=20' SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.
 12-00356-01-PV PEORIA 519 213
 CONTRACT NO.89626
 ILLINOIS FED. AID PROJECT TIG-50931(58)

