


	STATION	OFFSET	
1.	153+68.41	19.23'	LT
2.	153+68.41	26.41'	LT
3.	153+73.41	26.41'	LT
4.	153+73.41	31.41'	LT
5.	153+97.18	31.41'	LT
6.	153+97.18	19.31'	LT
7.	154+15.33	48.72'	LT
8.	154+15.33	64.47'	LT
9.	154+20.22	64.47'	LT
10.	154+20.23	48.72'	LT
11.	153+68.39	26.41'	RT
12.	153+68.39	17.58'	RT
13.	153+75.65	17.58'	RT
14.	153+75.65	14.02'	RT
15.	153+96.97	14.67'	RT
16.	153+96.97	26.41'	RT
17.	152+38.28	28.91'	LT
18.	152+72.77	28.91'	LT
19.	153+07.25	28.91'	LT
20.	153+41.77	28.91'	LT
21.	153+97.03	36.00'	LT
22.	154+07.04	39.30'	LT
23.	154+10.41	48.84'	LT
24.	152+37.36	26.41'	RT
25.	152+43.54	27.16'	RT
26.	152+43.54	39.85'	RT
27.	152+72.75	23.91'	RT
28.	153+07.25	23.91'	RT
29.	153+41.75	23.91'	RT
30.	154+03.25	27.33'	RT
31.	154+18.00	40.33'	RT
32.	153+82.79	20.22'	RT
33.	153+82.79	25.22'	LT
34.	153+98.23	40.64'	RT

CONTROL POINTS PROVIDED FOR ALL STANDARD PLANTER BOXES AND 3' AND 4' INTERSECTION BRICK PAVER INLAY FOR CONSTRUCTION, SEE DETAILS 4, 23, AND 24 RESPECTIVELY FOR FURTHER INFORMATION.



FILE NAME *	USER NAME * manak01390	DESIGNED - STH	REVISED -
o:\pwise\work\do_not_delete\dms73427\04	01\0155-shc-1ndscp007.dgn	DRAWN - STH	REVISED -
	PLOT SCALE * 20.0000' / 1" =	CHECKED - BAB	REVISED -
	PLOT DATE * 07/23/2012	DATE - 7/18/12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**ADAMS STREET
STREETSCAPE PLAN**

SCALE: 1"=10' SHEET NO. OF SHEETS STA. 152+20.00 TO STA. 154+45.00

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	12-00356-01-PV	PEORIA	519	249
CONTRACT NO. 89626				
ILLINOIS FED. AID PROJECT TIG-50931581				

Farnsworth GROUP
7707 N. KNOXVILLE AVE. SUITE 100
PEORIA, ILLINOIS 61614
(309) 696-0608 / (309) 696-0620 Fax
www.fw.com