



PRINT DATE: 9/28/2018 11:31:37 AM Z:\5052 Poplar Street Complex\DCN\Bridg\Final\Plotsheets\Roadway G\006\_Rawy\_G\_Deck\_Plan2 (05-C8).dgn



PLAN (SPANS G5 & G6)



PLAN (SPANS G7 & G8)

SPAN	PARTIAL DEPTH REPAIRS (Sq Yd)	FULL DEPTH REPAIRS (Sq Yd)	TOTAL (Sq Yd)
G5	17	1	18
G6	19	1	20
G7	60	4	64
G8	24	2	26

Deck Slab Repair

Note:  
 Deck sounding was performed in April 2017, with quantities increased to account for anticipated growth.  
 The Resident Engineer will determine final patch locations and quantities in the field before bridge deck patching operations begin.  
 For details of full depth or partial depth patching, see Sheet 30 of 43.

**BILL OF MATERIAL**

ITEM	UNIT	QUANTITY
Deck Slab Repair (Full Depth, Type I)	Sq Yd	8
Deck Slab Repair (Partial)	Sq Yd	120

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
 Wss, Janney, Elstner Associates, Inc.  
 330 Pfingsten Road  
 Northbrook, Illinois 60062  
 847.272.7400 tel | 847.291.9595 fax

USER NAME = acb	DESIGNED - SMG	REVISED -
	CHECKED - ARB/RW	REVISED -
PLOT SCALE = 0.1667' / 1"	DRAWN - ACB	REVISED -
PLOT DATE = 9/28/2018	DATE - 09/28/2018	REVISED -


**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**DECK PATCHING REPAIRS (SPANS G5 THRU G8)  
 S.N. 082-0254**


SHEET NO. 6 OF 43 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	201
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				

PRINT DATE: 9/28/2018 11:31:37 AM Z:\5052 Poplar Street Complex\DCN\Bridg\Final\Plotsheets\Roadway G\007\_Rawy\_G\_Deck\_Plan3 (G9-G13).dgn



**PLAN (SPANS G9, G10 & G11)**



**PLAN (SPANS G12 & G13)**

SPAN	PARTIAL DEPTH REPAIRS (Sq Yd)	FULL DEPTH REPAIRS (Sq Yd)	TOTAL (Sq Yd)
G9	20	2	22
G10	52	3	55
G11	29	2	31
G12	4	1	5
G13	53	3	56

Deck Slab Repair

Note:  
 Deck sounding was performed in April 2017, with quantities increased to account for anticipated growth.  
 The Resident Engineer will determine final patch locations and quantities in the field before bridge deck patching operations begin.  
 For details of full depth or partial depth patching, see Sheet 30 of 43.

**BILL OF MATERIAL**

ITEM	UNIT	QUANTITY
Deck Slab Repair (Full Depth, Type I)	Sq Yd	11
Deck Slab Repair (Partial)	Sq Yd	158

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
 Wss, Janney, Elstner Associates, Inc.  
 330 Pingsten Road  
 Northbrook, Illinois 60062  
 847.272.7400 tel | 847.291.9595 fax

USER NAME = acb	DESIGNED - SMG	REVISED -
PLOT SCALE = 0.1667' / 1"	CHECKED - ARB/RW	REVISED -
PLOT DATE = 9/28/2018	DRAWN - ACB	REVISED -
	DATE - 09/28/2018	REVISED -




**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**DECK PATCHING REPAIRS (SPANS G9 THRU G13)**  
**S.N. 082-0254**

SHEET NO. 7 OF 43 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	202
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				

PRINT DATE: 9/28/2018 11:31:38 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Roadway\_G\008\_Rawy\_G\_Exp\_Joint\_Removal.dgn



**CONCRETE REMOVAL**

Location	Dimension "A"	Dimension "B"	Dimension "C"	Dimension "D"	Concrete Removal (Cu Yd)
Pier G1	56'-11 1/4"	53'-9 1/4"	2 1/2"	3'-0"	13.8
Pier G5	40'-8 1/8"	37'-6 1/8"	4 1/4"	5'-0"	14.1
Pier G9	36'-0"	31'-10"	2 1/2"	3'-0"	9.1
Pier G12	37'-11 3/4"	34'-9 3/4"	3"	3'-0"	11.0

Notes:  
See Sheet 9 of 43 for additional removal details at Pier G12.

**BILL OF MATERIAL**

ITEM	UNIT	QUANTITY
Concrete Removal	Cu. Yd.	48.0

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
 Wss, Janney, Elstner Associates, Inc.  
 330 Pfingsten Road  
 Northbrook, Illinois 60062  
 847.272.7400 tel | 847.291.9595 fax  
 www.wje.com

USER NAME = acb	DESIGNED - SMG	REVISED -
	CHECKED - RW	REVISED -
PLOT SCALE = 0:2 '1" = 1"	DRAWN - ACB	REVISED -
PLOT DATE = 9/28/2018	DATE - 09/28/2018	REVISED -


**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**EXPANSION JOINT REMOVAL DETAILS**  
**S.N. 082-0254**


SHEET NO. 8 OF 43 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	203
			CONTRACT NO. 76945	
ILLINOIS FED. AID PROJECT				


PRINT DATE: 9/28/2018 11:31:39 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Roadway\_G\009\_Rawy\_G\_Exp\_Joint\_RemovalDetails.dgn



**PIER G12 RETURN WALL PLAN VIEW**



**VIEW A-A**



**VIEW B-B**

Notes:  
See Sheet 8 of 43 for additional removal details at Pier G12.

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
Wiss, Janney, Elstner Associates, Inc.  
330 Pingsten Road  
Northbrook, Illinois 60062  
847.272.7400 tel | 847.291.9595 fax  
www.wje.com

USER NAME = acb	DESIGNED - SMG	REVISED -
CHECKED - RW	REVISOR -	REVISOR -
PLOT SCALE = 0.1667' / 1" =	DRAWN - ACB	REVISOR -
PLOT DATE = 9/28/2018	DATE - 09/28/2018	REVISOR -


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EXPANSION JOINT REMOVAL DETAILS (PIER G12)  
S.N. 082-0254**


SHEET NO. 9 OF 43 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	204
<b>CONTRACT NO. 76945</b>				
ILLINOIS FED. AID PROJECT				


PRINT DATE: 9/28/2018 11:31:39 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Roadway\_G\010\_Rdwy\_G\_Exp\_Joint\_Removal\Abutment\_G14.dgn



**PLAN SHOWING REMOVAL**



**SECTION A-A**



**VIEW B-B  
(Showing Reinforcement)**

**BILL OF MATERIAL**

ITEM	UNIT	QUANTITY
Concrete Removal	Cu. Yd.	10.0

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
 Wss, Janney, Elstner Associates, Inc.  
 330 Pfingsten Road  
 Northbrook, Illinois 60062  
 847.272.7400 tel | 847.291.9595 fax  
 www.wje.com

USER NAME = acb	DESIGNED - SMG	REVISED -
	CHECKED - RW	REVISED -
PLOT SCALE = 0.1667' / 1"	DRAWN - ACB	REVISED -
PLOT DATE = 9/28/2018	DATE - 09/28/2018	REVISED -


**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**EXPANSION JOINT REMOVAL DETAILS  
 S.N. 082-0254**


SHEET NO. 10 OF 43 SHEETS

F.A.I. RE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	205
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				


PRINT DATE: 9/28/2018 11:31:40 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Roadway\_G01L\_Rdwy\_G\_Pier\_G1\_Exp\_Joint\_Details.dgn




PIER G1 PLAN SHOWING REPLACEMENT



SECTION A-A




VIEW B-B  
(Showing Reinforcement)




SECTION THRU PARAPET


\* Adjust to match existing dimensions



BAR x(E)



BAR d(E)



BAR d1(E)

BILL OF MATERIAL

Bar	No.	Size	Length	Shape	
a(E)	14	#5	56'-6"	—	
a1(E)	14	#5	28'-0"	—	
a2(E)	14	#5	28'-4"	—	
d(E)	16	#4	5'-4"	L	
d1(E)	16	#5	3'-11"	⌋	
x(E)	116	#5	3'-3"	—	
Reinforcement Bars, Epoxy Coated				Lbs.	2160
Concrete Superstructure				Cu. Yds.	13.8

WJE ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
Wiss, Janney, Elstner Associates, Inc.  
330 Pingsten Road  
Northbrook, Illinois 60062  
847.272.7400 tel | 847.291.9595 fax

USER NAME = acb  
DESIGNED - SMG  
CHECKED - RW  
DRAWN - ACB  
DATE - 09/28/2018  
REVISOR -  
REVISION -  
REVISION -  
REVISION -

DESIGNED - SMG  
CHECKED - RW  
DRAWN - ACB  
DATE - 09/28/2018  
REVISOR -  
REVISION -  
REVISION -  
REVISION -


STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

EXPANSION JOINT REPLACEMENT DETAILS (PIER G1)  
S.N. 082-0254


SHEET NO. 11 OF 43 SHEETS

F.A.I. RE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HYB-2R-(2,1)-1-2	ST. CLAIR	238	206
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				


PRINT DATE: 9/28/2018 11:31:41 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Roadway\_G\02\_Rdwy\_G\_Pier\_G5\_Exp\_Joint\_Details.dgn





PIER G5 PLAN SHOWING REPLACEMENT



SECTION A-A



VIEW B-B  
(Showing Reinforcement)



SECTION THRU PARAPET

\* Adjust to match existing dimensions

BILL OF MATERIAL

Bar	No.	Size	Length	Shape	
a3(E)	44	#5	40'-4"	—	
d(E)	24	#4	5'-4"	L	
d1(E)	24	#5	3'-11"	L	
x1(E)	82	#4	6'-7"	U	
Reinforcement Bars, Epoxy Coated				Lbs.	2400
Concrete Superstructure				Cu. Yds.	14.1

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
 Wess, Janney, Elstner Associates, Inc.  
 330 Pingston Road  
 Northbrook, Illinois 60062  
 847.272.7400 tel | 847.291.9595 fax

USER NAME = acb	DESIGNED - SMG	REVISED -
PLOT SCALE = 0.1667' / 1"	CHECKED - RW	REVISED -
PLOT DATE = 9/28/2018	DRAWN - ACB	REVISED -
	DATE - 09/28/2018	REVISED -


STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

EXPANSION JOINT REPLACEMENT DETAILS (PIER G5)  
S.N. 082-0254


SHEET NO. 12 OF 43 SHEETS

F.A.I. RT.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HYB-2R-(2,1)-1-2	ST. CLAIR	238	207
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				


PRINT DATE: 9/28/2018 11:31:42 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Roadway\_G\013\_Rdwy\_G\_Pier\_G9\_Exp\_Joint\_Details.dgn




PIER G9 PLAN SHOWING REPLACEMENT




SECTION A-A




VIEW B-B  
(Showing Reinforcement)




SECTION THRU PARAPET  
\* Adjust to match existing dimensions



BAR x(E)



BAR d(E)



BAR d1(E)

BILL OF MATERIAL

Bar	No.	Size	Length	Shape	
a4(E)	28	#5	35'-8"	—	
d(E)	16	#4	5'-4"	L	
d1(E)	16	#5	3'-11"	└	
x(E)	74	#5	3'-3"	—	
Reinforcement Bars, Epoxy Coated				Lbs.	1380
Concrete Superstructure				Cu. Yds.	9.1

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
 Wss, Janney, Elstner Associates, Inc.  
 330 Pingsten Road  
 Northbrook, Illinois 60062  
 847.272.7400 tel | 847.291.9595 fax

USER NAME = acb	DESIGNED - SMG	REVISED -
CHECKED - RW	DRAWN - ACB	REVISED -
PLOT SCALE = 0.1667' / 1"	DATE - 09/28/2018	REVISED -
PLOT DATE = 9/28/2018		






STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

EXPANSION JOINT REPLACEMENT DETAILS (PIER G9)  
S.N. 082-0254

SHEET NO. 13 OF 43 SHEETS

F.A.I. RE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HYB-2R-(2,1)-1-2	ST. CLAIR	238	208
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				

PRINT DATE: 9/28/2018 11:31:42 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Roadway\_G\04\_Rdwy\_G\_Pier\_G12\_Exp\_Joint\_Details.dgn



**BILL OF MATERIAL**

Bar	No.	Size	Length	Shape
a5(E)	28	#5	37'-7"	—
d(E)	12	#4	5'-4"	L
d1(E)	12	#5	3'-11"	Λ
d2(E)	4	#5	9'-8"	Λ
e(E)	10	#5	2'-10"	—
x(E)	76	#5	3'-3"	—
Reinforcement Bars, Epoxy Coated			Lbs.	1550
Concrete Superstructure			Cu. Yds.	11.0
Bar Splicer			Each	10

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
 Wss, Janney, Elstner Associates, Inc.  
 330 Pingsten Road  
 Northbrook, Illinois 60062  
 847.272.7400 tel | 847.291.9595 fax

USER NAME = acb	DESIGNED - SMG	REVISED -
CHECKED - RW	REVISIONS -	
PLOT SCALE = 0.1667' / 1"	DRAWN - ACB	REVISED -
PLOT DATE = 9/28/2018	DATE - 09/28/2018	REVISED -


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EXPANSION JOINT REPLACEMENT DETAILS (PIER G12)  
S.N. 082-0254**


SHEET NO. 14 OF 43 SHEETS

F.A.I. RE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	209
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				


PRINT DATE: 9/28/2018 11:31:43 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Roadway G\015\_Rdwy\_G\_Exp\_Joint\_Replacement\_Details.dgn




**PIER G12 RETURN WALL PLAN VIEW**




**VIEW A-A**




**SECTION B-B**



**BAR d2(E)**



**BAR d(E)**



**BAR d1(E)**

See Sheet 21 of 43 for Barrier Wall Replacement at Ramp S Gore

Notes:  
See Sheet 14 of 43 for additional details and quantities.

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
Wiss, Janney, Elstner Associates, Inc.  
330 Pingsten Road  
Northbrook, Illinois 60062  
847.272.7400 tel | 847.291.9595 fax

USER NAME = acb	DESIGNED - SMG	REVISED -
PLOT SCALE = 0.1667' / 1"	CHECKED - RW	REVISED -
PLOT DATE = 9/28/2018	DRAWN - ACB	REVISED -
	DATE - 09/28/2018	REVISED -


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EXPANSION JOINT REPLACEMENT DETAILS (PIER G12)  
S.N. 082-0254**


SHEET NO. 15 OF 43 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	210
CONTRACT NO. 76945			ILLINOIS FED. AID PROJECT	


PRINT DATE: 9/28/2018 11:31:44 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Roadway\_G016\_Rdwy\_G\_Pier\_G14\_Exp\_Joint\_Details.dgn




**ABUTMENT G14 PLAN SHOWING REPLACEMENT**



**SECTION A-A**




**VIEW B-B  
(Showing Reinforcement)**




**SECTION THRU PARAPET**


\* Adjust to match existing dimensions



**BAR x(E)**



**BAR d(E)**



**BAR d1(E)**

**BILL OF MATERIAL**

Bar	No.	Size	Length	Shape	
a6(E)	18	#5	54'-5"	—	
d(E)	8	#4	5'-4"	L	
d1(E)	8	#5	3'-11"	⌋	
x(E)	56	#5	3'-3"	—	
Reinforcement Bars, Epoxy Coated				Lbs.	1270
Concrete Superstructure				Cu. Yds.	10.0
Relocating Name Plates				Each	1

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
 Wss, Janney, Elstner Associates, Inc.  
 330 Pingsten Road  
 Northbrook, Illinois 60062  
 847.272.7400 tel | 847.291.9595 fax

USER NAME = acb	DESIGNED - SMG	REVISED -
PLOT SCALE = 0.1667' / 1"	CHECKED - RW	REVISED -
PLOT DATE = 9/28/2018	DRAWN - ACB	REVISED -
	DATE - 09/28/2018	REVISED -


**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**EXPANSION JOINT REPLACEMENT DETAILS (ABUTMENT G14)  
 S.N. 082-0254**


SHEET NO. 16 OF 43 SHEETS

F.A.I. RT.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	211
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				

PRINT DATE: 9/28/2018 11:31:45 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Roadway\_G\017\_Rdwy\_G\_Prefomed\_Joint\_Strip\_Seal.dgn




**PLAN AT PARAPET**




**SECTION B-B**

**Notes:**  
 The strip seal shall be made continuous and shall have a minimum thickness of 1/4". The configuration of the strip seal shall match the configuration of the locking edge rails. Open or "webbed" strip seal gland configurations are not permitted. The gland shall be sized for a maximum rated movement of 4 inches.  
 The locking edge rails depicted are configured for typical applications and are conceptual only. The actual configuration of the locking edge rails and matching strip seal may vary from manufacturer to manufacturer provided they fit the application and meet the minimum anchorage shown. Flanged edge rails, however, will not be allowed. Locking edge rails may exceed the 4 1/2" maximum depth provided the anchorage system is revised according to the manufacturer's recommendation.  
 The manufacturer's recommended installation methods shall be followed.  
 All steel components shall be galvanized after fabrication according to Article 520.03 of the Standard Specifications.  
 The Maximum space between locking edge rail segments shall be 3/16" and sealed with a suitable sealant; however, any rail joint within 10' measured perpendicular to the face of the curb or parapet shall be welded as shown in the locking edge rail splice detail.




**ELEVATION AT PARAPET**

(Skews > 30° shown. Skews ≤ 30° similar except as shown in plan view.)




**DETAIL A**



**TRIMETRIC VIEW**  
(Showing embedded plates only)


**EXPANSION OPENINGS**

Pier	"A"	"B"
G1	1 5/8"	2 1/2"
G9	1 1/2"	2 3/8"
G12	1 1/2"	2 3/8"
G14	1 1/2"	2 3/8"




**SHOWING ROLLED RAIL JOINT**


\* 5/8" Ø x 6" studs @ 6" cts. (alternate angled/bent studs with horizontal studs)  
 3/8" Ø threaded rods in 7/16" Ø holes at ±4'-0" cts. for holding the proper joint opening based on the temperature during the deck pour. Place to miss studs. All rods shall be burned, or sawed off flush with the plates after concrete is set.




**SHOWING WELDED RAIL JOINT**



**ROLLED (EXTRUDED) RAIL**



**WELDED RAIL**



**LOCKING EDGE RAIL SPLICE**

The inside of the locking edge rail groove shall be free of weld residue. Rolled rail shown, welded rail similar.

**LOCKING EDGE RAILS**

\*\* Back gouge not required if complete joint penetration is verified by mock-up.

**SECTION A-A**

\* Granular or solid flux filled headed studs conforming to Article 1006.32 of the Std. Specs., automatically end welded.

**BILL OF MATERIAL**

Item	Unit	Total
Prefomed Joint Strip Seal	Foot	186

EJ-SS

8-11-17

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
 Wss, Janney, Elstner Associates, Inc.  
 330 Pingsten Road  
 Northbrook, Illinois 60062  
 847.272.7400 tel | 847.291.9595 fax

USER NAME = acb	DESIGNED - SMG	REVISED -
PLOT SCALE = 0:2.0000 '1' / in.	CHECKED - RW	REVISED -
PLOT DATE = 9/28/2018	DRAWN - ACB	REVISED -
	DATE - 09/28/2018	REVISED -


**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**PREFORMED JOINT STRIP SEAL  
 S.N. 082-0254**


SHEET NO. 17 OF 43 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HYB-2R-(2,1)-1-2	ST. CLAIR	238	212
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				


PRINT DATE: 9/28/2018 11:31:46 AM Z:\5052 Poplar Street Complex\DCN\Bridg\Final\Plotsheets\Roadway\_G\018\_Rdwy\_G\_Pier\_G5\_Finger\_Joint.dgn



**PLAN OF FINGER PLATE EXPANSION JOINT AT PIER G5**



**SECTION C-C**  
 See Sheet 17 of 43 for typical sliding plate detail.  
 See Sheet 12 of 43 for parapet dimensions.



**SECTION A-A**  
 Span G4 shown. Span G5 similar.

**NOTES:**  
 See Sheet 19 of 43 for Section B-B.  
 See Sheet 20 of 43 for details of stools.

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
 Wss, Janney, Elstner Associates, Inc.  
 330 Pingsten Road  
 Northbrook, Illinois 60062  
 847.272.7400 tel | 847.291.9595 fax

USER NAME = acb	DESIGNED - SMG	REVISED -
PLOT SCALE = 0.1667' / 1"	CHECKED - RW	REVISED -
PLOT DATE = 9/28/2018	DRAWN - ACB	REVISED -
	DATE - 09/28/2018	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**


**FINGER PLATE REPLACEMENT DETAILS (PIER G5)**  
**S.N. 082-0254**

SHEET NO. 18 OF 43 SHEETS


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	213
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				



PRINT DATE: 9/28/2018 11:31:47 AM Z:\5052 Poplar Street Complex\DCN\Bridg\Final\Plotsheets\Roadway G\020\_Rawy\_G\_Pier\_G5\_Finger\_Joint\_Details2.dgn



**STOOL DETAILS AT FINGER PLATE JOINT**




**SECTION THRU STOOL**


Cut stool from WT13.5x42, typ. See table below for stool heights

**STOOL HEIGHTS**

SPAN	STOOL NUMBER	HEIGHT
G4	1-4 & 15-18	9 3/4"
G4	10-16	9 1/2"
G5	1-18	10 1/4"



**FLAME CUTTING DIAGRAM**



**JOINT OPENING AND GEOMETRY DETAIL**



**NOTES:**

- "CVN" denotes Charpy V Notch impact energy requirements, zone 2.
- Finger plate expansion joints shall be assembled in their final relative position with the ends in place for shop inspection and acceptance.
- Finger plates and sliding plates shall conform to the requirements of AASHTO M270, Grade 50.
- The cost of all material for finger plates and trough support brackets shall be included in the cost of Finger Plate Expansion Joint, 4".
- All steel components of the expansion joint including hardware associated with the trough system and sliding plates shall be galvanized after fabrication according to Section 520.03 of the Standard Specifications.


**BILL OF MATERIAL**

ITEM	UNIT	QUANTITY
Finger Plate Expansion Joint, 4"	Foot	38
Fabric Reinforced Elastomeric Trough	Foot	41


PRINT DATE: 9/28/2018 11:31:48 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Roadway G\02\_Rdwy\_G\_Barrier Wall Replacement at Ramp S Gore.dgn




\*Drill and epoxy #5 d3(E), d4(E), and d5(E) bars according to epoxy manufacturer's recommendations. Maximum depth of hole shall not exceed 6". Anchoring epoxy shall be approved by engineer.



**SECTION A-A**




**SECTION B-B**




**SECTION C-C**

**BILL OF MATERIAL**


Bar	No.	Size	Length	Shape
d3(E)	10	#5	6'-0"	┘
d4(E)	6	#5	5'-10"	┘
d5(E)	27	#5	8'-2"	┘
e1(E)	10	#5	21'-10"	
e2(E)	10	#5	18'-0"	
e3(E)	5	#4	8'-3"	□
Reinforcement Bars, Epoxy Coated			Lbs.	770
Concrete Superstructure			Cu. Yds.	8.3




**BAR d3(E)**



**BAR d4(E)**







**BAR d5(E)**



**BAR e3(E)**

Note:  
Trim or bend existing return wall reinforcement as necessary to maintain 1 1/2" cover.

PRINT DATE: 9/28/2018 11:31:49 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Piers\022\_Pier\_G1.dgn



Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)

Epoxy Crack Injection

**Note:**  
Remove existing hoops that intersect repair areas. Replace each removed hoop with a column tensioned strand after the repair area has reached design strength. See sheet 31 of 43 for related details and notes.

Repairs may be visible in multiple views on circular elements, however, the repair is only shown in the most descriptive view.

**PIER G1**  
**BILL OF MATERIAL**

ITEM	UNIT	QUANTITY
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)	Sq Ft	300
Epoxy Crack Injection	Foot	40
Galvanic Anode	Each	195
Column Tensioned Strands	Each	4

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
Wiss, Janney, Elstner Associates, Inc.  
330 Pingsten Road  
Northbrook, Illinois 60062  
847.272.7400 tel | 847.291.9595 fax

USER NAME = acb	DESIGNED - ARB	REVISED -
PLOT SCALE = 0:2.0000 '1' / in.	CHECKED - RW	REVISED -
PLOT DATE = 9/28/2018	DRAWN - ACB	REVISED -
	DATE - 09/28/2018	REVISED -


**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**PIER G1**  
**S.N. 082-0254**


SHEET NO. 22 OF 43 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	217
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				


PRINT DATE: 9/28/2018 11:31:50 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Piers\023\_Pier\_G5.dgn




**ELEVATION**  
(Looking Upstation)



**COLUMN A** (End View)    **COLUMN A** (Interior View)    **COLUMN B** (Interior View)    **COLUMN B** (End View)



**ELEVATION**  
(Looking Downstation)



**PLAN VIEW**

Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)  
 Epoxy Crack Injection

**Note:**  
 Remove existing hoops that intersect repair areas. Replace each removed hoop with a column tensioned strand after the repair area has reached design strength. See sheet 31 of 43 for related details and notes.

Repairs may be visible in multiple views on circular elements, however, the repair is only shown in the most descriptive view.

**PIER G5  
BILL OF MATERIAL**

ITEM	UNIT	QUANTITY
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)	Sq Ft	131
Epoxy Crack Injection	Foot	5
Column Tensioned Strands	Each	8
Galvanic Anode	Each	114

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
 Wss, Janney, Elstner Associates, Inc.  
 330 Pingsten Road  
 Northbrook, Illinois 60062  
 847.272.7400 tel | 847.291.9595 fax

USER NAME = acb	DESIGNED - ARB	REVISED -
	CHECKED - RW	REVISED -
PLOT SCALE = 0:2.0000 '1' / in.	DRAWN - ACB	REVISED -
PLOT DATE = 9/28/2018	DATE - 09/28/2018	REVISED -





**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**PIER G5  
S.N. 082-0254**

SHEET NO. 23 OF 43 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	218
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				

PRINT DATE: 9/28/2018 11:31:50 AM Z:\5052 Poplar Street Complex\DCN\Bridg\Final\Plotsheets\Piers\024\_Pier\_G9.dgn



Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)

Epoxy Crack Injection

**Note:**  
 Remove existing hoops that intersect repair areas. Replace each removed hoop with a column tensioned strand after the repair area has reached design strength. See sheet 31 of 43 for related details and notes.

Repairs may be visible in multiple views on circular elements, however, the repair is only shown in the most descriptive view.

**PIER G9**  
**BILL OF MATERIAL**

ITEM	UNIT	QUANTITY
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)	Sq Ft	100
Epoxy Crack Injection	Foot	30
Column Tensioned Strands	Each	8
Galvanic Anode	Each	97

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
 Wess, Janney, Elstner Associates, Inc.  
 330 Pingsten Road  
 Northbrook, Illinois 60062  
 847.272.7400 tel | 847.291.9595 fax  
 www.wje.com

USER NAME = acb	DESIGNED - ARB	REVISED -
	CHECKED - RW	REVISED -
PLOT SCALE = 0:2.0000 '1' = 1"	DRAWN - ACB	REVISED -
PLOT DATE = 9/28/2018	DATE - 09/28/2018	REVISED -


**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**PIER G9**  
**S.N. 082-0254**



SHEET NO. 24 OF 43 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	219
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				


PRINT DATE: 9/28/2018 11:31:51 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Piers\025\_Pier\_G12.dgn




**ELEVATION**  
(Looking Upstation)




**ELEVATION**  
(Looking Downstation)



**TOP VIEW OF TIE BEAM**



**UNDERSIDE OF TIE BEAM**



**TOP OF CRASHWALL**

**Note:**  
Remove existing hoops that intersect repair areas. Replace each removed hoop with a column tensioned strand after the repair area has reached design strength. See sheet 31 of 43 for related details and notes.

Repairs may be visible in multiple views on circular elements, however, the repair is only shown in the most descriptive view.

Tie Beams to be removed prior to any patching.

Existing Tie Beam reinforcement will be preserved. See project specification for details.

At the contractor's option, Type 2 bar splicers capable of resisting earthquake induced forces can be used with new reinforcement as opposed to preserving existing longitudinal beam reinforcement. At most, 50% of the longitudinal steel can be spliced in one cross-section. The distance between cross-sections with splices shall be 7'-7". Product data must be submitted to Engineer. Cost of splicers and steel to be included with concrete removal.

**PIER G12  
BILL OF MATERIAL**

ITEM	UNIT	QUANTITY
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)	Sq Ft	240
Column Tensioned Strands	Each	4
Epoxy Crack Injection	Foot	135
Galvanic Anode	Each	314

Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)

Epoxy Crack Injection

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
 Wss, Janney, Elstner Associates, Inc.  
 330 Plingsten Road  
 Northbrook, Illinois 60062  
 847.272.7400 tel | 847.291.9595 fax

USER NAME = acb	DESIGNED - ARB	REVISED -
PLOT SCALE = 0:2.0000 '1' / in.	CHECKED - RW	REVISED -
PLOT DATE = 9/28/2018	DRAWN - ACB	REVISED -
	DATE - 09/28/2018	REVISED -








**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**PIER G12  
S.N. 082-0254**

SHEET NO. 25 OF 43 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HV-B-2R-(2,1)-1-2	ST. CLAIR	238	220
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				

PRINT DATE: 9/28/2018 11:31:52 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Piers\026\_Pier\_G14.dgn



- Epoxy Crack Injection
- Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)

**PIER G14**  
**BILL OF MATERIAL**

ITEM	UNIT	QUANTITY
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)	Sq Ft	20
Epoxy Crack Injection	Ft	75
Galvanic Anode	Each	37

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
Wiss, Janney, Elstner Associates, Inc.  
330 Pingsten Road  
Northbrook, Illinois 60062  
847.272.7400 tel | 847.291.9595 fax

USER NAME = acb	DESIGNED - ARB	REVISED -
	CHECKED - RW	REVISED -
PLOT SCALE = 0:2.0000 '1' / in.	DRAWN - ACB	REVISED -
PLOT DATE = 9/28/2018	DATE - 09/28/2018	REVISED -


**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**ABUTMENT G14**  
**S.N. 082-0254**


SHEET NO. 26 OF 43 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	221
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				


PRINT DATE: 9/28/2018 11:31:52 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Roadway G\027\_Rawy\_G\_Abut G4-Wing Removal.dgn




EAST WINGWALL  
REMOVAL PLAN



WEST WINGWALL  
REMOVAL PLAN



EAST WINGWALL  
REMOVAL SECTION



WEST WINGWALL  
REMOVAL SECTION

LEGEND

Concrete Removal

Notes:







Existing wingwall reinforcement to remain. Trim and field coat existing bars with epoxy as needed to ensure 1-1/2" clear cover in the rebuilt wing wall.

Construction of wing wall modifications will require excavation and removal/replacement of roadway and curb. See Sheet 15 of 235 for additional information associated with this work.

USER NAME = acb	DESIGNED - ARB	REVISED -
	CHECKED - RW	REVISED -
PLOT SCALE = 0.1667' / 1"	DRAWN - ACB	REVISED -
PLOT DATE = 9/28/2018	DATE - 09/28/2018	REVISED -

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	222
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				

PRINT DATE: 9/28/2018 11:31:53 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Roadway\_G\028\_Rawy\_G\_Abut\_G14-Wingwalls.dgn



**BILL OF MATERIAL**

Bar	No.	Size	Length	Shape
h(E)	10	#5	7'-5"	L
h1(E)	4	#5	5'-8"	—
v(E)	6	#6	5'-0"	—
v1(E)	7	#6	4'-1"	—
v2(E)	6	#6	5'-2"	—
v3(E)	7	#6	4'-2"	—
Concrete Removal			Cu. Yd.	1.6
Concrete Superstructure			Cu. Yd.	3.0
Reinforcement Bars, Epoxy Coated			Pound	280

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
 Wss, Janney, Elstner Associates, Inc.  
 330 Pingsten Road  
 Northbrook, Illinois 60062  
 847.272.7400 tel | 847.291.9595 fax


USER NAME = acb	DESIGNED - ARB	REVISED -
PLOT SCALE = 0.1667' / 1"	CHECKED - RW	REVISED -
PLOT DATE = 9/28/2018	DRAWN - ACB	REVISED -
	DATE - 09/28/2018	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**WINGWALL MODIFICATION**  
**S.N. 082-0254**  
 SHEET NO. 28 OF 43 SHEETS


F.A.I. RT.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	223
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				

PRINT DATE: 10/11/2018 9:36:03 AM Z:\5052 Poplar Street Complex\DCN\Bridg\Final\Plotsheets\Roadway\_G\029\_Rawy\_G\_Tie Beam Repairs.dgn




Place galvanic anodes around perimeter of the new tie beam at a maximum spacing of 1 foot at each column. Attach anodes to existing steel.

**ELEVATION**  
(Pier G12)




Adjust seismic brace such that the center of the clevis is along this dashed line. Field drill hole to match.


**TYPICAL STIFFENER DETAIL**



**SECTION B-B**



**SECTION A-A**



Note:  
All nuts shall be AASHTO M291 Grade DH.  
All rods shall be ASTM A1554 Grade 55.  
Existing Tie Beam reinforcement will be preserved. See project specification for details.  
Concrete strength for the tie beam concrete shall be  $f'_c=4000$ psi, but otherwise conform to the provisions of Section 503 of the standard specifications.

**BILL OF MATERIAL**

Bar	No.	Size	Length	Shape
s1(E)	33	#4	7'-11"	□
s2(E)	56	#5	8'-2"	□
Galvanic Anode			Each	34
Concrete Removal			Cu. Yds.	7
Reinforcement Bars, Epoxy Coated			Lbs.	660
Concrete Structures			Cu. Yds.	7
Remove and Replace Seismic Retrofit Assembly			Each	2

**WJE** ENGINEERS ARCHITECTS MATERIAL SCIENTISTS  
Wiss, Janney, Elstner Associates, Inc.  
330 Pingsten Road  
Northbrook, Illinois 60062  
847.272.7400 tel | 847.291.9595 fax

USER NAME = acb	DESIGNED - ARB	REVISED -
PLOT SCALE = 0.1667' / 1"	CHECKED - RW	REVISED -
PLOT DATE = 10/11/2018	DRAWN - ACB	REVISED -
	DATE - 09/28/2018	REVISED -


**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**TIE BEAM REPAIRS**  
**S.N. 082-0254**


SHEET NO. 29 OF 43 SHEETS

F.A.I. RT.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	224
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				

PRINT DATE: 9/28/2018 11:31:55 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Roadway\_G\030\_Rdwy\_G\_Concrete\_Repair\_Details.dgn




**VERTICAL SURFACE REPAIR DETAIL**  
At Substructure




**SECTION A-A**


Anodes shall be installed around the perimeter of the patch. No more than 2" from the edge of the patch, anode shall be spaced at 12" on center max. on all crashwall faces and the top and bottom faces of the tie beams. Anodes shall be spaced at 16" on center max. on column faces and vertical faces of the tie beams. No anodes specified in deck slab repairs.



**HORIZONTAL SURFACE REPAIR (PARTIAL DEPTH)**  
At bridge deck and substructure.




**RE-ENTRANT CORNER MODIFICATIONS**




**HORIZONTAL SURFACE REPAIR (FULL DEPTH)**  
At bridge deck

Note:  
Where construction joints occur within patches due to staging requirements, concrete removal shall extend 1 inch into previously repaired regions such that all existing steel is cleaned and coated. See Roadway Plans for traffic control staging requirements.



**TYPICAL CONCRETE REPAIR GEOMETRY**




**COLUMN REPAIR AT DETERIORATED TIE**

Notes:  
Patch shall extend 4" past tie deterioration or to the extents of unsound concrete, whichever is greater.  
The standing leg of the 90 degree bent bars will be installed 1" to 3" from the edge of the patch.  
Stagger #3 pins 3" vertically (alternate sides of deteriorated existing tie)


USER NAME = acb	DESIGNED - ARB/SMG	REVISED -
	CHECKED - RW	REVISED -
PLOT SCALE = 0.1667' / 1"	DRAWN - ACB	REVISED -
PLOT DATE = 9/28/2018	DATE - 09/28/2018	REVISED -

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	225
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				

PRINT DATE: 9/28/2018 11:31:56 AM Z:\5052 Poplar Street Complex\DCN\Bridg\Final\Plotsheets\Roadway G\03\_Rdwy\_G\_Cable Tensioned Strands.dgn



PLAN








ELEVATION

USER NAME = acb	DESIGNED - ARB	REVISED -
	CHECKED - RW	REVISED -
PLOT SCALE = 0.1667' / 1" =	DRAWN - ACB	REVISED -
PLOT DATE = 9/28/2018	DATE - 09/28/2018	REVISED -

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	226
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				



PRINT DATE: 9/28/2018 9:21:49 AM Z:\5052 Poplar Street Complex\DCN\Bridg\Final\Plotsheets\Sign Truss - Transystems\Bridg\0820254-76945-002-05A2.dgn



- ① Contractor may alternatively use standard aluminum drive-fit cap to close end. 1/2" Ø drain hole in end plate/drive-fit cap. (Typ. at ends of all chords)
- ② 5 1/2" end dimension may vary by ±1" to provide uniform panel spacing (P).
- ③ Panel spacing (P) shall be uniform for entire truss and between 4'-0" and 5'-0" for Type I-A.
- ④ Vertical Diagonals in front and back face shall alternate.
- ⑤ Hidden lines show wind bracing alternates direction between planes of top and bottom chords.
- ⑥ All diagonals shall be detailed for minimum offset from the panel point based on the following: Offset shall be such as to provide a 3/4" minimum to 1 1/2" maximum clearance between any diagonal and any horizontal or vertical member, and to provide clearance for U-bolt connections of signs or walkway brackets.

05-A-2

2-17-2017



USER NAME = acb	DESIGNED - FAS	REVISED -
PLOT SCALE = 0:2.0000 '1' / in.	CHECKED - JPC	REVISED -
PLOT DATE = 9/28/2018	DRAWN - MJR	REVISED -
	DATE - 9/28/2018	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


**OVERHEAD SIGN STRUCTURES - ALUMINUM TRUSS  
DETAILS FOR TRUSS TYPE I-A**

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55/64	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	228
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				


SHEET NO. 33 OF 43 SHEETS

**TRUSS UNIT TABLE**


Structure Number	Station	Design Truss Type	Exterior Units (2)			Interior Unit				Upper & Lower Chord		Verticals; Horizontal; Vertical, Horizontal, and Interior Diagonals		Camber at Midspan	Splicing Flange					
			No. Panels per Unit	Unit Lgth.(Le)	Panel Lgth.(P)	No. Req'd.	No. Panels per Unit	Unit Lgth.(Li)	Panel Lgth.(P)	O.D.	Wall	O.D.	Wall		Bolts		Weld Sizes		A	B
															No./Splice	Dia.	W	WI		
8S0821055R001.2	77+68	I-A	5	26'-3"	4'-10½"	---	---	---	---	5	⅝	2½	⅝	¾	6	⅞	⅝	¼	8¾	11¾
8S0821055R001.3	87+35	I-A	7	33'-1"	4'-5½"	---	---	---	---	5	⅝	2½	⅝	1½	6	⅞	⅝	¼	8¾	11¾



① Splicing Flanges shall be attached to each truss unit with the truss shop assembled to camber shown. Truss units shall be in proper alignment and flange surfaces shall be shop bolted into full contact before welding. Sufficient external welds or tacks shall be made to secure flanges until remaining welds are made after disassembly. Adjacent flanges shall be "match marked" to insure proper field assembly.




Note:  
Units shall be shipped individually with adequate provision to prevent detrimental motion during transport. This may require ropes between horizontals and diagonals or energy dissipating (elastic) ties to the vehicle. The Contractor is responsible for maintaining the configuration and protection of the units.




Camber curve shown is theoretical. Actual camber attained by slope changes at splices between units.


**CAMBER ATTAINMENT EXAMPLES:**



Camber shown is for fabrication only, measured with truss fully supported. (No-load condition)



**TRUSS TYPES I-A, II-A, & III-A**



**TRUSS TYPES II-A & III-A**  
**SPLICING FLANGES**

ASTM B221, Alloy 6061-T6  
or ASTM B209, Alloy 6061-T651  
\*To fit O.D. of Chord with maximum gap of 1/16".

054-A-2

2-17-2017



USER NAME = acb	DESIGNED - FAS	REVISED -
CHECKED - JPC	REVISED -	
PLOT SCALE = 0:2.0000 '1' / in.	DRAWN - MJR	REVISED -
PLOT DATE = 9/28/2018	DATE - 9/28/2018	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**OVERHEAD SIGN STRUCTURES - ALUMINUM TRUSS DETAILS**  
**FOR TRUSS TYPE I-A**

SHEET NO. 34 OF 43 SHEETS


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55/64	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	229
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				

PRINT DATE: 9/28/2018 9:21:49 AM Z:\5052 Poplar Street Complex\DCN\Bridg\Final\Plotsheets\Sign Truss - Transystems\Ramp\_G.dgn\0820254-76945-003-054A2.dgn




PRINT DATE: 9/28/2018 9:21:51AM Z:\5052 Poplar Street Complex\DCN\Bridge\Final\Plotsheets\Sign Truss - Transystems\Ramp\_C.dgn\0820254-76945-005-05A4.dgn

$\frac{3}{4}$ "  $\emptyset$  stainless steel U-bolt.  
 Provide two washers and two hexagon locknuts. (4)  
 $1\frac{3}{16}$ " x 2" slots on  $\emptyset$  10"  $\emptyset$  pipe.  
 (4 slots required per pipe)




**DETAIL A**




**SECTION A-A**


As an alternate to bolts, may use galvanized drive-fit caps installed after galvanizing frame.




**SECTION B-B**




**SIDE ELEVATION**



**HANDHOLE COVERS**



**DETAIL D**



**END ELEVATION**

Support Design Loads: See Sheet 32 of 43 for design and loading criteria.  
 Load combinations checked include deadload plus:  
 a) 100% wind normal to sign, 20% parallel to sign  
 b) 60% wind normal to sign, 30% parallel to sign

- ① In lieu of fabricated handhole frame as shown, may cut from 2" plate (rolling direction vertical). All cut faces to be ground to ANSI Roughness of 500µ in or less.
- ② Galvanizing vent holes of adequate size shall be provided on underside at each end of bracing pipes. Alternately, holes may be provided in wall of pipe column. All vent holes shall be drilled and de-burred, typ.
- ③ Steel pipe, plate, carbon steel handhole covers and rolled sections shall be hot dip galvanized after fabrication. Painting is not permitted. See Base Sheet 05-A-1.
- ④ See General Notes for fasteners.
- ⑤ Dimensions shown are based on selection criteria in the Sign Structures Manual. Nonstandard applications must have dimensions verified or amended as appropriate.
- ⑥ "H" based on 15'-0" or actual sign height, whichever is greater.

**10"  $\emptyset$  PIPE TRUSS SUPPORT FRAME**

\*\* One butt welded joint is allowed only on one post per support frame. If used, weld procedure must be pre-approved by Engineer and joint shall receive 100% RT or UT (tension criteria) at Contractor's expense.

Structure Number	Station	Support		H ⑥	A
		Left	Right		
8S0821055R001.2	77+68	X		32.45	25.87
8S0821055R001.2	77+68		X	29.04	22.46
8S0821055R001.3	87+35	X		30.74	24.16
8S0821055R001.3	87+35		X	29.04	22.46




USER NAME = acb	DESIGNED - FAS	REVISED -
PLOT SCALE = 0:2.0000 '1' / in.	CHECKED - JPC	REVISED -
PLOT DATE = 9/28/2018	DRAWN - MJR	REVISED -
	DATE - 9/28/2018	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**OVERHEAD SIGN STRUCTURES**  
**SUPPORT FRAME FOR TYPE I-A ALUMINUM TRUSS**


F.A.I. RTE. 55/64	SECTION 82-3HVB-2R-(2,1)-1-2	COUNTY ST. CLAIR	TOTAL SHEETS 238	SHEET NO. 231
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				

PRINT DATE: 9/28/2018 9:21:52 AM Z:\5052 Poplar Street Complex\DCN\Bridg\Final\Plotsheets\Sign Truss - Transystems\Ramp\_C dgns\0820254-76945-006-05A4A.dgn




**DETAIL B**

Ribs shall be cut to fit slope of pipe.




**SECTION D-D**



**SADDLE SHIM DETAIL**

ASTM B26 Alloy 356-F  
or  
ASTM B209 Alloy 6061-T651  
(4 required per sign truss)


Truss Chord Nominal Dia.	a
5"	3/4"
5 1/2"	1 3/16"
6"	7/8"
6 1/2"	1 5/16"




**ANCHOR ROD DETAIL**

Anchor Rods shall conform to ASTM F1554 and shall be fully galvanized per AASHTO M232. No welding shall be permitted on rods.

Note:  
Anchor Rods are included in the cost of Overhead Sign Structure - Span, Type I-A (4'-0"x4'-6")



**SECTION B-B**



**SECTION C-C**

(Handhole cover not shown)

**DETAIL C**

**TYPE I-A TRUSS  
10" Ø PIPE SUPPORT FRAME DETAILS**



USER NAME = acb	DESIGNED - FAS	REVISED -
PLOT SCALE = 0:2.0000 '1' / in.	CHECKED - JPC	REVISED -
PLOT DATE = 9/28/2018	DRAWN - MJR	REVISED -
	DATE - 9/28/2018	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


**OVERHEAD SIGN STRUCTURES  
SUPPORT FRAME DETAILS - ALUMINUM TRUSS**

SHEET NO. 37 OF 43 SHEETS


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55/64	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	232
CONTRACT NO. 76945				

ILLINOIS FED. AID PROJECT

PRINT DATE: 9/28/2018 9:21:52 AM Z:\5052 Poplar Street Complex\DCN\Bridge\Final\Plotsheets\Sign Truss - Transystems\Ramp\_C\_dgns\0820254-76945-007-05A9.dgn



**TYPICAL FRONT ELEVATION**  
 With lights and handrail omitted for clarity.  
 For Section B-B, see Base Sheet 05-A-10.



**PLAN WALKWAY AND HANDRAIL SKETCH**  
 (Road plan beneath truss varies)

**BRACKET TABLE**

WF(A-N)4x1.79 or WF(A-N)4x3.06 ASTM B308, Alloy 6061-T6		
Sign Width		Number Brackets Required
Greater Than	Less Than or Equal To	
	8'-0"	2
8'-0"	14'-0"	3
14'-0"	20'-0"	4
20'-0"	26'-0"	5
26'-0"	32'-0"	6


Notes:  
 \* Space walkway brackets WF(A-N)4x3.06 and sign brackets WF(A-N)4x1.79 for efficiency and within limits shown:  
 $f = 12"$  maximum,  $4"$  minimum (End of sign to  $\phi$  of nearest bracket)  
 $g = 12"$  maximum,  $4"$  minimum (End of walkway grating to  $\phi$  of nearest support bracket)  
 $h = 6'-0"$  maximum ( $\phi$  to  $\phi$  sign and/or walkway support brackets, WF(A-N)4x1.79 or WF(A-N)4x3.06)  
 $k = 2"$  maximum gap between adjacent walkway grating sections and handrail ends

\*\* If walkway bracket at safety chain location is behind sign, add angle to bracket, see Alternate Safety Chain Attachment on Sheet 37 of 38.

For Details T and W, Section B-B and Grating Splice Details see Sheet 36 of 38.

For Handrail Details see Sheet 37 of 38.

\*\* Alternate angle for safety chain attachment  
 Standard Aluminum Grating, see Details T and W



**SECTION A-A**

Handrail and walkway shall span a minimum of three brackets between splices and/or gap joints. Place all sign and walkway brackets as close to panel points as practical. Handrail joints, grating, and light support splices placed as needed.

Structure Number	Station	a	b	c	d	e	Walkway Grating and Handrail Lengths
8S0821055R001.2	77+68	6'-6"	43'-6"	0'-11 1/2"	---	---	43'-6"
8S0821055R001.3	87+35	0'-6"	64'-0"	0'-9"	---	---	64'-0"

Truss grating to facilitate inspection shall run full length (center to center of support frames)  $\pm 12"$  on overhead trusses. Cost of truss grating is included in "Overhead Sign Structure".

Walkway and Truss Grating width dimensions are nominal and may vary  $\pm 1/2"$  based on available standard widths.

05-A-9

2-17-2017



USER NAME = acb	DESIGNED - FAS	REVISED -
PLOT SCALE = 0:2.0000 '1' / in.	CHECKED - JPC	REVISED -
PLOT DATE = 9/28/2018	DRAWN - MJR	REVISED -
	DATE - 9/28/2018	REVISED -







**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**OVERHEAD SIGN STRUCTURES  
 ALUMINUM WALKWAY DETAILS**



SHEET NO. 38 OF 43 SHEETS

F.A.I. RTE. 55/64	SECTION 82-3HVB-2R-(2,1)-1-2	COUNTY ST. CLAIR	TOTAL SHEETS 238	SHEET NO. 233
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				

PRINT DATE: 9/28/2018 9:21:53 AM Z:\5052 Poplar Street Complex\DN\Bridg\Final\Plotsheets\Sign Truss - Transystems\Ramp\_C.dgn:0820254-76945-008-0SA10.dgn



**DETAIL T'**  
(Truss grating splice)  
Details not shown same as Detail T.  
Alternate materials may be used subject to the Engineer's review and approval.



**SPECIFICATIONS FOR STANDARD ALUMINUM GRATING**

Main Bearing Bars shall be 3/16" x 1 1/2" on 1 3/16" centers and conform to ASTM B221 Alloy 6061-T6.  
Cross bars shall be 3/16" x 1 1/2" on 4" centers and conform to ASTM B221 Alloy 6063-T5 or 6061-T6.  
**OR**  
Aluminum Grating with modified "t" sections for main bearing bars shall meet the following requirements:  
Main bars shall conform to ASTM B221 Alloy 6061-T6 and have a minimum section modulus equal to 0.0705 in.<sup>3</sup> per bar, a depth of 1 1/2", spaced on 1 3/16" centers.  
Cross bars shall conform to ASTM B221 Alloy 6063-T5 or T-42 and spaced on 4" centers.

Structure Number	Station	A	⑥ B	C	⑥ D
8S0821055R001.2	77+68	6"	6'-6"	4'-6"	11'-6"
8S0821055R001.3	87+35	6"	6'-6"	4'-6"	11'-6"

- ① Drilling holes in grating may be done in shop or field, based on Contractor's preference and subject to accurate alignment.
- ② Stainless steel shims shall be placed as shown in Detail T if needed to compensate for alignment variations between horizontal and diagonal pipes beyond adjustment provided by angles. Thicker shims may be used subject to shims performing properly.
- ③ If Handrail Joint present, weld angle to WF(A-N)4 and 1/4" extension bars. (See Base Sheet OS-A-11.)
- ④ L 1/8" x 1/2" x 2" welded to handrail posts to protect locations that contact grating.
- ⑤ Tube to grating gap may vary from 0 to 1/2", max. to align walkway, allow for camber, etc.
- ⑥ Based on actual height of tallest sign given on OS-A-1.

05-A-10

2-17-2017



USER NAME = acb	DESIGNED - FAS	REVISED -
PLOT SCALE = 0:2.0000 '1' / in.	CHECKED - JPC	REVISED -
PLOT DATE = 9/28/2018	DRAWN - MJR	REVISED -
	DATE - 9/28/2018	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**OVERHEAD SIGN STRUCTURES  
ALUMINUM WALKWAY DETAILS**

SHEET NO. 39 OF 43 SHEETS

F.A.I. RTE. 55/64	SECTION 82-3HVB-2R-(2,1)-1-2	COUNTY ST. CLAIR	TOTAL SHEETS 238	SHEET NO. 234
CONTRACT NO. 76945				ILLINOIS FED. AID PROJECT







PRINT DATE: 9/28/2018 9:21:54 AM Z:\5052 Poplar Street Complex\Sign\PlotSheets\Sign Truss - Transystems\Ramp\_C\_dgns\0820254-76945-009-05All.dgn  
 05-A-11 2-17-2017



1 Install standard force-fit end caps or weld 1/8" end plates with 1/8" c.f.w. and grind smooth. (All rail ends)  
 Fittings-ASTM B26, Alloy 356-T7 or 1 1/2" Ø aluminum pipe

2 Horizontal handrail member shall be continuous thru fitting. Provide 7/16" Ø hole in fitting for 3/8" Ø bolt. Field drill 7/16" Ø hole in horizontal rail member. Provide locknut and two stainless steel washers for bolt. (Use 5/16" eyebolts in 7/16" Ø holes on top rail at ends only.)

HANDRAIL DETAILS  
 Handrail pipe shall be ASTM B241 or B429, Alloy 6063-T6 or Alloy 6061-T6.








LIGHTING FIXTURE MOUNTS (IF REQUIRED)  
 5 Field cut ends of light support channels shall be free of burrs or hazardous projections and coated with zinc-rich primer or equivalent.

ALTERNATE SAFETY CHAIN ATTACHMENT (With Sign Present)


SIDE ELEVATION

FRONT ELEVATION

ELEVATION AT HANDRAIL JOINT



3 3/16" Type 304L stainless steel chain, approximately 12 links per foot.  
 4 Extrusions may be used in lieu of the details shown, with approval of the Engineer.



USER NAME: acb	DESIGNED: FAS	REVISED:
CHECKED: JPC	REVISIONS:	
DRAWN: MJR	REVISIONS:	
DATE: 9/28/2018	REVISIONS:	

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION






OVERHEAD SIGN STRUCTURES  
 ALUMINUM HANDRAIL DETAILS

F.A.I. R.E. 55/64	SECTION 82-3HYB-2R-(2,1)-1-2	COUNTY ST. CLAIR	TOTAL SHEETS 238	SHEET NO. 235
CONTRACT NO. 76945				

SHEET NO. 40 OF 43 SHEETS

ILLINOIS FED. AID PROJECT

PRINT DATE: 9/28/2018 9:21:55 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Sign Truss - Transystems\Bridges\Sign Truss - Transystems\0820254-76945-010-DETAILS.dgn



\* Install 5 Each 3/4" Ø x 4" Stud Shear Connector along C/C of Beam.

SECTION B-B  
(Stud Shear Connectors not shown for clarity)

**BILL OF MATERIAL**

Bar	No.	Size	Length	Shape
b11(E)	40	#5	9'-3"	—
Reinforcement Bars, Epoxy Coated		Pound		390

**BILL OF MATERIAL**

ITEM	UNIT	TOTAL
Concrete Removal	Cu. Yd.	2.7
Concrete Superstructure	Cu. Yd.	2.7
Stud Shear Connectors	Each	40

Note:  
#5 rebar protruding from bridge deck to remain. Clean concrete from rebar.



USER NAME = acb	DESIGNED - FAS	REVISED -
PLOT SCALE = 0.1667' / 1"	CHECKED - JPC	REVISED -
PLOT DATE = 9/28/2018	DRAWN - MJR	REVISED -
	DATE - 9/28/2018	REVISED -


STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

OVERHEAD SIGN STRUCTURES  
SLAB REMOVAL/REPLACEMENT DETAILS

SHEET NO. 41 OF 43 SHEETS

F.A.I. RT#	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55/64	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	236
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				

PRINT DATE: 9/28/2018 9:21:56 AM Z:\5052 Poplar Street Complex\DCN\Bridg\Final\Plotsheets\Sign Truss - Transystems\Ramp\_C\_dgns\0820254-76945-01-SIGN.dgn




12.0" Radius, 2.0" Border, White on Green;  
 [SOUTH] E 2K; [WEST] E 2K;  
 [TO] E 2K;  
 [St Louis] E Mod 2K; Down Arrow 22.0" 270°; Down Arrow 22.0" 270°;  
 TYPE ZZ SHEETING

Table of letter and object lefts.

S	O	U	T	H	W	E	S	T
12.7	27.2	40.0	51.7	62.8	97.1	115.3	125.9	137.0
24.6	80.5	126.5	180.5	191.2	209.3			
S	t	L	o	u	i	s		
76.2	92.4	116.7	130.6	146.4	163.4	171.2		
41.0	185.0							

SE3




12.0" Radius, 2.0" Border, White on Green;  
 [SOUTH] E 2K; [WEST] E 2K;  
 [TO] E 2K;  
 [St Louis] E Mod 2K; Down Arrow 22.0" 270°; Down Arrow 22.0" 270°;  
 TYPE ZZ SHEETING

Table of letter and object lefts.

S	O	U	T	H	W	E	S	T
12.7	27.2	40.0	51.7	62.8	97.1	115.3	125.9	137.0
24.6	80.5	126.5	180.5	191.2	209.3			
S	t	L	o	u	i	s		
76.2	92.4	116.7	130.6	146.4	163.4	171.2		
41.0	185.0							

SE5




12.0" Radius, 2.0" Border, White on Green;  
 [EXIT] E Mod 2K 120% spacing; [1] E Mod 2K;  
 [SOUTH] E 2K;  
 [Cahokia] E Mod 2K;  
 Down Arrow 22.0" 270°;  
 TYPE ZZ SHEETING

Table of letter and object lefts.

E	X	I	T	1		
65.6	74.7	85.9	90.1	112.5		
S	O	U	T	H		
12.0	26.5	39.3	51.1	62.1		
24.0	84.0					
C	a	h	o	k	i	a
16.7	32.7	49.7	65.2	81.0	96.6	104.7
50.0						

SE4




12.0" Radius, 2.0" Border, White on Green;  
 [EXIT] E Mod 2K 120% spacing; [1] E Mod 2K; [B] E Mod 2K;  
 [13th St] E Mod 2K; Arrow 160 - 35.0° 40°;  
 [Tudor Ave] E Mod 2K;  
 TYPE ZZ SHEETING

Table of letter and object lefts.

E	X	I	T	1	B		
75.5	84.6	95.8	99.9	122.3	134.9		
1	3	t	h	S	t		
16.8	24.7	40.7	54.1	80.7	96.8		
15.6	31.2	46.8	62.3	78.1	102.1		
T	u	d	o	r	A	v	e
15.6	31.2	46.8	62.3	78.1	102.1	120.4	135.9

SE7



12.0" Radius, 2.0" Border, White on Green;  
 [EXIT] E Mod 2K 120% spacing; [1] E Mod 2K;  
 [SOUTH] E 2K;  
 [Cahokia] E Mod 2K;  
 [1/8 MILE] E 2K;  
 TYPE ZZ SHEETING

Table of letter and object lefts.

E	X	I	T	1		
65.5	74.7	85.9	90.1	112.5		
S	O	U	T	H		
12.0	26.5	39.3	51.1	62.1		
24.0	84.0					
C	a	h	o	k	i	a
16.7	32.7	49.7	65.2	81.0	96.6	104.7
1/8	M	I	L	E		
32.2	60.1	74.5	79.8	90.8		

SE6



USER NAME = acb	DESIGNED - FAS	REVISED -
PLOT SCALE = 0:2.0000' = 1" / in.	CHECKED - JPC	REVISED -
PLOT DATE = 9/28/2018	DRAWN - MJR	REVISED -
	DATE - 9/28/2018	REVISED -


STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

OVERHEAD SIGN STRUCTURES  
 SPECIAL SIGN DETAILS


SHEET NO. 42 OF 43 SHEETS

F.A.I. RTE. 55/64	SECTION 82-3HVB-2R-(2,1)-1-2	COUNTY ST. CLAIR	TOTAL SHEETS 238	SHEET NO. 237
CONTRACT NO. 76945			ILLINOIS FED. AID PROJECT	

PRINT DATE: 9/28/2018 9:22:09 AM Z:\5052 Poplar Street Complex\DCN\Bridges\Final\Plotsheets\Sign Truss - Transystems\Ramp G.dgn 0820254-76945-02-LOC1.dgn



**ELEVATION - G3**  
 (Looking at Face of Signs)  
 (Station 77+68)



**ELEVATION - G13**  
 (Looking at Face of Signs)  
 (Station 87+35)



USER NAME = acb	DESIGNED - FAS	REVISED -
	CHECKED - JPC	REVISED -
PLOT SCALE = 0:2.0000 '1' / in.	DRAWN - MJR	REVISED -
PLOT DATE = 9/28/2018	DATE - 9/28/2018	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**OVERHEAD SIGN STRUCTURES  
 LOCATION OF SIGNS ON OVERHEAD TRUSS**

SHEET NO. 43 OF 43 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55/64	82-3HVB-2R-(2,1)-1-2	ST. CLAIR	238	238
CONTRACT NO. 76945				
ILLINOIS FED. AID PROJECT				