

FIELD TILE REPLACEMENT




DETAIL A NO SCALE

- *IF A 4" COVER CAN NOT BE PROVIDED A PAVED DITCH SHALL BE CONSTRUCTED AS SHOWN IN DETAIL C.
- NOTES


 1. WIDTH OF CONCRETE SLAB SHALL BE THE SAME
 AS THE TRENCH WIDTH IN ACCORDANCE WITH
 SECTION 550 OF THE STD. SPECIFICATIONS, OR 3' MIN.
- 2. CONCRETE FOR SLAB, HEADWALL AND PAVED DITCH SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER CUBIC YARD FOR MISCELLANEOUS CONCRETE."
- 3. COST OF FURNISHING AND INSTALLING WIRE MESH SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER CUBIC YARD FOR MISCELLANEOUS CONCRETE. WIRE MESH TO WEIGH NOT LESS THAN 58* PER 100 SQ. FT.



DETAIL C NO SCALE




SECTION B-B



FIELD TILE RELOCATION PLAN

NOTE: THE QUANTITIES PROVIDED FOR THE FIELD DRAIN RELOCATION ARE ESTIMATED. THE PROPOSED GRADES AND ACTUAL QUANTITIES WILL BE DETERMINED BY THE ENGINEER ONCE THE FIELD TILE NEAR THE RIGHT-OF-WAY LINE IS LOCATED USING EXPLORATORY TRENCHES. THE FIELD TILE JUNCTION VAULTS SHALL BE LOCATED WITH RIGHT-OF-WAY



FIELD TILE JUNCTION VAULT

FED. ROAD DIST. NO.	ILLINOIS FED. AID	PROJECT
TERNATE MATERIALS FOR WALLS		Ττ
ECAST DEINEADCED CONCDETE DISE	-DC	1,,,

SECTION 115 BR

COUNTY TOTAL SHEET NO.

LIVINGSTON 32 27

TO STA.


ALTERNATE MATERIALS FOR WALLS	Т
PRECAST REINFORCED CONCRETE RISERS	
CONCRETE MASONRY UNIT	5"
MONOLITHIC CONCRETE	6"
BUILDING BRICK, GRADE SW FROM CLAY OR SHALE	8"
CONCRETE BUILDING BRICK, GRADE A	8"

F.A.P. RTE. 681


STA.

NOTES

- 1. THE CONTRACT UNIT PRICE FOR FIELD TILE JUNCTION VAULT SHALL INCLUDE THE COST OF FURNISHING AND PLACING THE FRAME AND GRATE OR PRECAST CONCRETE LID AND WHEN REQUIRED, THE SAND CUSHION.
- 2. ALL FIELD TILE JUNCTION VAULTS SHALL BE 2'-0" IN DIAMETER UNLESS OTHERWISE NOTED ON THE PLANS.



± 145#



SECTION A-A

REVISIONS AME	DATE	ILLINOIS DEPARTMENT OF TRANSPORTATION
		FIELD TILE REPLACEMENT
		FAP ROLLTE 681

FAP ROUTE 681 SECTION 115 BR LIVINGSTON COUNTY

DATE NAME SCALE NAME