CONTRACT NO. 70232

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
721	(113BR)BR	DEWITT	81	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

GENERAL NOTES

SHEET 2 OF 2

G. N. - 781

RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED IN ACCORDANCE WITH STANDARD 781001, AND THE DETAILS SHOWN IN THE PLANS. IF THERE IS ANY DISCREPANCY BETWEEN THE STANDARD AND THE DETAILS IN THE PLANS, THE DETAILS IN THE PLANS SHALL GOVERN. THE FINAL PAVEMENT MARKINGS SHALL BE IN PLACE PRIOR TO PLACING THE RAISED REFLECTIVE PAVEMENT MARKERS AND THE RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED MIDWAY IN THE 30 FOOT (9 m) SPACE BETWEEN THE DASHED CENTERLINE STRIPES (WHEN APPLICABLE).

606 (SPECIAL) -

ANY SUBGRADE MATERIAL REQUIRED TO BRING THE CONCRETE CURB AND GUTTER AT THE ENTRANCE AT STATION 240+92 OR THE CONCRETE GUTTER, TYPE B TO THE PROPER ELEVATION SHALL BE INCLUDED IN THE COST FOR COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 AND CONCRETE GUTTER, TYPE B.

G. N. - 1004.01

COARSE AGGREGATE GRADATION CA-10 MAY BE USED WHENEVER COARSE AGGREGATE CA-6 IS SPECIFIED IN THE STANDARD SPECIFICATIONS.

G. N. - Z0038

AN ALUMINUM TABLET OF THE TYPE SHOWN ON STANDARD 667101 SHALL BE PLACED ON THE PROPOSED STRUCTURE AS DIRECTED BY THE ENGINEER. THE BENCH MARK ELEVATION WILL BE ESTABLISHED AND MARKED BY THE DEPARTMENT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR PERMANENT BENCH MARKS.

COMMITMENTS:

1. PARCEL NO. 5316006 - (11-17-2006) AS A RESULT OF R. O. W. NEGOTIATIONS THE CONTRACTOR IS TO CONTACT MR. KEN LANE AT (217)871-5179 IF THERE IS ANY EXTRA CONCRETE OR ASPHALT TO DISPOSE.

2. CONTACT STATION 1 AT THE CENTRAL OFFICE IN SPRINGFIELD AND THE DISTRICT COMMUNICATIONS OFFICE IN PARIS THREE TO FOUR WEEKS PRIOR TO THE BEGINNING OF CONSTRUCTION. STATION 1 IS THE CONTACT FOR THE ILLINOIS EMERGENCY MANAGEMENT AGENCY (I. E. M. A.) AND ANY CONTENGENCY EVACUATION PLANS INVOLVING THE CLINTON POWER PLANT.

3. PARCEL NO. 5316002 - (11-17-2006) PLEASE DO NOT DISTURB THE EXISTING FIREWOOD PILE LOCATED IN THE TEMPORARY EASEMENT.

4. CONTACT MR. MICHAEL MARTIN, SITE ASSISTANT SUPERINTENDENT FOR THE CLINTON LAKE STATE RECREATION AREA AT RR1, BOX 4, DEWITT, IL 61735, (217)935-8722; FOR THE EXACT LOCATION OF THE INFORMATIONAL SIGN TO BE ERECTED ON COUNTY HIGHWAY 14 (DEWITT ROAD) NEAR THE MASCOUTIN AREA ENTRANCE.

ILLINOIS DEPARTMENT OF TRANSPORTATION
GENERAL NOTES
F.A.P. ROUTE 721 (IL 10)
SECTION (113BR)BR
DEWITT COUNTY
Sheet 2 of 2
SCALE: NOT TO SCALE — DRAWN BY: B.B.P.
DATE: 07/03/07 — CHECKED BY: R.M.N.

PLOT DATE = 7/3/2007
FILE NAME = c:\projects\d703002 (v8i)\70232-text.dgn
PLOT SCALE = 43.2355 ' / IN.
USER NAME = cadlerbw