F.A.P.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
34			_13_	2_
STA TO STA.				

CONTRACT NO. 72B28

FED. ROAD DIST. NO. | ILLINOIS FED. AID PROJECT

D-6 SHLDR RUMBLE STRIPS 2008

MENARD, SANGAMON COUNTY

GENERAL NOTES AND COMMENTS

- 1. ALL ENTRANCES CURRENTLY IN USE SHALL REMAIN ACCESSIBLE BOTH DURING AND AFTER CONSTRUCTION.
- 2. NO LANE CLOSURES WILL BE ALLOWED WITHOUT FLAGGER PROTECTION AND NO WORK OR LANE CLOSURES PRIOR TO 9: 00 AM.
- 3. SAW CUTS SHALL BE MADE AT ALL COMMERCIAL, RESIDENTIAL, AND FIELD ENTRANCES (WITHIN LIMITS OF SHOULDER WIDENING) THAT HAVE ASPHALT ENTRANCES.
- ALL AGGREGATE NEEDED FOR TEMP ACCESS IS INCLUDED IN SHOULDER WORK AND EXCAVATION ACROSS DRIVEWAYS IS INCIDENTAL.
- 5. NEW SHOULDERS WILL FOLLOW RADIUS AROUND ALL SIDEROAD QUADRANTS AS OUTLINED IN THE TYPICALS SECTION.
- 6. ALL ADVANCED CURVE WARNING SIGNS SHALL HAVE A SUPPLEMENTAL PLAQUE NAMING CROSSROAD (W16-8) WHERE APPROPRIATE.

 CONVENTIONAL SIZE SIGNS SHALL BE USED

 IF THERE IS AN INTERSECTION THEN THE ADVANCE CURVE SIGN SHALL DEPICT IT. (SEE DETAIL SHEET 12 & 13)
- 7. FIELD/RESIDENT ENGINEER WILL COORDINATE WITH OPERATION TO VERIFY NO PASSING ZONES.
- 8. HIDDEN ENTRANCE SIGNS SHALL BE PLACED AT APROX STA# 308+00 SB. 370+00 NB. 80+00 SB & 132+00 NB RE WILL ADJUST ACCORDING TO SIGHT DISTANCE.
- B. DELINEATORS WILL BE SPACED ACCORDING TO STANDARD 635001 AND PLACED ON THE FIRST CURVE SOUTH OF SALISBURY ON THE EAST SIDE AT APROX. STA* 325+00 (FIELD VERIFY).
- 10. ALL SIGN LOCATIONS WILL BE STAKED AND VERIFIED BY RESIDENT ENGINEER PRIOR TO INSTALLATION.
- 11. PAINT PAVEMENT MARKING LINE 5" WILL BE USED ON ALL AREAS OF NEW SHOULDER IF REQUIRED.
- 12. CENTERLINE RUMBLE STRIPE WILL BE USED FOR THE NO PASSING ZONES WITHIN THE TWO REVERSE CURVES AND USE POLUREA PAVEMENT MARKING LINE 5" (DOUBLE YELLOW).
- 13. ALL EXCAVATED MATERIAL FROM EXCAVATION & SHOULDER GRADING SHALL BE REMOVED AND DISPOSED OUTSIDE OF EXISTING R.O.W., ACCORDING TO ARTICLE 202.03
- 14. THERE SHALL BE NO LANE CLOSURES WITHIN THE LIMITS OF THIS PROJECT DURING THE ILLINOIS STATE FAIR AUGUST 10-19. 2007
- 15. SHOULDER DROP-OFF SIGNS (W21-1103) IF THERE IS MORE THAN 3 INCHES DROP OFF ARTICLE 701.07 INCLUDED IN PAY ITEM TRAFFIC CONTROL 701326

LIST OF STANDARDS

THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT

000001-04 701006-02 482001-01 701011-01 635001 701201-02 720001 701301-02 720001 701306-01 728001 701326-02 780001-01

MIXTURE USE:	SHOULDERS	INCIDENTAL SURFACE
PG:	PG 58-22	PG 64-22
DESIGN ACR VOIDS:	2.0% & N DESIGN = 30	4.0% @ N DESIGN = 50
MIXTURE COMPOSITON: (GRADATION MIXTURE)	ВАМ	IL 9.5 OR 12.5
FRICTION AGGREGATE:	N/A	MIX "C"

COMMITMENTS

THE FIELD/RESIDENT ENGINEER SHALL CONTACT STUDIES AND PLANS CONCERNING ANY MAJOR PLAN CHANGES TO MAKE SURE NO PREVIOUS COMMITMENTS (NOT LISTED) WERE MADE AFFECTING THE DESIGN, AND ALLOW AN IMPROVED DESIGN FOR FUTURE PROJECTS.

EXPERIMENTAL FEATURES - CENTERLINE RUMBLE STRIPS & SHOULDER RUMBLE STRIPS ON TWO-LANE RURAL HIGHWAY

PAP 34 (IL 27 97)
D-6 SHLDR Rumble STRIPS 2008
Menord / SAMBAROWN

Route

Section

County

DISTRICT SIX

EXAMINED Tuly 24 2007

OPERATIONS ENGINEER

PROGRAM IMPLEMENTATION ENGINEER

PROGRAM DEVELOPMENT ENGINEER

REVISIONS
NAME DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

FAP 34 (IL 97)
SECTION D-6 SHLDR
RUMBLE STRIPS 2008
MENARD, SANGAMON COUNTY

11

SCALE: VERT. HORIZ. DRAWN BY CHECKED BY