THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UNDERGROUND OR SURFACE UTILITIES EVEN THOUGH THEY MAY NOT BE SHOWN ON THE PLANS. ANY UTILITY THAT IS DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED OR REPLACED TO THE SATISFACTION OF THE ENGINEER, THE VILLAGE AND THE UTILITY OWNER.

BEFORE STARTING ANY EXCAVATING, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC. TELEPHONE. CABLE AND GAS FACILITIES AND THE VILLAGE OF OAKBROOK TERRACE PUBLIC WORKS DEPT. FOR FIELD LOCATIONS OF BURIED WATER AND STORM FACILITIES (48-HOUR ADVANCE NOTIFICATION IS REQUIRED).

STAKING

THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL SECTION OR SUBSECTION MONUMENTS OR PROPERTY OR REFERENCE MARKERS UNTIL THE VILLAGE. HIS AGENT OR AN AUTHORIZED SURVEYOR HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATIONS.

STORM SEWER

WHENEVER DURING CONSTRUCTION OPERATIONS ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF DRAINAGE STRUCTURES SUCH THAT THE NATURAL FLOW OF WATER IS OBSTRUCTED. IT SHALL BE REMOVED AT THE CLOSE OF EACH WORK ING DAY. AT THE CONCLUSION OF CONSTRUCTION OPERATIONS, ALL UTILITY STRUCTURES SHALL BE FREE FROM DIRT AND DEBRIS. THE WORK SPECIFIED ABOVE WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF TRAFFIC CONTROL AND PROTECTION.

WHEN EXISTING DRAINAGE FACILITIES ARE DISTURBED. THE CONTRICATION SHALL PROVIDE AND MAINTAIN TEMPORARY OUTLETS AND CONNECTIONS FOR ALL PRIVATE ON PUBLIC DRAINS, SEWERS OR CATCH BASINS. HE SHALL PROVIDE AND SEWERS OR CATCH BASINS. HE SHALL PROVIDE AND SEWERS OR CATCH BASINS. HE SHALL PROVIDE AND SEWERS AND ISCARRGE IS STORM WATER WHICH WILL BE RECEIVED BY THESE DRAINS AND SEWERS AND ISCARRGE THE SAME. HE SHALL PROVIDE AND MAINTAIN AN EFFICIENT PUMPING PLANT; F NECESSARY, AND A TEMPORARY OUTLET, AND BE PREPARED AT ALL TIMES TO DISPOSE OF THE WATER RECEIVED FROM THESE TEMPORARY CONNECTIONS UNTIL SUCH TIME AS THE PERMANENT CONNECTIONS WITH SEWERS ARE BUILT AND IN SERVICE. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE COST OF TRAFFIC CONTROL AND PROTECTION.

WATER MAIN

THE CONTRACTOR SHALL NOT OPEN OR SHUT ANY WATER VALVES OR FIRE HYDRANTS WITHOUT FRIOR AUTHORIZATION FROM THE VILLAGE PUBLIC WORKS DEPARTMENT. UNAUTHORIZED USE SHALL SUBJECT THE OFFENDER TO ARREST AND PROSECUTION.

MISCELLANEOUS

DIMENSIONS: IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO ORDERING MATERIALS AND BEGINNING CONSTRUCTION.

ALL SAWCUTTING SHALL BE INCIDENTAL TO REMOVAL ITEMS AND SHALL BE PERFORMED PRIOR TO BEGINNING REMOVAL. ANY ITEMS OF WORK REMOVED PRIOR TO SAWCUTTING WILL NOT BE MEASURED FOR PAYMENT.

RELOCATING EXISTING SIGNS: EXISTING SIGNS WHICH ARE IN CONFLICT WITH PROPOSED IMPROVEMENTS SHALL BE REMOVED AND REINSTALLED UPON COMPLETION OF CONFLICTING IMPROVEMENTS IN ACCORDANCE WITH THE ILLINOIS DEPARTMENT OF TRANSPORTATION "MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES" AND THE "STANDARD SPECIFICATIONS FOR TRAFFIC CONTROL ITEMS" SHALL BE INCLUDED IN THE COST OF TRAFFIC CONTROL AND PROTECTION.

POLLUTION CONTROL: THE CONTRACTOR WILL BE REQUIRED TO COMPLY WITH STATE REGULATIONS REGARDING AIR, WATER AND NOISE POLLUTION, CONSTRUCTION OPERATIONS SHALL BE CONFINED TO THE PERIOD BEGINNING AT 7:00 A.M. AND ENDING AT 6:00 P.M. WEEKDAYS, B:00A.M. TO 4:00P.M. SATURDAY, THE PERIOD SECIONING AT 7:00 A.M. AND ENDING AT 6:00 P.M. WEEKDAYS, BOORAM. TO 4:00 AND NO WORK SHALL BE PERFORMED ON SUNDAYS OR HOLIDAYS, PER VILLAGE ORDINANCE. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION OPERATIONS TO INSURE TRAFFIC MAINTENANCE, SURFACE DRAIMAGE, ETC. THROUGHOUT THE DURATION OF THE CONSTRUCTION PERIOD IN ACCORDANCE WITH THE REQUIREMENTS OF THE VILLAGE OF OAKBROOK TERRACE, AND ANY OTHER GOVERNING AGENCIES. AND ANY UTHER GOVERNING AGENCIES.
THE CONTRACTOR SHALL TAKE ALL NECESSARY SAFETY PRECAUTIONS TO PROTECT AND PROVIDE ACCESS TO ABUTTING PROPERTY, UTILITIES, PEDESTRIANS AND VEHICULAR TRAFFIC.
NO BURNING OR INCINERATION OF RUBBISH WILL BE PERMITTED ON SITE.

DO NOT SCALE DRAWINGS IF COORDINATES AND DIMENSIONS ARE GIVEN. THE PROPOSED GRADING ELEVATIONS SHOWN ON THE PLANS ARE FINISHED GRADE, ALLOW FOR THE THICKNESS OF TOPSOIL AS SHOWN.
THE CONTRACTOR IS ADVISED THAT MUD AND DEBRIS MUST NOT BE DEPOSITED ON THE ADJACENT ROADWAYS. ANY DIRT AND DEBRIS ACCUMULATED ON THE PAVEMENT SHALL BE CLEANED BY THE CONTRACTOR WITHIN FOUR (4) HOURS OF THE INCIDENT OR HE WILL BE BACK CHARGED AT THE RATE OF \$500.00 PER INCIDENT PLUS THE COST OF THE VILLAGE'S FORCES TO COMPLETE THE WORK.
THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO STREETS OR ROADWAYS AND ASSOCIATED STRUCTURES AND SHALL MAKE REPAIRS AS NECESSARY TO CORRECT DAMAGE AT HIS OWN EXPENSE THE GRADING AND CONSTRUCTION OF THE PROPOSED IMPROVEMENTS SHALL NOT CAUSE PONDING OF STORM WATER.

F.A RTE.	F.A. SECTION 03-00019-00-BR		COUNTY		TOTAL SHEETS	SHEET NO.
			DUPAGE		35	2
STA.	* *	TO STA.				
FED. RO	AD DIST. NO. 1	ILLING	IS FED.	AID	PROJECT	

CONTRACT NO. 83965

PROJECT UTILITY CONTACTS

COMMONWEALTH EDISON 2 LINCOLN CENTER OAKBROOK TERRACE, IL 60181 ATTN: TOM STUTZMAN TEL: 630-437-2236 SENT: 5/18/07 **COMMENTS: NO CONFLICTS ANTICIPATED**

COMCAST

688 INDUSTRIAL DRIVE ELMHURST, IL 60126 ATTN: MARY STEFAN TEL: 630-600-6346 SENT: 5/18/07 COMMENTS: NO CONFLICTS ANTICIPATED

NICOR GAS 1844 FERRY ROAD NAPERVILLE, IL 60563 ATTN: CONSTANCE LANE TEL: 630-983-8676 (Ext. 2362) SENT: 5/18/07 COMMENTS: NO CONFLICTS ANTICIPATED

AT&T (SBC) 1000 COMMERCE DRIVE FLOOR 2 OAK BROOK, IL 60523 ATTN: TOM FOLLIN SENT: 5/18/07 COMMENTS:

AT&T 301 WHALEY ST. ROOM 403 LONGVIEW TX 75601 ATTN: LLOYD MAGOWN SENT: 5/18/07 COMMENTS:

XO ILLINOIS, INC. 7001 FRONTAGE ROAD BURR RIDGE, IL 60527 ATTN: GLEN LUEHRSEN SENT: 5/18/07 COMMENTS:

HIGHWAY STANDARDS

000001-04	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
280001-03	TEMPORARY EROSION CONTROL SYSTEMS
630001-07	STEEL PLATE BEAM GUARDRAIL
701321-08	LANE CLOSURE, 2L, 2W, BRIDGE REPAIR WITH BARRIER
70150103	URBAN LANE CLOSURE, 2L, 2W UNDIVIDED
701701-04	URBAN LANE CLOSURE, MULTILANE INTERSECTION
702001-06	TRAFFIC CONTROL DEVICES
780001-01	TYPICAL PAVEMENT MARKINGS
631031-06	TRAFFIC BARRIER TERMINAL, TYPE L

REVISIONS ILLINOIS DEPARTMENT OF TRANSPORTATION **GENERAL NOTES** SCALE: N.T.S. DRAWN BY BEH DATE 8/24/2007 CHECKED BY LMF

G.